PURSUIT®



OWNER'S MANUAL

DC 365
DUAL CONSOLE

APRIL 2018

U.S. Patents

8,113,137

8,191,495

Other Patents Pending

SPECIFICATIONS

L.O.A. - - - - - - - - - - - - - - - - - - -37’ 11” (11,56 m)
Beam -12’ 0” (3,66 m)
Hull Draft
(motors up) - - - - - - - - - - - - - -2’ 2” (0,66 m)
(motors down) - - - - - - - - - - - -3’ 1” (0,94 m)
***Clearance w/ Hardtop**
(from waterline) - - - - - - - - - - -9’ 3” (2,81m)
Approx. Dry weight
(triple F300 engines) - - - - - - - -17,000 lbs. (7.711 kg)
**** Fuel Capacity - - - - - - - - - - -326 U.S. Gallons (1.234 L)**
Fresh Water Capacity - - - - - - -42 U.S. Gallons (159L)
Holding Tank Capacity - - - - - -22 U.S. Gallons (83,28 L)
Diesel Generator Tank - - - - - -23 U.S. Gallons (87 L)
Max. Horsepower - - - - - - - - - -900 hp (671 kW)
Deadrise - - - - - - - - - - - - - - -20 Degrees

* Hardtop clearance shown does not include options which could increase this height dimension.

**Net tank capacity. The usable fuel capacity will be affected by several factors, including EPA-required fuel system components, temperature and loading of the boat. These factors will reduce the usable fuel capacity by approximately 10%.

Safety Information

Your Owner's Manual was written to include safety instructions to ensure safe operation and maintenance of your boat. Safety alerts symbols are used to alert potential personal injury hazards.

⚠ DANGER

Indicates a hazardous situation which, if not avoided, will result in death or serious injury.

⚠ WARNING

Indicates a hazardous situation which, if not avoided, could result in death or serious injury.

⚠ CAUTION

Indicates a hazardous situation which, if not avoided, could result in minor or moderate injury.

NOTICE

Indicates a potentially hazardous situation which, if not avoided, may result in property damage.

All instructions are viewed from the stern looking toward the bow, with starboard (to your right) and port (to your left). A glossary of boating terms is included.

Your boat produces carbon monoxide (CO) and uses flammable fuel. CO will cause BRAIN DAMAGE or DEATH. Carbon monoxide gas (CO) is colorless, odorless and extremely dangerous.

Every precaution has been taken by Pursuit Fishing Boats to reduce the risks associated with death, possible injury and damage from fire or explosion. Your own precaution and good maintenance procedures are necessary in order to enjoy safe operation of your boat.

⚠ DANGER

Exposure to carbon monoxide will cause death or serious injury. Avoid direct and prolonged exposure to CO.

Gasoline and other fuels are extremely flammable and highly explosive under certain conditions.

- **DO NOT smoke or allow open flame or sparks nearby when fueling.**
- **DO NOT block fuel vents.**
- **DO NOT store fuel in any containers or compartments which are not designated for storing fuel.**

Operator Notes

Table of Contents

Safety Information

General Information DC 365 1
Engine and General Specifications 1
Boat Information 2
Warranty and Warranty Registration Cards 3
Federal Boat Safety Act 3
Product Changes 3
Transferring the Warranty 3
Owner/Operator Responsibilities 3

Propulsion Systems

1.1 General 1-1
1.2 Saltwater Application 1-1
1.3 Engine Lubrication 1-2
1.4 Engine Cooling System 1-2
1.5 Propellers 1-2
1.6 Engine Instrumentation 1-2

Helm Systems

2.1 General 2-1
2.2 Helm Access 2-1
2.3 Engine Throttle and Shift Controls 2-1
2.4 Neutral Safety Switch 2-2
2.5 Engine Power Tilt and Trim 2-2
2.6 Engine Stop Switch 2-2
2.7 Automatic Fire Extinguisher System . 2-3
2.8 Steering System 2-4
2.9 Optional Electronics 2-5
2.10 Trim Tabs 2-5
2.11 Compass 2-6
2.12 Bow Thruster 2-6
2.13 Spotlight (Optional) 2-7
2.14 Control Systems Maintenance 2-7

Fuel Systems

3.1 General 3-1
3.2 Fuel System 3-2
3.3 Diesel Generator Fuel System 3-3
3.4 Fueling Instructions 3-4

Electrical Systems

4.1 General 4-1
4.2 DC System 4-1
4.3 12-Volt DC Panels 4-5
4.4 AC System 4-7
4.5 AC Main Distribution 4-7
4.6 Battery Charger Operation 4-8
4.7 Shore Power Connection 4-9
4.8 Generator 4-10
4.9 Electrical System Maintenance 4-10

Plumbing System

5.1 Fresh Water System 5-1
5.2 Raw Water Washdown 5-2
5.3 Livewell 5-3
5.4 Drainage 5-3
5.5 Plumbing System Maintenance 5-5

Ventilation System

6.1 Cabin Ventilation 6-1
6.2 Windshield Ventilation 6-1
6.3 Carbon Monoxide and Proper Ventilation 6-1
6.4 Bilge Compartment Ventilation 6-1
6.5 Maintenance 6-1

Exterior Equipment

7.1 Deck 7-1
7.2 Cockpit 7-4

Table of Contents

Interior Equipment

8.1 Companionway Door 8-1
8.2 Mid-Berth 8-1
8.3 Head Compartment 8-1
8.4 Galley 8-2
8.5 Carbon Monoxide Detector 8-2
8.6 Air Conditioner 8-2
8.7 Audio and Video Systems 8-3

Safety Equipment

9.1 General 9-1
9.2 Engine Alarms 9-1
9.3 Neutral Safety Switch 9-1
9.4 Engine Stop Switch 9-1
9.5 Automatic Fire Extinguishing System 9-2
9.6 Carbon Monoxide Hazards 9-2
9.7 First Aid 9-4
9.8 Required Safety Equipment 9-5
9.9 Additional Safety Equipment 9-7

Operation

10.1 General 10-1
10.2 Homeland Security Restrictions 10-1
10.3 Rules of the Road 10-2
10.4 Pre-Cruise Check 10-4
10.5 Operating your Boat 10-5
10.6 Fishing 10-6
10.7 Docking, Anchoring and Mooring ... 10-6
10.8 Controls, Steering or Propulsion System Failure 10-8
10.9 Grounding, Towing and Rendering Assistance 10-9

Routine Maintenance

11.1 General 11-1
11.2 Exterior Hull and Deck 11-1
11.3 Seats, Upholstery, Canvas and Enclosures 11-5
11.4 Cabin Interior 11-6
11.5 Bilge 11-6
11.6 Generator (Optional) 11-7

Seasonal Maintenance


12.1 Storage and Lay-up 12-1
12.2 Winterizing 12-2
12.3 Recommissioning 12-4

APPENDICES

Glossary of Terms A-1
Maintenence Schedule B-1
Maintenance Log B-2
Boating Accident Report C-1
Float Plan D-1
Troubleshooting Guide E-1
Schematics E-1
Fresh Water System G-1
Acuatic Invasive Species H-1





Label Locations

DC 365 - Warning Label Diagram



Labels and Logos




Not All Labels and Logos May Apply

1	**LOGO: "P" 12V LED, LIGHTED** **P/N: 5346801**	
2	**LABEL, CAUTION - HOT WATER HEATER** **P/N: 5430190**	
3	**LABEL, WASHDOWN/BAITWELL PICKUP** **P/N: 5435220**	
4	**LOGO: "P" SMALL PLATINUM** **P/N: 5437700**	
5	**LABEL, WARNING CO HATCH** **P/N: 5437750**	
6	**TAG, WARNING ETHANOL FUEL** **P/N: 5450041**	
7	**TAG, OVERBOARD DISCHARGE YELLOW** **P/N: 5450050**	
8	**LABEL, WARNING SUNSHADE STOWAGE** **P/N: 5450054**	

Label Locations



Labels and Logos

Not All Labels and Logos May Apply

9	**LABEL, NOTICE DASH PANEL CLEANING** **P/N: 5450055**	
10	**LABEL, FUEL SYSTEM WARNING MYLAR** **P/N: 5450060**	
11	**LABEL, BOATMAN'S CHECKLIST** **P/N: 5450120**	
12	**LABEL, "110 VOLTS" RED ON WHITE** **P/N: 5450170**	
13	**LABEL, "FRESH WATER"** **P/N: 5450260**	
14	**LABEL, "RAW WATER"** **P/N: 5450270**	
15	**LABEL, TRANSOM DOOR WARNING** **P/N: 5450550**	
16	**LABEL, BOARDING DOOR WARNING** **P/N: 5450551**	

Labels and Logos









Not All Labels and Logos May Apply

17	**LABEL, FISH BOX VALVE PORT** **P/N: 5450580**	
18	**LABEL, FISH BOX VALVE STBD** **P/N: 5450585**	
19	**PLATE, YACHT CERTIFICATION OVER 26' ALL** **P/N: 5450650**	
20	**LABEL, STORAGE AREA NOTICE MYLAR 3"X1-1/8** **P/N: 5450710**	
21	**LABEL, GELCOAT DAMAGE NOTICE MYLAR 3" LONG** **P/N: 5450720**	
22	**LABEL, "FORWARD" MECHANICAL HATCH** **P/N: 5450730**	
23	**TAG, LEXAN "GENERATOR PICKUP"** **P/N: 5450800**	
24	**TAG, LEXAN "HEAD OVERBOARD DISCHARGE"** **P/N: 5450805**	

Label Locations




Labels and Logos

Not All Labels and Logos May Apply

25	**TAG, LEXAN "AIR CONDITIONING PICKUP"** **P/N: 5450810**	
26	**TAG, LEXAN "WASHDOWN PICKUP"** **P/N: 5450815**	
27	**TAG, LEXAN "BAITWELL PICKUP"** **P/N: 5450820**	
28	**TAG, LEXAN "FUEL SYS ENG WITHDRAWL STBD"** **P/N: 5450825**	
29	**TAG, LEXAN "FUEL SYS ENG WITHDRAWL PORT"** **P/N: 5450830**	
30	**TAG, LEXAN "FUEL SYS GENERATOR WITHDRAWL"** **P/N: 5450835**	
31	**TAG, LEXAN "FUEL SYSTEM GENERATOR RETURN"** **P/N: 5450840**	
32	**TAG, LEXAN "TO DECK PUMPOUT"** **P/N: 5450845**	

Labels and Logos




Not All Labels and Logos May Apply

33	**TAG, LEXAN "FROM WASTE TANK"** **P/N: 5450850**	
34	**TAG, LEXAN, GREEN "WINTERIZED"** **P/N: 5450855**	
35	**LABEL, HAZARDOUS VOLTAGE (WRAP AROUND)** **P/N: 5451120**	
36	**LABEL, NO SMOKING** **P/N: 5451130**	
37	**LABEL, CAPACITY TOWER Y8** **P/N: 5451160**	
38	**LABEL, WARNING PROPELLER, SWIM PLATFORM** **P/N: 5451180**	
39	**LABEL, SWIM LADDER WARNING** **P/N: 5451750**	
40	**LABEL, MANUAL DOOR OVERRIDE "UP"** **P/N: 5451781**	

Label Locations







Labels and Logos

Not All Labels and Logos May Apply

41	**LABEL, "FIRE EXTINGUISHER INSIDE"** **P/N: 5452010**	
42	**LABEL, "ESCAPE HATCH" WHITE/CLEAR** **P/N: 5452020**	
43	**LABEL, WARNING "DO NOT RUN W/HELM OPEN"** **P/N: 5452510**	
44	**LABEL, WARNING HARDTOP** **P/N: 5453160**	
45	**TAG, WARNING CA CODE PROP 65** **P/N: 5453551**	
46	**LABEL, "SLING" PS POLYESTER** **P/N: 5453600**	
47	**LABEL, TRANSOM CO CALIFORNIA** **P/N: 5453650**	
48	**LABEL, WARNING CO CABIN** **P/N: 5453680**	

Labels and Logos



Not All Labels and Logos May Apply

49	**LABEL, WARNING CO HELM** **P/N: 5453690**	
50	**LABEL, "NO STEP" 3"X8" RED/WHITE** **P/N: 5453970**	
51	**LABEL, KIT FOR FUSE BLOCK** **P/N: 5454010**	
52	**PLATE, CAPACITY C 238 MY2016** **P/N: 5454215**	
53	**PLATE, CAPACITY DC 235 MY2017** **P/N: 5454216**	
54	**LABEL, "DISCHARGE OF OIL PROHIBITED"** **P/N: 5454490**	
55	**LABEL, "TRASH OVERBOARD DISCHARGE"** **P/N: 5454500**	
56	**LABEL, FILL W/DIESEL ONLY** **P/N: 5454580**	

Label Locations






Labels and Logos

Not All Labels and Logos May Apply

57	**LABEL, "NMMA" CERT SLVR/BLK 2IN CIRCLE** **P/N: 5455250**	
58	**LABEL, ENGINE FLUSHING SYSTEM** **P/N: 5455602**	
59	**LABEL, NOTICE CONSISTENT TEMPERATURE** **P/N: 5455650**	
60	**LABEL, NOTICE KEEP HATCHES CLOSED** **P/N: 5455660**	
61	**LABEL, WARNING HOT SURFACE - GRILL** **P/N: 5455680**	
62	**LABEL, WARNING V - BERTH TABLE** **P/N: 5455770**	
63	**LABEL, WARNING AFT FACING SEAT** **P/N: 5455780**	
64	**LABEL, WARNING "DO NOT DRILL"** **P/N: 5455830**	

Labels and Logos



Not All Labels and Logos May Apply

65	**LABEL, DANGER "DO NOT EXCEED 1000LB CAP"** **P/N: 5455840**	
66	**LABEL, WARNING SUNPAD FILLER** **P/N: 5455870**	
67	**LABEL, WARNING NO FLAMMABLE LIQUIDS** **P/N: 5455950**	
68	**LABEL, WARNING WINDLASS LEWMAR** **P/N: 5455960**	
69	**LABEL, NOTICE ANCH RODE LEWMAR** **P/N: 5455970**	
70	**LABEL, NOTICE BALL VALVE ACTUATOR** **P/N: 5456080**	
71	**LABEL, HOUSE BATTERY & BREAKER LOCATION** **P/N: 5456081**	
72	**LABEL, NOTICE WINDSHIELD CLEANING** **P/N: 5456090**	

Label Locations



Labels and Logos

Not All Labels and Logos May Apply

73	LABEL, CAUTION "SEAT ASSEMBLY" P/N: 5450215	
74	LABEL, WARNING "FALLING OVERBOARD" P/N: 5450062	
75	LABEL, "TOWER CAPACITY" P/N: 5453602	
76	LABEL, WARNING "FALLING OVERBOARD" P/N: 5454491	
77	LABEL, WARNING "FALLING FROM HARDTOP" P/N: 5453601	

Labels and Logos

Not All Labels and Logos May Apply

78	**LABEL, GYRO PICKUP** **P/N: 5450821**	
79	**LABEL, GYRO DISCHARGE** **P/N: 5450822**	
80	**LABEL, BATTERY TRAY** **P/N: 5456085**	
81	**LABEL, "AMERICAN MADE" 2.4" X 12"** **P/N: 5455601**	
82	**MODEL DESIGNATOR LABEL, "DC 365"** **P/N: 5456045**	

To obtain replacement labels, contact Pursuit Customer Relations at (772) 460-4626.

General Information

General Information DC 365

Engine and General Specifications

Maximum Horsepowe	900 HP	671 kW
L.O.A	37’ 11”	11,56 meters
Beam	12’ 0”	3,66 meters
Draft (fully loaded, motors up)	2’ 2”	0,66 meters
Draft (fully loaded, motors down)	3’ 1”	0,94 meters
Clearance with Hardtop (from waterline)	9’ 3”	2,81 meters
Average Dry weight	17,000 LBS	7.710 kg
Fuel Capacity	326 Gallons	1.234 liters
Generator Diesel Capacity	23 Gallons	87 liters
Water Capacity	42 Gallons	159 liters
Holding Tank Capacity	22 Gallons	83,28 liters
Deadrise at Transom	20 Degrees	

Boat Information

Fill out the following information and leave it in your PURSUIT Owner's Manual. This information will be important for you and PURSUIT service personnel to know, if and when you may need to call PURSUIT for technical assistance or service.

Boat	
Model:	**Hull Serial #:**
Purchase Date:	**Delivery Date:**
Ignition Keys #:	**Registration #:**
Draft:	**Weight:**
Engine(s)	
Make:	**Model:**
Port Serial #:	**Starboard Serial #:**
Transmission(s) (Inboard)	
Make:	**Model:**
Port Serial #:	**Starboard Serial #:**
Ratio:	
Outdrive(s) (Inboard/Outboard)	
Make:	**Model:**
Port Serial #:	**Starboard Serial #:**
Propeller(s)	
Make:	**Blades:**
Diameter/Pitch:	**Other:**
Generator	
Make:	**Model:**
Serial #:	**kW:**
Dealer	**Pursuit**
Name:	**Phone:**
Dealer/Phone:	**Representative:**
Salesman:	**Address:**
Service Manager:	
Address:	

PURSUIT Fishing Boats reserves the right to make changes and improvements in equipment, design and vendor supplied equipment at any time without notification.

Warranty and Warranty Registration Cards

The PURSUIT Limited Warranty Statement is included with your boat. It has been written to be clearly stated and easily understood. If you have any questions after reading the warranty, please contact PURSUIT Customer Relations.

PURSUIT, engine manufacturers, and the suppliers of major components maintain their own manufacturer's warranty and service facilities. It is important that you properly complete the warranty registration cards included with your boat and engine(s) and mail them back to the manufacturers to register your ownership. This should be done within 15 days of the date of purchase and before the boat is put into service. A form for recording this information is provided at the beginning of this manual. This information will be important for you and service personnel to know, if and when you may need service or technical information.

The boat warranty registration requires the **H**ull **I**dentification **N**umber **"HIN"** which is located on the starboard side of the transom, just below the rub rail. The engine warranty registration requires the engine serial number(s). Please refer to the engine owner's manual for the location of the serial number(s).

Federal Boat Safety Act

All boat manufacturers are required by the Federal Boat Safety Act of 1971 to notify first time owners in the event any defect is discovered "which creates a substantial risk of personal injury to the public." It is essential that we have your warranty registration card complete with your name and mailing address in our files so that we can comply with the law if it should become necessary.

Product Changes

PURSUIT is committed to the continuous improvement of our boats. As a result, some of the equipment described in this manual or pictured in the catalog may change or no longer be available.

PURSUIT reserves the right to change standard equipment, optional equipment and specifications without notice or obligation. If you have questions about the equipment on your PURSUIT, please contact PURSUIT Customer Relations.

Transferring the Warranty

Pursuit Boats will extend warranty coverage to subsequent owners of Pursuit models for the duration of the original warranty period. Please refer to the Pursuit Limited Warranty Statement for the procedure to transfer the warranty. To take advantage of this program, notification of the change of ownership, including the new owner's name, address and telephone number must be sent to Pursuit Boats, Customer Relations Department, 3901 St. Lucie Boulevard, Ft. Pierce, Florida 34946, within 30 days of resale.

Pursuit Boats will confirm, in writing, that the transfer of warranty has taken place. After which, the transferee will be treated as the original purchaser as outlined in the Pursuit Limited Warranty Statement.

Owner/Operator Responsibilities

Towing

Pursuit Boats offers a custom bow tow eye on certain models as an optional feature. If your boat is equipped with this optional feature the following operational guidelines must be followed to prevent damages or injury from occurring during towing operations:

Ensure that towing tackle is properly rated/ sized for the weight of your vessel.

Inspect the towing tackle prior to and at the end of every towing operation.

Prior to towing, close all seacocks which are designed to pick up raw water for air conditioning, generator, washdown pumps and live wells. Close all seacocks which are designed to discharge water through the hull bottom or hull sides for macerators, fish box pumps and deck drains. This will prevent flooding of mechanical spaces if a break in a

line were to occur. Since it is assumed the vessel will be unoccupied during towing operations this is a critical step prior to beginning the towing operation.

On boats equipped with a generator, the generator exhaust outlet must be sealed to prevent water filling exhaust and flooding generator engine block/cylinders. This can be accomplished by installing an expandable plug in the exhaust outlet. Note, after a towing operation is completed and prior to starting the generator, the exhaust outlet plug must be removed. Failure to remove the exhaust outlet plug can lead to damage to the generator, it's exhaust system and/or associated components.

Sea conditions will dictate the speed at which your boat can be safely towed. Be mindful of changing conditions and adjust towing speeds accordingly.

It is the owner's responsibility to ensure these guidelines are followed during all towing operations. Failure to follow the guidelines can possibly lead to damages or injury. Damages to equipment and/or the vessel which are deemed to be caused by failure to follow the guidelines can void any warranty coverage.

On models which do not offer an optional factory installed custom bow tow eye, owner will assume all responsibility for damages to the vessel and equipment which are deemed the result of installation and or use of the non-factory tow eye.

Registration and Documentation

Federal law requires all undocumented vessels equipped with propulsion machinery be registered in the state of principal use. A certificate of documentation will be issued upon registration. These registration numbers must be displayed on your boat. The owner/operator of a boat must carry a valid certificate of registration whenever the boat is in use. When moved to a new state of principal use, the certificate is valid for 60 days.

In order to be valid, the numbers must be installed to the proper specifications. Check with your dealer or state boating authority for numbering requirements. The Coast Guard issues the certificate of number in Alaska; all others are issued by the state.

Insurance

In most states the boat owner is legally responsible for damages or injuries the boat causes. Responsible boaters carry adequate liability and property damage insurance for their boat. You should also protect the boat against physical damage and theft. Some states have laws requiring minimum insurance coverage. Contact your dealer or state boating authority for information on the insurance requirements in your boating area.

Reporting Boating Accidents

All boating accidents must be reported by the owner or operator of the boat to the proper marine law enforcement authority for the state in which the accident occurred. Immediate notification is required if a person dies or disappears as a result of a recreational boating accident.

If a person dies or there are injuries requiring more than first aid, a formal report must be filed within 48 hours.

A formal report must be made within 10 days for accidents involving more than $500.00 damage or the complete loss of a boat.

A "Boating Accident Report" form is located near the back of this manual to assist you in reporting an accident. If you need additional information regarding accident reporting, please call the Boating Safety Hotline, 800-368-5647 or uscgboating.org.

Education

If you are not an experienced boater, we recommend the boat operator and other people that normally accompany the operator, enroll in a boating safety course. Organizations such as the U.S. Power Squadrons, United States Coast Guard Auxiliary, State Boating Authorities and the American Red Cross offer excellent boating educational programs. These courses are worthwhile even for experienced boaters to sharpen your skills or bring you up to date on current rules and regulations. They can also help in pro-

viding local navigational information when moving to a new boating area. Contact your dealer, State Boating Authority or the Boating Safety Hotline, 800-368-5647 or uscgboating.org for further information on boating safety courses.

Required Equipment

U.S. Coast Guard regulations require certain equipment on each boat. The Coast Guard also sets minimum safety standards for vessels and associated equipment. To meet these standards some of the equipment must be Coast Guard approved. “Coast Guard Approved Equipment” has been determined to be in compliance with USCG specifications and regulations relating to performance, construction or materials. The equipment requirements vary according to the length, type of boat, and the propulsion system. Some of the Coast Guard equipment is described in the Safety Equipment Section of this manual. For a more detailed description, obtain “Federal Requirements and Safety Tips for Recreational Boats” by contacting the Boating Safety Hotline 800-368-5647, uscgboating.org or your local marine dealer or retailer.

Some state and local agencies go beyond USCG regulations or impose similar equipment requirements on waters that do not fall under Coast Guard jurisdiction. Contact your dealer or local boating authority, they can provide you with additional information for the equipment requirements for that boating area.

EPA Compliant Fuel System

EPA (Environmental Protection Agency) regulations have required additional emissions related components for the fuel tank, fuel fill and fuel vent systems. It is unlawful to remove or intentionally defeat these emission related components.

Operator Notes

Propulsion Systems

1.1 General

Your Pursuit boat is designed to be powered with triple 4-cycle outboard engines.

Each manufacturer of the various outboard engines provides an owner's information manual which includes its limited warranty statement with its product. It is important you read and understand the information and become familiar with the warranty, operation and maintenance of the engines and drive systems.

NOTICE

DO NOT attempt to service any part of the outboard or boat systems unless you are familiar and qualified to do so. Do not use parts which are not designed for a marine application.

⚠ WARNING

MOVING PARTS HAZARD

Contact with moving parts can entangle, cut and cause death or serious injury. DO NOT get close enough to make contact with any running machinery moving parts, i.e., engine or propeller. Contact can result in loss of body parts, strangulation, burns and/or severe loss of blood resulting in death or serious injury.

NOTICE

Use only the fuel recommended by the engine manufacturer. Use of old, contaminated fuel can cause the engine to malfunction or severe damage.

1.2 Saltwater Application

Each outboard engine is a complete drive system with the gear case (transmission) forward of the propeller and connected to the power head with a vertical drive shaft. Other than the routine maintenance outlined in the engine owner's manual, there is little to be concerned with unless the boat is to be kept in saltwater for extended periods. Marine growth will occur when components are left in the water for extended periods and can cause poor performance or permanent damage to the exposed components. The type of growth and how quickly it occurs is relative to the water conditions in your boating area. Water temperature, pollution, current, etc. can have an effect on marine growth.

NOTICE

DO NOT use copper-based coatings or any coatings not approved for use with aluminum. Some paint manufacturers claim their paints are safe for aluminum. Copper components and copper-based paints can cause severe corrosion to aluminum. DO NOT use copper-based paints. Mercury or mercury-based compounds that come into contact with aluminum will result in severe corrosion.

Galvanic corrosion is the corrosion process occurring when different metals are submerged in an electrolyte. Sea water is an electrolyte and submerged engine components must be properly protected. Outboard engines are equipped with sacrificial anodes to help prevent galvanic corrosion problems. The anodes must be monitored and replaced as necessary. For locations and maintenance, refer to the engine owner's manual.

When leaving the boat in the water, tilt the motors as high as possible to decrease the risk of marine growth around the cooling inlets, propeller and exhaust ports and damage from galvanic corrosion.

1.3 Engine Lubrication

4-cycle engines have an oil sump in the crankcase. The oil type, grade and level must be followed in accordance with the engine manufacturer's recommendation. It is normal for 4-cycle engines to consume a small amount of oil. Check the oil level before each use and change it following the engine manufacturer's recommendation.

NOTICE

Use only the oil recommended by the engine manufacturer, and monitor the oil level. Use of any other type of oil can cause the engine to malfunction or severe damage.

1.4 Engine Cooling System

Outboard engines are raw water (sea water) cooled. Water is pumped through the water inlets, circulated through the engine block, and expelled with the exhaust through exhaust port, water port and the propeller hub. The water pump uses a small impeller made of synthetic rubber. The impeller and water pump cannot run dry for more than a few seconds. In most outboard engines, some cooling water is diverted through ports below the engine cowling. This allows the operator to visually check the operation of the cooling system. When the engine is started, make sure a steady stream of water is present.

NOTICE

DO NOT operate an engine out of the water, even momentarily. Water must be supplied to the cooling system of the power head and water pump, or serious damage will result. If it is necessary to run the engine out of the water, connect it to an engine flush attachment design for your specific engine.

If the boat is used in salt or badly polluted water, flush the engines after each use to reduce corrosion. Refer to the engine owner's manual for the proper engine flushing procedure.

1.5 Propellers

The propellers convert the power of the engines into thrust. Propellers vary in style, diameters and pitch. The best set for your needs will depend on your application and expected average load. Propeller sizes are identified by two numbers stamped on the prop in sequence; the first is the diameter and the second is the pitch (example 14 x 21). Pitch is the theoretical distance the propeller will travel in one rotation. Repair or replace a propeller immediately if it has been damaged. A damaged propeller can cause vibration that can be felt in the boat and can damage the engine gear case. Refer to the engine owner's manual for information on propeller removal and installation.

1.6 Engine Instrumentation

The helm station is equipped with a set of engine instruments and alarms. The instruments allow the operator to monitor the operational conditions of the engines. Monitoring the instrumentation allows the operator to operate the engines most efficiently and prevent serious costly damage. The instrumentation is unique to the type of out-

board engines installed on your Pursuit. Your boat may not be equipped with all of the following gauges.

Some models may be equipped with Yamaha Command Link Integrated Information System®. Refer to the Yamaha manuals for information on the operation of this system.

Tachometer

The tachometer displays the speed of the engine in revolutions per minute (RPM). This speed is not the boat speed or the speed of the propeller. The tachometer may not register zero with the key in the “OFF” position.

NOTICE

DO NOT exceed maximum recommended engine RPM. Exceeding, maintaining or close to maintaining maximum RPM can reduce engine life.

Speedometer

The speedometer indicates the speed of the boat in miles per hour (MPH). Most speedometers measure the water pressure against a small hole in a pick-up tube located in the engine lower unit or from GPS in a Yamaha® installation.

Temperature Warning

The temperature warning indicates the temperature of the engine. A sudden increase in the temperature could indicate an obstructed water inlet or an impeller failure.

NOTICE

Continued operation of an overheated engine will cause severe engine damage. If the engine overheats, shut off the engine, investigate the problem and correct it.

Fuel Gauge

The fuel gauge indicates the approximate fuel level in the fuel tanks. This gauge is a relative indication of the fuel supply available; it is not a calibrated instrument.

Voltmeter

The voltmeter displays the voltage for the battery and the charging system. The normal voltage for a full charged battery is 12.6 volts with the engine(s) off and 13 to 14.5 volts with the engine(s) running.

Hourmeter

The hourmeter keeps a running total of engine hours while operating.

Tilt/Trim Gauge

The tilt/trim gauge monitors the position of the outboard engine. The upper range of the gauge indicates the tilt, which is used for shallow water operation, trailering and to keep the gear case out of the water. The lower range indicates the trim position. Trim is used to adjust the hull angle while operating your boat on plane. Refer to the engine owner’s manual for more information on the operation of the outboard power tilt and trim.

Engine Alarms

Most outboards are equipped with an audible alarm system mounted in the helm area to monitor selected critical engine systems and functions. The alarm will sound if one of these systems begins to fail. Refer to the engine owner's manual for information on the alarms installed with your engines.

NOTICE

If an engine alarm sounds, shut off the engine, investigate the problem and correct it.

Fuel Management

Fuel management systems are standard equipment with some outboard engines. On Yamaha® engines, the fuel management gauge is a multifunction gauge used to monitor fuel consumption of the engines. If your boat is equipped with this system, refer to the engine or fuel management manual.

Instrument Maintenance

Electrical system, instruments and ignition circuitry are protected by a circuit breaker or fuse located on the engine. The ignition switches and all instruments, controls, etc. must be protected from the weather when not in use. Excessive exposure can lead to gauge and ignition switch failures.

Moisture may fog the inside of the gauge lens. Turning the gauge lights on will help dry the lenses. Fogging will normally not harm the gauges, but if the fogging continues and moisture accumulates, the excess water can damage the gauges. The gauges are designed with drain holes to reduce the accumulation of moisture. Make sure that if a gauge is removed, it is reinstalled with the drain holes in the proper position.

Helm Systems

2.1 General

The helm controls consist of engine throttle and shift controls, steering system, trim tab control switches, optional spotlight and the optional bow thruster controls.

Each manufacturer of the control components provides an owner's manual with its product. It is important that you read, understand and become familiar with the proper care and operation of all control systems.

2.2 Helm Access

The helm and engine controls are located on an opening helm station. The helm station is hinged at the bottom and opens to provide access to service the helm equipment. To open, slide the seat back to its furthest aft position and tilt the steering wheel to the full upright position and open the two latches securing the helm in place. A strap holds the helm in the open position. To secure the helm back in place, close the helm and secure the two latches. The helm station must be secured before operating or transporting your boat. Injury or damage can occur if the helm is left unsecured. Do not open the helm station with engines running; accidental engagement of shift and throttle levers can occur.

⚠ WARNING

LOSS OF CONTROL AND UNSAFE BOAT HAZARD

Hazard from improper securing of helm is hazardous and can cause death or serious injury from sudden loss of control. Make sure the helm is secure before getting underway and during transporting the boat.

2.3 Engine Throttle and Shift Controls

The shift and throttle controls on your boat may vary depending on the engines. The following control description is typical to most outboard remote controls. Refer to the engine or control manuals for specific information on the controls installed on your Pursuit.

The helm on your Pursuit is designed for a binnacle style control with a single gear shift and a throttle lever for each engine; a position for neutral (straight up and down), forward position (first detent forward of neutral) and reverse position (the first detent aft of neutral). Advancing the control lever beyond the shift range will advance throttle, forward or reverse. Each control is equipped to allow the engine to be operated above idle RPM while in neutral for cold starting or warming up.

The handles of dual lever controls may not always align with each other at all RPM settings because of variations in adjustments at the engine. Usually the alignment of the handles can be optimized at a chosen RPM, but may vary at other settings.

⚠ CAUTION

Avoid possible injury or engine damage when shifting:

Pause in neutral before shifting from FORWARD to REVERSE, or REVERSE to NEUTRAL.

- **DO NOT shift into reverse while the boat is traveling forward at speed.**
- **Keep area around shifter control clear of obstructions.**

See your Pursuit dealer for necessary control adjustments. If the starter for either engine engages with the shift controls in any position other than neutral, the neutral safety switch is not functioning properly and must be repaired before using your boat.

2.4 Neutral Safety Switch

Every control has a neutral safety switch to prevent the engine from being started while in gear. Control adjustments must be performed if the engine will start in forward or reverse.

Test the neutral safety switches periodically to ensure they are operating. To test the neutral safety switches; tilt the engines down and move the shift levers to the forward position, past first detent. DO NOT advance past the idle position. Turn the ignition key to the start position. The starter should not engage for either engine. Repeat test with the shift levers in reverse and the engine throttles at idle, the starter should not engage for either engine. If an engine starts in gear during this test, immediately move the control levers to the neutral position and turn the engine off. Ejection or sudden loss of control can occur if an engine can start in gear and neutral safety switch system does not function properly.

⚠ WARNING

Test the neutral safety switch periodically. If the switch is not operating properly, DO NOT use the boat. Contact your Pursuit Dealer and have it repaired. A neutral safety switch not operating properly can allow the boat to start in FORWARD or REVERSE causing sudden boat movement and throwing operator and passengers.

⚠ WARNING

LOSS OF CONTROL AND UNSAFE BOAT HAZARD

A neutral safety switch that does not function properly can cause death or serious injury. DO NOT operate the boat if the switch does not function properly.

2.5 Engine Power Tilt and Trim

All outboard engines used on your boat have a tilt and trim feature. The tilt and trim switches are usually built into the engine shift and throttle controls and allow the operator to control the position of the outboards from the helm. Moving the gear cases closer to the boat transom is called trimming “in” or “down.” Moving the gear cases away from the boat transom is called trimming “out” or “up.” In most cases, the boat will perform best with the outboards adjusted so the hull will run at a three to five degree angle to the water.

The term “trim” generally refers to the adjustment of the outboards within the first 20 degree range of travel. This is the range used while operating your boat on plane. The term “tilt” refers to adjusting the outboards further up for shallow water operation, trailering or “tilting” the outboards out of the water. Refer to the engine owner’s manual for information on the proper use and maintenance of the power tilt and trim.

NOTICE

The outboard hoses, rigging or the transom gel coat can be damaged if the engine(s) are tilted to full up position or turned in the wrong direction. Turn the steering wheel completely to one direction or the other before tilting up to determined which direction is best for your boat.

2.6 Engine Stop Switch

Your Pursuit is equipped with an engine stop switch and lanyard. When the lanyard is pulled away, it will shut off the engines.

⚠ WARNING

LOSS OF CONTROL AND UNSAFE BOAT HAZARD

An engine stop switch system that does not function properly or is not used can cause death or serious injury. DO NOT operate the boat if the emergency stop switch system does not function properly.

Attach the engine stop switch lanyard to a strong piece of clothing on the operator. The engines will not start if the clip is not inserted into the stop switch. Make sure the lanyard is properly attached to the engine stop switch before attempting to start the engine.

DO NOT use the switch to stop the boat under normal operation. Test the switch periodically, if the switch is not operating properly, DO NOT use the boat. Contact your Pursuit Dealer and have it repaired.

Refer to the engine owner's manual for more information on the engine stop switch.



Start Stop Switch Panel

2.7 Automatic Fire Extinguisher System

⚠ WARNING

FIRE/EXPLOSION HAZARD

The gas of the fire extinguisher system displaces oxygen to "smother" the fire. DO NOT open the hatch. Oxygen can feed a fire and flashback can occur which can cause death or serious injury. If the onboard fire system discharges, wait at least 15 minutes before opening engine hatch.

The generator is equipped with an automatic fire extinguishing system. The extinguisher has been chosen and located to provide sufficient coverage of the generator compartment. While the system helps ensure bilge fire protection, it does not eliminate the U.S. Coast Guard requirement for hand held fire extinguishers.

The system is equipped with an engine shutdown circuit to automatically shut down the generator. The red light on the fire extinguisher control panel will light and an alarm will sound if this should occur. When sufficient time has elapsed for the fire to be extinguished and a flashback is no longer possible, find and fix the problem, then the override switch on the control panel can be moved to the "OVERRIDE" position and the engines can be restarted. Refer to the Automatic Fire Extinguisher System in the Plumbing Systems.

If the extinguisher system is activated, shut down all engines immediately. Turn off all electrical systems, powered ventilation and extinguish all smoking materials. DO NOT open the engine compartment hatch, this will feed oxygen to the fire and a flashback can occur. Allow the extinguishing agent to soak the generator compartment for at least 15 minutes and wait for hot metals or fuels to cool before inspecting for cause or damage. Have an approved portable fire extinguisher at hand and ready for use and DO NOT breathe fumes or vapors caused by the fire. It is extremely important that you read, understand and know how this system works, refer to the manufacturer's literature.



Automatic Fire Extinguisher Display Unit

2.8 Steering System

The steering system is hydraulic and made of two main components: the helm assembly and the hydraulic cylinder. The helm unit acts as both a fluid reservoir and pump. Turning of the helm, or steering wheel, pumps the fluid in the hydraulic hoses and activates the hydraulic cylinder causing the motors to turn. A slight clicking sound may be heard as the wheel is turned. This sound is the opening and closing of valves in the helm unit and is normal. Refer to the steering manufacturer owner's manual for specific information on the steering system.

Triple engine outboards are coupled at the tiller arms by a tie bar. The outboards must be aligned with each other to provide maximum stability on straight ahead runs and proper tracking through corners. If damage has ever occurred with the outboards or steering system, the outboards may have to be realigned.

NOTICE

Some autopilot systems have engine position sensors mounted to the hydraulic steering cylinder. The sensor bracket can contact the transom when the engines are fully tilted up and damage the autopilot, engine rigging or transom. Monitor the bracket and rigging while engines are tilting to determine the best position for your application.

Power Steering

The power steering system uses an electrically controlled hydraulic pump to provide power to the standard hydraulic steering system. Additional components are a helm mounted power steering switch and a hydraulic pump. The switch activates the power steering feature. Manual steering is always available regardless of the switch position. To reduce the sensitivity of the steering, turn off the power steering at low speeds. To conserve battery power, because of limited engine charging output during extended periods of slow speed operation, the power steering should be turned off. Refer to the Teleflex® Power Assist manual for more information.

Yamaha Helm Master (Optional)

The Yamaha Helm Master system is an option. **Before using this system, you should carefully review the Yamaha Owner's Manual for important safety warnings and information, including important operating information and instructions.**

NOTICE

If your boat is equipped with the Yamaha Helm Master system it is very important to install the trailering clips on each steering cylinder when transporting the vessel. Failure to do so can cause damage to the engine cowlings.

⚠ CAUTION

Ensure steering lock clips are removed BEFORE operating boat. Failure to remove steering lock clips may result in no steering control and potential injury.

Tilt Helm

A tilt helm and steering wheel is installed on your boat. To tilt the helm, depress the lever located in the base of the helm and move into position. DO NOT adjust when the boat is underway.

2.9 Optional Electronics

If your boat is equipped with a factory installed electronics package care must be used when cleaning the acrylic trim panel. Use only soapy water with a soft, non-abrasive cloth to assure the best appearance.

NOTICE

Use only warm soapy water and a soft, non-abrasive cloth to clean the acrylic electronics trim. Using any other chemicals or abrasive cloth will cause irreparable damage.

2.10 Trim Tabs

The trim tabs are recessed into the hull on the transom. Switches are used to control the trim tabs. The switches are labeled and control bow up and down movements. They also control starboard and port up and down movements. Bow up and bow down will control the hull planning attitude, while port and starboard up and down provide control for the hull trim side to side.

Before leaving the dock, make sure that the tabs are in the full “UP” position by holding the control in the bow “UP” position for ten seconds. Do not continue to operate the switch when the tabs are fully up or down.

Establish the intended heading and cruise speed before attempting to adjust the hull attitude with the trim tabs. Always make slight adjustments to reduce over adjustments. After stabilizing speed and direction, move the trim tabs to achieve a level side to side running attitude being careful not to over trim.

After depressing a trim tab switch, always wait a few seconds for the change in the trim plane to take effect.

Avoid depressing the switch while awaiting the trim plane reaction. By the time the effect is noticeable the trim tab plane will have moved too far and the boat will be in an overcompensated position.

When running at a speed that will result in the boat falling off plane, lowering the tabs slightly, bow down, will improve the running angle and operating efficiency. Too much bow down tabs can reduce operating efficiency and cause difficult steering and handling.

When running at high speeds, make sure the tabs are in the full “UP” position. Only enough trim plane action should be used to compensate for any listing. Trim tabs are more sensitive at higher speeds. Adjust for this and be prepared to slow down if difficulties arise.

Be extremely careful when operating in a following sea. The effect of trim tabs is amplified under these conditions. Difficulty in steering and handling can result from improper trim tab usage, especially in a following sea; raise the tabs to the full bow “UP” position.

When running into a chop, a slight bow down attitude will improve the ride. Be care-

ful not to over trim, difficulty in handling can result.

Trim Tab Indicator



Trim Tab Switches

The switches are labeled to indicate the reaction of the bow of the boat. The L.E.D. displays indicate the position of the trim tabs. When adjusting the starboard bow up or down, the L.E.D. indicator on the right side of the panel will activate, indicating the movement of the port tab. Refer to the trim tab operation manual.

Trim Tab Maintenance

Marine growth can affect the operation of the trim tab planes and actuators. To help reduce marine growth, return the trim tabs to the full “UP” position after operating the boat. Inspect and clean the actuators and planes regularly.

The trim tabs also include a zinc anode to help prevent galvanic corrosion. Galvanic corrosion occurs when different metals are submerged in an electrolyte. Sea water is an electrolyte and submerged metal components must be protected. Anodes were factory installed and need to be replaced when they are 75% of their original size.

Refer to Routine Maintenance for information regarding zinc anodes and the trim tab owner’s manual for additional maintenance information, fluid specifications and operating instructions.

2.11 Compass

The compass is located at the helm. To adjust the compass, read the instructions on “Compass Compensation” included in the literature packet. The compass cannot be adjusted accurately at the factory as it must be compensated for the influence of the electrical equipment and electronics unique to your boat. The compass should be adjusted by a professional after the electronics and additional electrical accessories are installed and before operating the boat.

2.12 Bow Thruster



Bow Thruster Control

The bow thruster is electrically driven and controlled by a joystick on the helm. Service access for the bow thruster is achieved by removing the forward cabin hatch under the bow berth cushion. The bow thruster is powered by its own battery. This battery is located below the aft hatch under the bow berth cushion. Operate in short bursts of a few seconds to preserve battery life. Refer to the bow thruster manual for more information, maintenance and warranty information.

⚠ WARNING

ROTATING PARTS HAZARD

A rotating bow thruster can cut, entangle or draw a swimmer closer or into the thruster causing death or serious injury. DO NOT use the bow thruster near swimmers.

NOTICE

DO NOT operate bow thruster out of the water, even momentarily. Water must be supplied to prevent impeller from over speeding, which will result in serious damage and void the warranty.

2.13 Spotlight (Optional)

The spotlight is controlled by a panel on the helm and a microprocessor. The microprocessor is located inside the hardtop. It is above the center acrylic access panel in the overhead. Refer to the spotlight manufacturer's owner's manual for an explanation of the features and operation.

2.14 Control Systems Maintenance

Control Maintenance

Periodic inspection of the control systems and all connections should be made. Signs of rust, corrosion, wear, or other deterioration must immediately be serviced. Periodic lubrication of all moving parts and connections with waterproof grease is required.

Control system adjustments may become necessary. If adjustments are necessary, see your Pursuit Dealer.

Steering System Maintenance

Periodically inspect all steering hoses, linkages and helm assemblies. Signs of corrosion, cracking, loosening of fastenings, excessive wear, or deterioration must be corrected immediately. Check the hydraulic steering fluid level frequently and maintain the proper level. Periodic lubrication of all moving parts and connections with light waterproof grease is required. Failure to do so can lead to steering system failure and result in loss of control.

When new, or after repairs, hydraulic steering systems may need to be purged of air. Refer to the information provided with the steering system for specifications and service information.

Check steering operation and visually inspect for loose or missing hardware before operating the boat. If you suspect the steering system is damaged, see your Pursuit dealer. DO NOT operate the boat if you suspect the steering system is malfunctioning.

⚠ WARNING

LOSS OF CONTROL AND UNSAFE BOAT HAZARD

Improper maintenance of steering system is hazardous and can cause death or serious injury from sudden loss of control. Make sure all steering hardware, and fluid levels are regularly inspected and maintained.

DO NOT attempt to service any part of the steering system unless you are familiar or qualified to do so. Follow all instructions regarding maintenance procedures in the steering system owner's manual.

Operator Notes

Fuel Systems

3.1 General

The fuel system of your Pursuit boat is designed to meet the requirements of the U.S. Coast Guard, Environmental Protection Agency (EPA), National Marine Manufacturers Association (NMMA), and American Boat and Yacht Council (ABYC) in effect at the time of manufacture.

Pursuit Boats has engineered an improved fuel tank fill and vent system that will reduce or eliminate fuel spillage when re-fuelling the boat with a standard automatic shut-off fuel fill nozzle provided by marinas and gas stations. This is in accordance to EPA regulations.

While this system provides a clean consistent refueling experience, it still requires the operator's attention and must not be defeated by attempting to over-fill the tank with fuel. This system will automatically provide the proper air space (approximately 5% of total tank volume) in the fuel tank to accommodate the expansion of fuel during daily temperature cycles.

This new EPA compliant fuel system is engineered to vent through a carbon canister when the fuel cap is installed. This will greatly reduce fuel vapors that escape to the atmosphere and reduce the fuel odor that was present on traditional systems. For that reason, the fuel cap has been changed to help the operator verify the cap is properly closed.

The fuel system was factory inspected and pressure tested in accordance with regulations in effect at the time of manufacture. It is the responsibility of the boat owner to maintain the safe condition of the system. Inspect the system frequently to ensure no deterioration or loosening of connections has occurred.

⚠ DANGER

FIRE/EXPLOSION HAZARD

Fuel and their vapors are highly explosive when exposed to open flame or spark, resulting in death or serious injury.

- **Make sure no vapors are present before turning on electrical equipment or starting engines.**
- **Make sure fuel is added to the fuel tank only. DO NOT confuse other deck fills with fuel fills.**
- **DO NOT remove anti-siphon valves from the system.**
- **Turn off all electrical switches before servicing the fuel system.**
- **DO NOT drain any fuel in the bilge.**
- **Check all fuel lines and fittings for leaks before and after starting the engines and after any fuel system service.**
- **Prime fuel system and check all fittings for leaks before and after starting the engines.**
- **DO NOT block fuel vents.**
- **DO NOT store fuel in any containers or compartments not designated for fuel storage.**

NOTICE

Certain bulkhead areas are sealed following U.S. Coast Guard regulations at the date of manufacture. Any modifications must be in accordance with the regulations.

3.2 Fuel System

The fuel system on your Pursuit boat has one fuel tank and three manual “ON/OFF” fuel valves. Refer to the schematics section. The valves are off when the handle is perpendicular to the fuel flow. The fuel valves are normally left in the “ON” position except for extended storage and servicing of the system. Turn all three valves to the “OFF” position when servicing the system and changing the fuel filters.

The fuel delivery lines are equipped with anti-siphon valves where the lines attach to the fuel tank. These valves help prevent gasoline from siphoning out of the fuel tank should a line rupture.

All boats equipped with gasoline engines are required to have anti-siphon valves by the U.S. Coast Guard.

DO NOT remove anti-siphon valves from the system. Anti-siphon valves prevent fuel from flowing into the bilge should a fuel hose or fitting leak. If the fuel valve becomes clogged, clean and reinstall or replace it.

Fuel Tank

The fuel pick-up tubes are positioned in the tanks to achieve optimum fuel usage, fuel line routing, etc. At certain speeds and hull trim angles, the fuel supply at the withdrawal tube can increase or decrease accordingly. Be extremely careful when attempting to operate the boat when low on fuel. Though some fuel may be in the tank, the trim angle of the boat may cause the fuel to flow away from the pickup tubes.

Fuel Gauge Senders

The fuel gauge senders are more accurate when the boat is stationary and level. Because of the change in attitude when the boat is underway, variations in gauge readings can occur. This system is a relative indication of the available fuel supply and not a calibrated instrument.

Fuel Fills


The fuel fill is located on the port gunwale and is marked “GAS”. It is located directly aft of the spring line cleat. The fuel fill is opened by turning it counterclockwise. After fueling, screw the cap on in a clockwise direction until an audible click is heard indicating that the cap is seated. If the cap is lost or damaged replace only with original equipment. During refueling the tank vents out at both the fuel fill plate and the vent located on the side of the hull. **Note:** There should not be any residual fuel at the vent but there could be residual fuel at the deck fill plate. Do not block or restrict either of these vents.

NOTICE

First time fueling may require a slower than normal flow due to the expansion of the air in the tank. Subsequent fills should allow for a normal flow rate.

Fill the fuel tank slowly and monitor the fuel gauge while filling. Once fueling is completed wash the areas around the fuel fill(s) to help reduce discoloration of the fiberglass. Use only the fuel recommended by the outboard manufacturer; refer to the engine owner’s manual for additional information.

If fuel is added to any other tank by mistake, DO NOT attempt to pump fuel out; these systems are not designed to pump fuel. Fuel must be removed by qualified personnel only. Fuel in other systems may also require replacement of that system and/or components.



EPA Fuel Fill

Fuel Vents

There is a single vent for the fuel tank on the port side of the hull. While the tank is being filled, air displaced by the fuel will escape from the vent. Do not allow fuel to be expelled from the vent and pollute our environment. Fill the fuel tank slowly and monitor the fuel gauge while filling. Spilled fuel can be dangerous.

Fuel Filters



Fuel Filters

Fuel filters are located in the mechanical space under the aft in deck hatch. The filters are the water separator type and there is one filter for each engine fuel line. Check all three filters for water frequently to ensure an adequate supply of clean, dry fuel to the engines. The filter elements should be changed once a season.

Turn off all electrical switches before servicing the fuel system and DO NOT drain any fuel into the bilge. Check all fuel lines and fittings for leaks before and after starting the engines and after any fuel system service. Prime fuel system and check all fittings for leaks before starting the engines.

3.3 Diesel Generator Fuel System

The diesel generator is equipped with a separate 24 gallon fuel tank. The diesel filter is located on the port side stringer, midship and is accessed through the mechanical space hatch. This tank is filled through a deck fill marked “DIESEL” on the aft port gunwale. The fuel level of this tank is read on the center tank of the engine display.

NOTICE

DO NOT confuse the diesel and gas fuel fills; severe engine damage will result.

The diesel system is not equipped with anti-siphon valves and there is a fuel return line to return unused fuel to the fuel tank. The diesel system may require priming after servicing. Refer to the generator owner's manual for information on priming.

Make sure the fuel valve is in the “ON” position before attempting to start the generator.

A water separator type fuel filter is installed near the diesel fuel tank. The fuel filter has a sediment bowl that must be inspected frequently for water to ensure an adequate supply of clean, water-free fuel is supplied to the engine. Inspect the filter periodically and change the element as needed.

3.4 Fueling Instructions

⚠ DANGER

FIRE/EXPLOSION HAZARD

Gasoline vapors are highly explosive when exposed to open flame or spark, resulting in death or serious injury.

- **Stop engines before fueling.**
- **DO NOT smoke or allow open flames or sparks nearby, within 50 ft (15 m) of the fueling area.**
- **Maintain contact between fuel nozzle and fuel tank fill to prevent electrostatic spark. DO NOT use a plastic funnel.**
- **Fill in an open area.**

BURN HAZARD

Fuel floating on water which is ignited can cause death or serious injury. Fuel will float on top of water and can burn. If the boat is abandoned, swim upwind, far enough to avoid fuel that can spread over the surface of the water.

Try not to spill fuel. If fuel is spilled, wipe up all traces with dry rags and immediately dispose of the rags properly onshore. DO NOT allow fuel to stay on the finish of the boat, discoloration and damage to trim can occur. Avoid fueling at night, except under well-lighted conditions. Also, monitor fuel level gauge to avoid overfilling.

To fill fuel:

1. Turn all switches to “OFF.”
2. Secure boat.
3. Remove passengers from boat.
4. Extinguish all flame producing items.
5. Open fuel fill(s) by turning counterclockwise.
6. Put nozzle in the fuel fill opening.
7. The fuel delivery system will shut off when the tank is filled to the proper capacity.
8. Remove the nozzle.
9. Install and tighten fuel cap until it clicks.
10. Check the fuel compartment and below the deck for fuel odors. If you smell fuel, DO NOT start engines until the source is isolated and repairs have been made.

Fuel System Maintenance

⚠ DANGER

FIRE / EXPLOSION HAZARD

Fuels are extremely flammable and highly explosive under certain conditions. DO NOT smoke or allow open flames or sparks nearby when inspecting the fuel system.

Frequently check fuel lines and all system components (filters, primer bulbs, clamps and connections) for leaks, damage or deterioration, or if you suspect damage, replace as necessary. Surface cracking on a hose indicates wear. Replace it.

Spray the valves, fuel tank gauge sender and ground connections with a metal protector.

Inspect the fuel fill cap o-ring seals frequently and lubricate with petroleum jelly or silicone grease. The o-ring seal prevents water from entering the fuel system through the fuel fill cap. If the o-ring is damaged, or you suspect it is damaged, replace it.

NOTICE

Use only the fuel recommended by the engine manufacturer. Use of old, contaminated fuel can cause the engine to malfunction or severe damage. Do not use fuel that contains more than 10% ethanol, harsh additives or methanol; damage to the engines and fuel system will result. Fuel system damage, related to use of alcohol-blended fuels, is not covered by the Pursuit Limited Warranty. Refer to the engine owner's manual for specific fuel requirements for your engines.

Old, degraded gasoline can affect engine performance and damage the engine and boat fuel system. Chemical changes occur as gasoline ages, reducing octane and can cause deposits and varnish in the fuel system.

If your boat is not operated enough to require at least one full tank of fresh fuel a month, a fuel stabilizer should be added to the gasoline to protect the fuel from degrading. Do not allow the boat to sit unused for an extended period with the fuel tanks less than 3/4 full. Changes in temperature and weather conditions can cause condensation in fuel tanks. Your Pursuit dealer or the engine manufacturer can provide additional information on fuel degrading and fuel stabilizers recommended for your engine.

Improper storage of fuel at marinas, limited boat usage, etc. can cause the fuel to become contaminated. Periodically, it may be necessary to pump accumulating water and contaminated fuel from the bottom of the fuel tanks. If the fuel system on your boat becomes contaminated, contact your dealer or marina for assistance.

Avoid using fuels with alcohol additives. Alcohol blend gasoline will absorb moisture from the air which can reach such concentrations that “phase separation” can occur where the water and alcohol mixture becomes heavy enough to settle out of the gasoline to the bottom of the tank. Since the fuel pickup tubes are near the bottom of the tank, phase separation can cause the engine to run very poorly or not at all. Phase separation is more severe with methyl alcohol and will increase as the alcohol content increases. Water or a jelly like substance in the fuel filters is an indication of phase separation from the use of alcohol blended fuels.

Diesel engine operation requires a good supply of clean, water-free diesel fuel. Algae can grow in the accumulated water in the diesel fuel tank. This will normally occur in warm climates. Adding a high quality diesel fuel additive containing an algaecide periodically may be required to control algae in your diesel system, depending on your boating area. Contact your Pursuit Dealer or engine manufacturer for additional information regarding fuels and additives.

Operator Notes

Electrical Systems

4.1 General

Your Pursuit boat is equipped with DC and AC electrical systems. The DC system draws current from onboard batteries. The AC system can draw current from either shore power outlets at dockside or the optional generator.

Electrical schematics are included in this manual to assist technicians in the servicing the electrical systems. Pursuit recommends you take your boat to an authorized Pursuit dealer for service or installation of additional electrical equipment. Pursuit reserves the right to modify or update the electrical system at any time without notice to the consumer or obligation to make updates to boats built prior to the change.

Some compartments on your boat may be lighted. Lights bulbs produce heat and can ignite combustible products. Turn off all lighting before you leave the boat.

⚠ WARNING

FIRE OR EXPLOSION HAZARD
Ignited combustible products can cause fire or explosion, resulting indeath or serious injury. DO NOT store combustibles near lights and turn off all lighting before leaving the boat.

4.2 DC System

Batteries

The 12-volt batteries have been selected to provide optimum performance for engine starting, and house and electronics loads. There are three, Group 31, lead acid batteries: one for the port engine, one for the center engine, and one for the starboard engine. These batteries require similar maintenance to automobile batteries. There are three AGM (Absorbed Glass Mat) batteries. There is a house battery, electronics battery and a bow thruster battery.

The three engine starting batteries are located in the port side slide out tray. Remove the pull pin and the tray will slide inboard for servicing. The aft battery is for starting the port engine. The center port battery is for starting the center engine. The forward port battery is for starting the starboard engine.


The house and electronics batteries are located in the starboard side slide out tray. Remove the pull pine and the tray will slide in for servicing. The forward starboard battery is for the house service. The aft starboard battery is for the electronics service.

After inspection or servicing the batteries, slide the battery tray outboard and reinstall the pull pin. The pin locks the tray in the closed position.

The bow thruster battery is located under the removable hatch below the forward berth cushion. The main circuit breaker for the bow thrusted is located in a gray box adjacent to the battery.

DC Distribution

The 12-volt OS system batteries are charged by the engine charging system or the battery chargers when connected to shore power or when operating the generator. 12-volt power is distributed to the battery switches and breakers on the Main Distribution Panel (MDP) (located on the inboard side of the port L-Lounge) that protect the switch panels on the helm and in the cabin. The battery voltage for the house and electronics batteries is monitored using the volt meters on the MDP. The engine battery voltage is monitored on the respective tachometer.



Main Electronics Battery Disconnect


The house and electronics main breaker disconnects ALL battery power to the house and electronics batteries. This breaker is located under the starboard cockpit deck hatch. It is mounted to the side of the hull stringer directly opposite the power steering pump. If the boat is stored out of the water, turn off the house and electronics breakers to ensure there is no electrical drain from the associated battery.

Bow Thruster Main

The bow thruster main breaker protects the bow thruster and its wiring. It is located below the forward hatch under the bow berth cushion. It is directly outboard of the bow thruster battery.



Bow Thruster Main



12 INCHES

BACK PANEL (X2 FLAT PRINTER)
-RED SCREEN PRINT (5A)
-YEL SCREEN PRINT (10A)
-GRN SCREEN PRINT (15A)
-BLU SCREEN PRINT (20A)
-ORG SCREEN PRINT (25A)
-VIO SCREEN PRINT (30A)
-CYN SCREEN PRINT (40A)
-GRY SCREEN PRINT (50A)
-BLACK TEXT PRINT (BREAKER VALUES)

Battery Switches

There are two battery switches to manage the 12-volt power distribution. One battery switch controls the house battery and the electronics battery. The other battery switch controls the two engine batteries. The electronics and house batteries or the port and starboard engine batteries can be paralleled by switching to “combine batteries.” It is not possible to parallel the engine batteries with the house and electronics batteries.

Make sure the electronics and house and the engines battery switches are in the “ON” position whenever the engines are running to ensure ALL 12-volt accessories will operate when they are needed. Current is supplied to the CO detector, the automatic float switches for the bilge pumps, stereo memory, high water bilge alarm and the sump when the batteries are connected and the battery switches are “OFF”.

⚠ CAUTION

DO NOT operate the boat with the engine battery switch in the combine batteries position. This could potentially lead to dead batteries and stranding.

Main Breakers

Electronics Main

This breaker is reserved for electronic accessories installation. An electronic bus is located behind the helm.

House Main

Supplies the 12-volt current to breakers for cabin equipment and the cabin switch panels.

Helm Main

Supplies the 12-volt current to helm and cockpit switch panels.

Vacuflush

The Vacuflush breaker powers the head holding tank vacuum pump and switch panel.

Head Macerator

The macerator breaker powers the head switch panel.

Cockpit Refrigerator

The refrigerator breaker powers the sliding drawer refrigerator in the cockpit. This breaker should not be left on unless the boat is plugged into shore power as it will drain the house battery.

Windlass Main

The windlass breaker is located on the MDP. To reset or turn the circuit breaker on, rotate the lever to “ON.” Turn off this breaker when the windlass is not in use to reduce the possibility of accidentally activating the windlass.

CO Detector

These breakers supply current to the carbon monoxide detector. The power indicator on the carbon monoxide detector should be lit whenever someone is occupying the cabin. If the breaker has tripped, it indicates there is a problem with the carbon monoxide detector or the breaker or the wiring from the breaker panel to the detector. Determine the cause of the problem and correct it before resetting the breaker.

Carbon monoxide detectors are safety devices designed to sound an audible alarm when carbon monoxide is detected in the area of the detector. Carbon Monoxide (CO) gas is colorless, odorless and extremely dangerous. All engines and fuel-burning appliances produce CO as exhaust.

CO detectors are recommended in areas where CO build-up is a possibility, especially in boats having confined areas; such as sleeping quarters, galleys and head compartments. Check the condition of the CO detector regularly for proper operation. See the manufacturer instructions for installation requirements and operating instructions.

⚠ DANGER

EXTREME HAZARD
Carbon monoxide (CO) gas is colorless, odorless and extremely dangerous.
All engines and fuel-burning appliances produce CO as exhaust. Directand prolonged exposure to CO will cause brain damage or death.

4.3 12-Volt DC Panels

Helm Switch Panel

The following are descriptions of the components controlled by the helm switches:



Horn

Activates the boat horn.

Nav/Anc

Pressing the top of the rocker switch activates the navigation lights. Pressing the bottom will activate the anchor light.

NOTICE

Do not let your boats lights confuse. The USCG reports that some boaters have hazardously installed unapproved red and green LED strip lighting on the bow, which hampers other boater's efforts to avoid collision. Also avoid displaying any light that could be confused as another navigation light or another vessel. And do remember flashing blue lights are reserved for law enforcement – at a distance, wave action combined with the steady rocking of below the waterline high-intensity blue lights can give the appearance of a police vessel.

Cockpit

Activates lights to illuminate the cockpit area.

Underwater Lights (Optional)

Activates the optional underwater lights. Use these lights only when the boat is in the water as they rely on water for cooling.

NOTICE

These lights should only be used while vessel is anchored, at the dock or on a mooring.

Spreader

Activates the flood lights located on the hardtop.

Hardtop

Activates the lights located on the hardtop. Engaging this switch cycles through the different colors.

Deploy/Retrieve

Pressing the rocker switch drops (deploys) and retrieves the anchor. Refer to the Windlass in the Exterior Equipment.

Sun Shade (Optional)

Activates the retractable sun shade awning. Depressing the bottom of the switch will deploy the shade. Depressing the top of the switch will stow the shade within the hardtop. CAUTION – When retrieving the sun shade make sure all objects are clear of the area. Damage or injury could occur.

ACCY

These are open and reserved for additional accessories. DO NOT exceed 10 amps.

Forward Bilge or Aft Bilge

Depressing the switch will activate the respective manual pump. If the automatic pump activates, the automatic bilge pump indicator on the switch will light.

Fresh Water

Activates the fresh water pump. The pump is the pressure demand type and is protected by a circuit breaker on the MDP and an automatically resetting breaker on the pump motor.

Refer to the Plumbing Systems Section for more information on the fresh water system.

Washdown Pump

Pressing this switch activates the raw water washdown pump. The pump is the pressure demand type and is protected by a circuit breaker on the MDP and an automatically resetting breaker on the pump motor.

Refer to the Plumbing Systems Section for more information on the washdown system.

Livewell

Activates the livewell circulating pump to supply water to the livewell. The pump is protected by a circuit breaker on the MDP.

Refer to the Plumbing Systems Section for more information on the livewell system.

Port Fishbox

The fishbox switch activates the overboard discharge system for the port in floor fishbox. The pump is protected by a circuit breaker on the MDP. See the Plumbing section for more information on pumping out the fishbox.

Washer

Activates the windshield washer. The fresh water system must be on to operate the washer.

Port and Starboard Wiper

Activates the port and starboard windshield wiper.

Power Steering

Activates the optional power steering feature.

Cabin Switch Panels

Switches on the cabin panels operate the interior and accent lighting for the cabin.

Head Panel



The indicators on this panel display the holding tank level and also includes the holding tank overboard discharge macerator switch. The macerator switch can only be activated when the key switch is fully turned. Refer to Head Compartment of the Interior Equipment.

4.4 AC System

⚠ DANGER

ELECTROCUTION, FIRE OR EXPLOSION HAZARD

Contact with live wires or working onan energized electrical system can cause electrocution. It can also cause sparks, resulting in fire and/or explosion. Both cases will result in death or serious injury. DO NOT work on an energized system or allow unqualified personnel to work on the system.

To reduce the possibility of an electrical shock, it is important that the AC ground system is functioning properly and that a proper connection exists between the shore power cord, the shore power inlet, the boat bonding system and the outlet ground circuits. If there is any doubt about the integrity of the ground circuit, a qualified marine electrician should be contacted immediately and the AC should be disconnected until the necessary repairs are completed. Replace with:

The AC electrical system operates on a 240 volt, 50 amp, 60 cycle system. Models with CE designations operate on a 230 volt, 32 amp, 50 cycle system.

The AC system is fed by the shore power or by the generator. Your boat is equipped with an isolation transformer. The isolation transformer maintains correct AC polarity regardless of the polarity of the shore power supply and eliminates the need for a galvanic isolation system and a reverse polarity indicator.

Refer to the isolation transformer manual for additional information.

The main breakers in the AC Main Distribution Panel (AC MDP) are equipped with a selector slide to prevent the shore power source and the generator source from being energized simultaneously and damaging the electrical system components. These breakers protect the system and components from an overload. All AC current is distributed to the AC components through individual 120V/240V (230V for CE) circuit breakers located in the AC MDP.

4.5 AC Main Distribution

The AC panel is located in the cabin. The following are descriptions of the AC panel equipment and the breakers that protect the accessories:

AC Multi-Meter

Use the arrow keys to scroll through digital readouts for amperage (A), voltage (V), cycles (hertz) (Hz) and watts (W).

- (A) Indicates the total amperage being drawn through the AC MDP. It is the total current level of all of the AC equipment in operation at the time.
- (V) Indicates the voltage supplied to the panel. Ideally the voltage should be approximately 240 volts (230 for CE) but never less than 208 volts.

- (Hz) Indicates cycles which should be 60 (50 for CE).
- (W) Indicates total watts being consumed as a result voltage x amperage.

AC Main

Protects the general distribution network. This breaker should be on when the boat is using shore power for its source. This breaker is very sensitive. The resulting power surge that occurs when connecting the dockside cord may cause the main breaker to trip. To avoid this surge, turn the main breaker to “OFF” position before plugging or unplugging the shore power cord.

Battery Charger Switches

Supplies AC to the two on-board battery chargers.

Cabin Air

Supplies AC directly to the cabin air conditioning control panel and the air conditioner (if option is installed). Otherwise it is reserved for additional AC equipment. This breaker will trip if raw water is not being supplied to the air conditioner. If this breaker trips, reset and check for water flow out of the air conditioning thru-hull. Refer to the air conditioner manual for additional information.

Cooling Pump

Supplies power to the AC cooling pump. This switch must be on prior to running the cabin or cockpit air systems or a high pressure fault will result on the AC control panels. Refer to the air conditioner manual for additional information.

Water Heater

Supplies AC directly to the water heater. The water temperature is automatically controlled by a thermostat in the water heater control panel. Before operation, the water heater tank must have water. Refer to the water heater manual for more information.

Cockpit Air (Optional)

Supplies AC directly to the cockpit air conditioning control panel and the air conditioner. Otherwise it is reserved for additional AC equipment. This breaker will trip if raw water is not being sup-plied to the air conditioner. If this breaker trips, reset and check for water flow out of the air conditioning thru-hull. Refer to the air conditioner manual for additional information.

Cockpit Grill

Supplies AC power directly to the cockpit grill. This switch should be off at all times other than while using the grill as a safety precaution. Refer to the grill manual for additional information.

Microwave

Supplies AC directly to the microwave oven. Refer to the microwave manual for more information. Electrical System Section 4.

Outlets

Supplies AC to the cabin electrical 120-volt outlets. AC electrical outlets are provided with ground fault interrupters (GFI) to help protect against electric shock. Test outlets periodically by pressing the test/reset buttons in the center of the face plate to ensure proper operation.

GFI outlets do not protect against short circuits and overloads. This protection is done by the outlet breakers on the AC panel. GFI outlets do not provide 100% protection from electric shock. Even though GFI outlets protect by reducing exposure time from line to ground shock hazards, it is still possible to receive an electric shock from defective appliances, power tools or misused electrical equipment.

4.6 Battery Charger Operation

The battery charger charges and maintains the 12-volt batteries simultaneously when activated. It is automatic and is equipped with an ammeter to monitor charging. Refer

to the battery charger manual for more information.

At dockside, when the boat is connected to shore power, the battery charger maintains the charge on the house and engine batteries. When operating on the optional generator, the on-board battery charger must be “ON” to maintain charge of the house battery. The generator charging system does not generate enough current to keep up with the electrical demand on the house battery.

The wires that supply OS charging current to the batteries are protected by an internal fuse in the battery charger and three circuit breakers, one for each battery bank output wire. The breakers protect the OS charging circuit from the batteries to the charger. They are located on the OS distribution panel. Push to reset the breakers. The internal fuses in the charger protect the OS charging circuit from the charger to the batteries.

4.7 Shore Power Connection

Connecting Shore Power

⚠ DANGER

ELECTROCUTION HAZARD
Exposure to high voltage will cause death or serious injury. DO NOT attempt to correct wiring yourself. DO NOT swim in marinas or near boats connected to shore power. Keep children away from any electrical cables or equipment and use grounded appliances onboard only.

If you suspect the shore power connection system is faulty or damaged, have a qualified marine electrician check the system.

Turn the AC main breaker to “OFF” position. If the dockside outlet includes a disconnect switch, turn it to “OFF. ”

Your boat is equipped with a Glendinning shore cable reel. To use simply open the shore power cord cover and pull using the strap on the shore cord to manually deploy.

To avoid strain on the cable make sure it has more slack than the mooring lines. Protect the cable so it cannot be damaged by chafing between the boat and the dock. Keep the cable from making contact with the water. Then connect the cable to the boat connection plug and the dockside outlet. Make sure the dockside connection plug includes a three-prong plug with a ground wire. Tighten the lock rings on both the shore and the boat connector plugs. Turn the dockside disconnect switch or circuit breaker to “ON.” Turn the main AC breaker on in the cabin.

Disconnecting Shore Power

Turn the main breaker on the AC panel and the disconnect switch on the dockside outlet to “OFF”.

Disconnect the cable from the dockside outlet and replace the outlet caps.

⚠ CAUTION

Care should be taken when retrieving the shore cord. Keep fingers and objects out of the retrieval path. Injury or damage can occur.

The Glendinning control switch is located directly in front of the transom door on the port side. It is above the switch for the cockpit lights. While guiding the shore power cord press the switch to retrieve the cord. Replace the cover over the shore cord storage.

⚠ DANGER

ELECTROCUTION HAZARD
Exposure to high voltage will cause death or serious injury. DO NOT attempt to correct wiring yourself. DONOT swim in marinas or near boats connected to shore power. Keep children away from any electrical cables or equipment and use grounded appliances onboard only.

4.8 Generator

Your Pursuit is equipped with a diesel generator. The generator is equipped with an automated start-up sequence to prevent over cranking which can lead to engine damage and to ensure that the generator is up to operating temperature before the electrical load is applied. The display on the generator panel provides detailed information on the operating status of the generator. Refer to the generator owner's manual for complete explanation on the operation and interpretation of the displayed data.

The generator uses a coolant reservoir tank to maintain proper operating temperatures. The coolant must be checked frequently. The tank is located behind the aft cockpit tackle locker drawer. The drawer is removable. To inspect the fluid level, open the door and remove the drawer. See generator manual for more information. Because of the number of OS systems on this boat that can be in operation, a significant drain on the batteries can occur. Depending on the RPM and the duration of operation of the engines, the engines' charging systems may not be able to keep up with the OS electrical demand particularly when the engines are run at low RPM for extended periods.

To ensure that the batteries remain at peak charge, Pursuit strongly recommends that the generator be run whenever the boat is in use and not connected to shore power. It is important to activate the house battery charger to maintain the house, electronics and bow thruster batteries whenever the generator is running. The generator is located in an enclosure in the machinery space. The generator compartment is equipped with an automatic fire extinguisher system and an automatic engine shutdown system. Refer to the Safety Equipment chapter.

NOTICE

DO NOT allow the generator to run outof fuel. Fuel injected generatorsrequire air to be removed from the fuel-delivery system before initial start-upor if the generator is allowed to run out of fuel. Continued attempts to start generator with air in the fuel system can lead to engine damage orerratic operation. Air must be purgedby your servicing dealer only.

Generator Panel

These switches control the starting, running, AC power selector and stopping of the generator. The procedures may vary depending on the model and type of generator installed in your boat. Refer to the generator manual for more information.

NOTICE

DO NOT start generator with GENERATOR switch in the on position. Allow generator to warm-up three to four minutes before transferring the electrical load. After warm-up, place GENERATOR switch in the on position.

4.9 Electrical System Maintenance

12-Volt OS Electrical System Maintenance

Semi-annually spray all exposed electrical components behind the helm and in the plugs with a protector specific for electrical connections.

Make sure to check that all below deck wiring is properly supported, the insulation is sound and there are no loose or corroded terminals. Clean any corroded terminals thoroughly, or replace them. Tighten securely and spray with a metal and electrical protector. Inspect all engine wiring.

Check the electrolyte level in the engine batteries regularly and add distilled water as necessary. If the batteries are frequently charged by a battery charger, check the electrolyte level more often. The correct fluid level in the cells is approximately ¼ to ½ inch above the plates. If fluid is needed, fill to the proper level with distilled water ONLY. DO NOT overfill. Some batteries are sealed and cannot be filled.

Keep the tops of any battery clean and dry. Dirt and water can conduct electricity from one post to the other and can cause battery discharge or cause errant engine warnings. Keep the battery posts free of corrosion. DO NOT use wing nuts to attach battery cables. Remove the cables and clean the posts and cable clamps with a battery post cleaner or sandpaper as required. Coating the battery posts and cable clamps with petroleum jelly or silicone grease will help protect and reduce corrosion. Battery cables, both positive and ground must be replaced when they show signs of corrosion or fraying. Deteriorated cables cause a considerable voltage loss when high currents are drawn, as for starting the engine.

⚠ DANGER

FIRE OR EXPLOSION HAZARD
Explosion or fire from hydrogen gases produced by lead acid batteries will cause death or serious injury. DO NOT smoke or bring a flame near battery storage area. If ignited by a spark or flame, gas may explode violently, causing spraying of battery acid or fragmentation of the battery.

AC Electrical System Maintenance

Inspect periodically all wiring insulation for nicks, chafing, brittleness, improper support, etc. Also, inspect portable appliance cords and plugs.

Examine the shore power cord for cracks in the insulation and corrosion in electrical connectors. Spraying receptacles and electrical connections with an electrical contact cleaner or a metal and electrical protector will help reduce corrosion and improve electrical continuity.

⚠ DANGER

ELECTROCUTION, FIRE OR EXPLOSION HAZARD
Contact with live wires or working onan energized electrical system will cause electrocution. It can also cause sparks, resulting in fire and/or explosion. Both cases will result in death or serious injury. DO NOT work on an energized system or allow unqualified personnel to work on the system.

General Precautions

- DO NOT work on an energized system; make sure all power sources are off.
- DO NOT allow unqualified personnel to perform electrical maintenance; only a qualified marine electrician should work on the electrical system.
- DO NOT work in a wet area.
- Use caution when connecting wires to avoid reversing polarity.
- DO NOT alter wires, connectors or use inferior parts; use OEM replacement parts only.

Corrosion on the electrical connectors can cause poor connections, shorts and ground faults, and/or poor ground connections. Check at least annually and clean as required. DO NOT allow corrosion to build on connections.

Inspect all terminals and make sure they are tight.

Have the entire AC circuitry tested every season by an experienced marine electrician, especially the shore power cord. This will detect any shorts, open wires or ground faults. Also, have the polarity indicator system inspected for proper operation.

Test all GFCI outlets periodically by pressing the test/reset buttons in the center of the face plate to ensure proper operation.

The engine maintenance required on the generator is similar to the main engines. The most important factors to the generator's longevity are proper ventilation, maintenance of the fuel, ignition, cooling and lubrication systems, and the AC alternator.

Maintenance schedules and procedures are outlined in your generator owner’s manual, follow them exactly.

Plumbing System

5.1 Fresh Water System

General

The fresh water system consists of a potable water tank, distribution lines and a distribution pump. The pump is equipped with an automatic pressure switch and is accessed by lifting the mid-berth mattress and removing the access hatch cover underneath. An in-line strainer located near the pump protects the system from debris. The tank is filled through a labeled deck fill located on the starboard forward gunwale.

DO NOT confuse other deck fills with the fresh water fill. If toxic fluids or fuel is added to the fresh water tank, the system will be contaminated. DO NOT attempt to pump fuel out; this system is not designed to pump fuel. Fuel must be removed by qualified personal only. Fuel in the fresh water systems will also require replacement of that system and/or many components.

⚠ DANGER

FIRE OR EXPLOSION HAZARD

Fuel and their vapors are highly explosive when exposed to open flame or spark, resulting in death or serious injury. Do not confuse deck fills.

Operation

Fill the water supply tank slowly through the FRESH WATER FILL deck plate. After filling tank, partially open all faucets. Turn on "Fresh Water" switch at the helm. Allow the pump to run until all of the air is purged from the system and a steady stream of water is flowing from each outlet. Next, turn off the faucets one by one. As the pressure builds, the pump will automatically shut off.

When properly primed and activated, the water system will operate like the water system in a home. An automatic pressure sensor keeps the system pressurized. If the system has been recently filled or has not been used for an extended period, air may accumulate at the pump and the system may have to be re-primed.

Whenever the boat is left unattended, turn the fresh water system switch "OFF."

NOTICE

DO NOT allow the fresh water pump to run dry; damage to the pump can occur. The fresh water pump works on demand and WILL NOT shut off when the tank is empty. Turn the water pump switch "OFF" when the system is not in use. Operating any pump from a low-charged battery can lead to a pump failure. Keep the batteries properly charged. The fresh water system must be properly winterized prior to winter lay-up. Refer to Winterizing.

Sink and Shower Operation

To use the head sink and shower, turn on the "Fresh Water" switch on the helm switch panel. Turn the water on at the faucet and adjust the hot and cold water until the desired temperature is obtained. Some minor variations in the water temperature may occur as the pressure pump cycles.

Shower water is drained from the head compartment by a sump pump system connected to the shower drain. An automatic float switch in the shower sump controls the pump. The pump is protected by the shower sump circuit breaker. After showering, let the cold water flow for a period of time to flush the drainage system of soap residue.

The shower sump system is located in the bilge compartment. To access the sump system, open the forward facing door on the centerline of the aft berth. With the door open, flip up the hinged poly hatch. The sump box is fitted with a clear lid and it is important that it is visually inspected on a regular basis for the accumu-lation of debris.

Should there be any accumulation on the drain strainer, the box should be cleaned out to prevent degradation in performance or potential stoppage in the system.

Water Heater

The water heater is located in the bilge compartment. To access the water heater, open the forward facing door on the centerline of the aft berth. With the door open, flip up the hinged poly hatch. All water heaters have an AC element that is thermostatically controlled at the heater and activated by a circuit breaker located in the AC panel. A high pressure relief valve protects the system from excessive pressure. Make sure all air is purged from the water heater and lines before activating the water heater breaker. Refer to the water heater manual for additional information.

NOTICE

DO NOT turn on water heater until it is filled and primed; damage to the heater will result.

Shore Water Connection

The shore water connection allows the direct connection of the water system to a shore side water supply. This provides the system with a constant supply of fresh water and minimizes the pressure pump operation. A female inlet fitting is located on the starboard side of the splash well. It is directly behind the livewell.

To use shore water, connect a hose from the shore water faucet to the shore water fitting on the boat, then turn on the shore water. The pressure pump will not run and the water in water tank of the boat will not be used. Also, the water tank will not be filled by connecting to shore water.

NOTICE

DO NOT change or modify the shore water inlet connector without contacting Pursuit Customer Relations or your dealer. Use of the wrong type or a modification can damage the fresh water system.

5.2 Raw Water Washdown

The raw water washdown system pump is supplied by hoses connected to a ball valve and a thru-hull fitting located in the bilge.

Operation

Make sure the ball valve is open before attempting to operate the raw water washdown system. The pump is activated by the “Washdown” switch located on the helm. When activated, the pressure switch will automatically control the pump. As pressure builds in the washdown hose, the pump will shut off. When the washdown hose is in use and the pressure drops, the pump will turn on. Turn the switch off when the washdown is not in use. The raw water washdown is equipped with a sea strainer on the intake side of the pump, located in the aft bilge; check it frequently and clean as necessary.

Priming the System

Open the ball valve and hose connector, and activate the pressure pump. Run the pump until all air is purged from the system. Close the thru-hull ball valve before the boat is hauled from the water to eliminate an air lock in the system. It may be necessary to re-prime the raw water system if the system is not used for an extended period.

NOTICE

DO NOT operate high-pressure pump dry, damage to pump will result. Turn the raw water pump switch “OFF” when leaving the boat unattended.

5.3 Livewell

Seawater is provided to the livewell by a 12-volt circulating pump. This pump is designed to carry a constant flow of water to the livewell. The pump is activated by the “Livewell” switch on the helm. An overflow built into the livewell automatically controls livewell water level. Always turn livewell pump off at the switch panel when not in use.

To fill livewell, plug drain fitting at the bottom of the livewell. Make sure the ball valve at the intake thru-hull fitting is open and turn on livewell pump. When water level reaches the overflow, it will begin to circulate.

To drain, turn off pump and remove plug. When the livewell has drained, use the washdown hose to flush livewell and drain debris.

Close the livewell thru-hull ball valve whenever livewell is not in use to prevent water from entering the livewell while the boat is cruising. The livewell pump is equipped with a sea strainer on the intake side of the pump located in the aft bilge. Check it frequently and clean as necessary.

Do not use livewell for stowage. Seawater can enter livewell when it is not in use and damage stowed equipment.

5.4 Drainage

General

Some drain thru-hull fittings are equipped with ball valves that are always open under normal operating conditions. In the event of an emergency, close the valves to prevent sea water from entering the boat through the drainage system. Check and operate the drain valves at least once a month to make sure they are in good condition and operating properly. Also, check the drain system to ensure it is free flowing and hoses on the thru-hull fittings are secure and not leaking.

Review and become familiar with the drainage schematic and location of the thru-hull drain valves.

A situation requiring one or more drain valves to be closed can be dangerous to boat and all onboard. If this occurs, distribute PFD’s and take all necessary safety precautions, including notifying the Coast Guard or local agency, until the problem is determined and corrected.

Bilge Drainage

The bilge pumps are located in the stern bilge, forward area of the aft bilge and under mid berth. All bilge pumps pump water out of thru-hulls located above the waterline in the hull. A high water bilge alarm monitors excessive bilge water levels and signals a high water condition through a visual and audible alarm. See Electrical Systems for additional information on bilge pump and high water bilge alarm operations.

Inspect the bilge area frequently for evidence of excessive water. Continuous operation of the bilge pump can mean there is excess water in the bilge. Test the bilge pump at regular intervals. Debris can also prevent the pump from operating or make it operate continuously.

Bilge pumps and bilge pumping systems are not designed for damage control. Continuous operation of the bilge pump can mean a leak or a drain plug is installed incorrectly; make sure all drain plugs are installed.

Excess water in the bilge area will adversely affect the handling and maneuverability of the boat and can cause personal injury. DO NOT allow the bilge pump to operate after all the water has been cleared from the bilge area. Damage to the pump will occur.

The aft bilge pump system consists of two pumps; one automatic and the other manual. The automatic bilge pump is activated by a sensor switch (black dot) located on the pump housing. This sensor activates the pump when water reaches the pre-set height. The aft pump is the manual pump and is controlled by the switch at the helm.



Aft Automatic Bilge Pump

Current is supplied to the automatic sensor switches whenever the batteries are connected. The bilge pump switches in the helm are supplied current when the house battery switch is in the “ON” position. Breakers for the manual and the automatic functions are located on the MDP.

Activate the manual bilge pump briefly each time the boat is used to ensure pumps are operating properly. Activate the automatic switch manually to verify operation by running water in the forward bilge until the pump activates. There is a delay (5 seconds) built into the switch before the pump will activate. The pump will continue to operate for a short time after you remove your finger. Refer to the manufacturer's information under “Plumbing” for more information.

When the boat is out of the water, the bilge can be drained by two thru-hull drain fittings located in the aft mechanical space, near the bottom of the hull. It is important to check the drain plugs regularly to ensure they are tight.

A loose drain plug will allow sea water to enter the bilge and cause the boat to sink. Check the drain plug frequently to make sure it is secure.


Any oil spilled in the bilge must be thoroughly removed and properly disposed of before operating the bilge pump. The discharge of oil from the bilge is illegal and subject to fine.

NOTICE

The federal water pollution control act prohibits the discharge of oil or oily waste into or upon the navigable waters of the United States or the waters of the contiguous zone if such discharge causes a film or sheen upon, or a discoloration of the surface of the water, or causes a sludge or emulsion beneath the surface of the water. Violators are subject to a penalty of $10,000.

Exterior Drains

Your Pursuit boat has scupper drains located in each corner of the rear cockpit. These drains are connected to ball valves in the hull side. To open and close the valves use the control rods in the mechanical space. The valves are closed when the rods are pushed all the way outboard. They are open when the rods are pulled all the way inboard.




Deck drain ball valve levers

All exterior sinks and livewells, provided with fresh or raw water, drain by gravity to overboard thru-hulls located in the hull sides just above the waterline.

The drain rails for the fish boxes and the mechanical space drain overboard by gravity.

The below floor fish box is equipped with a diaphragm pump located in the aft bilge. Access is through the aft in-deck hatch. The

fish box should be flushed out and cleaned after each use.



Fishbox Pump

The anchor locker drains overboard through a special drain fitting located in the hull side at the bottom of the rope locker. Inspect the drain frequently to remove any accumulated debris.

5.5 Plumbing System Maintenance

Information supplied with water system components, by the equipment manufacturers, is included with this manual. Refer to the information for additional operation and service information.

Fresh Water System

⚠ CAUTION

Turn the fresh water system switch "OFF" when leaving the boat unattended or when the fresh water system is not in use.

Perform these routine maintenance procedures to maintain your fresh water system:

- Remove filter screens from faucet spouts and eliminate any accumulation of debris. A debris build-up can cause the pump to cycle excessively.
- Check and clean the fresh water system strainer located on the intake line near the pump at least annually.
- When necessary, remove the lid on the shower sump assembly. It is located in the forward bilge compartment. To access the shower sump, open the forward facing door in the mid-berth on centerline. Flip open the hinged poly lid, clean debris from the sump and flush with clean water, activate the float switch to test the pump and spray the pumps and metal components with a metal protector periodically.

NOTICE

Maintain a proper charge on the batteries, operating the pressure pump from a battery with a low charge could lead to pump failure.

- Add a commercially available potable water conditioner to the water tank to keep it fresh.
- Make sure the fresh water system switch is "OFF" when leaving the boat unattended or when not in use.

Raw Water System

⚠ CAUTION

If the raw water inlet hose ruptures, turn pump off immediately. Close the thru-hull valve. If this condition is not quickly remedied severe damage and loss of life could occur.

Perform these routine maintenance procedures to maintain your raw water system:

- Check hoses for signs of deterioration, especially the sea water hoses.
- Remove and clean livewell, air conditioner and washdown pump sea water strainers, as needed. Spray pumps and thru-hull valves with a metal protector periodically.
- Drain and clean the fishboxes and livewells after each use.

- Operate all thru-hull valves at least once a month to keep them operating properly.

If a hose ruptures or leaks, turn off pump immediately. Keep the thru-hull valve closed when performing service on a sea water system.

NOTICE

Maintain a proper charge on the batteries; operating the pressure pump from a battery with a low charge could lead to pump failure.

The fresh and raw water systems must be winterized properly before storage. Refer to Winterizing.

Drainage Systems

Perform these routine maintenance procedures to maintain your drainage system:

- Clean the cockpit drain rails with a hose and water to remove all debris.
- Clean the hardtop leg drain holes, especially before winter storage.
- Clean the bilge pump and surrounding areas of any debris. Remove any debris that can block the function of the bilge pumps.
- Test rear automatic bilge pump switch and high water alarm float switch each time the boat is used, for proper operation. Activate the sensor by placing your finger on the black sensor switch on the aft end of the pump housing or add water to the bilge until the water level is high enough to activate the pump.
- Flush all gravity drains with fresh water to keep them clean and free flowing.
- When necessary, clean and inspect the shower and sink drain sump system. Remove accumulated debris and flush with fresh water. Test the automatic sump pump switch for proper operation, frequently.
- Clean and flush the fishbox and cooler/storage boxes with a mild soap or a bilge cleaner and fresh water after each use to keep them clean and fresh.
- Operate the thru-hull valves once a month and service as required.
- Check the drain system regularly to ensure it is free flowing and hoses on the thru-hull fittings are secure and not leaking.

NOTICE

DO NOT use harsh chemical drain cleaners in drain systems; permanent damage to the hoses, fittings and system can result. Also, drains and pumps must be properly winterized before winter lay-up.

Ventilation System

6.1 Cabin Ventilation

Ventilation is supplied by opening port lites or using the optional air conditioning system.

Port Lites

The port lites are secured by adjustable dogs. The dogs should be adjusted so they are tight enough to seal the window in the closed position, but not so tight that they are difficult to latch. The dogs are adjusted by turning a screw. The screw increases or decreases the pressure on each dog. The screen must be removed prior to closing the port light to ensure a water resistant seal.

6.2 Windshield Ventilation

The windshield vent is opened by moving the latch bar upward until the latch dogs clear the windshield frame. Make sure to fully engage the latches when in the fully opened or fully closed positions.

⚠ CAUTION

Operating the vent panel when the opening is obstructed may cause the glass to twist resulting in glass breakage or injury to people. Do not operate the opening vent unless it is clear of all obstructions.

6.3 Carbon Monoxide and Proper Ventilation

Read “Carbon Monoxide” in the Safety Section. It contains important information on carbon monoxide and the carbon monoxide detector.

6.4 Bilge Compartment Ventilation

Air flow into the bilge compartment is supplied by two vents located on the port side under the gunwale board.

6.5 Maintenance

- Periodically lubricate all hinges and latch assemblies with a light oil. And, clean and coat gasket materials with silicone to help keep them pliable.
- The opening cabin deck hatches and port windows are made of acrylic plastic. Acrylic can scratch easily. DO NOT use a dry cloth or glass cleaning solutions; use a soft cloth, mild soap, and water for routine cleaning. Solvents and products containing ammonia can permanently damage acrylic. Refer to Routine Maintenance for more information on the proper maintenance for acrylic.
- Carbon monoxide detectors have a limited life span. The End of Life (EOL) date, 5 years after the manufactured date, can be found on a sticker adhered to the body of the unit. Plan on replacing this unit prior to the EOL date comes. See the carbon monoxide detector manual for more information.

Operator Notes

Exterior Equipment

7.1 Deck

⚠ CAUTION

Unsecured open exterior doors and/or hatches can slam closed and cause injury or damage the boat. Most doors and hatches are equipped with fasteners, hatch lifters, snaps and/or straps to secure them open. Make sure they are properly secured while they are open.

Rails and Deck Hardware

Rails and deck hardware perform specific functions. Do not use for securing fenders or mooring lines; these must be secured to the cleats. Make sure mooring lines are clear of rails or stanchions, or damage can result.

DO NOT use cleats or any other hardware for the purpose of towing or being towed. Inspect all hardware periodically for loosening, wear or damage. Repair or replace immediately.

Anchor/Rope Locker

The anchor locker at the bow of the boat can be accessed through the deck hatch. The anchor locker is drained by a thru-hull fitting in the hull side near the bottom of the locker. Check it frequently and keep it clean and free flowing. Secure anchor chain when trailering or while underway.

Windlass

The windlass is located under the forward deck hatch above the rope locker. The anchor is stored on the anchor roller and is raised and lowered by the windlass. The anchor line is stored in the rope locker and routed out through the windlass to the anchor chain. The anchor locker is equipped with a receptacle for the windlass remote control.

Become familiar with the safe operation of the windless before using it. Refer to the windlass owner's manual for use of the windlass and remote control. The anchor is lowered by releasing the anchor from the cleat or chain snubber and activating the “Deploy” switch at the helm. After the anchor is set, do not allow the windlass to take the force from the anchor line; secure line to bow cleat.

NOTICE

DO NOT use windlass as the only method of securing anchor in the bow roller. Secure anchor line to a cleat or chain snubber before trailering or operating your boat.

Secure the anchor chain when trailering or while underway.

Become familiar with the safe operation of the windless before using it. Refer to the windlass owner's manual for use of the windlass and remote control.

The anchor is lowered by releasing the anchor from the cleat or chain snubber and activating the “Deploy” switch at the helm. After the anchor is set, do not allow the windlass to take the force from the anchor line; secure line to bow cleat. Secure anchor chain when trailering or while underway.

⚠ WARNING

MOVING PARTS OR ENTANGLEMENT HAZARD

Contact with moving parts can entangle, cut, resulting in loss of body parts, strangulation and/or severe loss of blood, causing serious injury or death. Stay clear of moving parts.

Boats at anchor in high swell conditions will snub on the anchor line. This can cause slippage or apply excessive loads to the windlass.



Anchor Line Secured Using Cable

DO NOT use the windlass as a winch to move the boat over the anchor. Move the boat under its own power to the anchor to break the anchor loose.

⚠ CAUTION

MOVING PARTS OR ENTANGLEMENT HAZARD

Contact with moving parts while operating the windlass can entangle, cut which can result in loss of body parts, strangulation and/or severe loss off blood, causing serious injury or death. Stay clear of moving parts.

The anchor is retrieved by releasing the line from the bow cleat and activating the "Retrieve" switch at the helm. Once the anchor is retrieved, secure the anchor to the chain snubber or bow cleat to prevent it from being released while underway.

Windshield

The DC 365 is equipped with an opening, heavy duty, aluminum windshield. The front and side wing panels are tempered safety glass. The vent window is provided with locks that secure the window in the open and closed position. The security of the vent window should always be verified before getting underway. The glazing can be replaced, similar to replacing automotive windshields.

⚠ CAUTION

To prevent injury or damage to the vent window or windshield the vent window must be secured when in either the open or closed position.

Hardtop

The hardtop consists of a fiberglass top supported by the windshield in the front and powder coated aluminum legs in the back. It is designed to accommodate radio antennas, radar antennas and navigation lights. It could also be equipped with optional outriggers and/or rod holders.

NOTICE

Care should be exercised to prevent damage to powder coated surfaces. If the surface is scratched, chipped or worn exposing the aluminum, it should be resealed to prevent corrosion from forming. If corrosion is allowed to form, it could cause the powder coating to bubble and lift away. Contact your dealer for repair service.

The hardtop is not designed to support the additional weight of items like an instrument locker or a life raft. Radar and electronics antennas must be mounted to the top

between the front and rear legs. Do not mount any antennas or equipment to the brow area. The hardtop frame is not designed to support the weight of accessories in this area and can be damaged. The starboard rear leg provides the chase for components mounted to the top.

The hardtop warranty will be voided if the top is modified in any way or heavy accessories are mounted to the top. Also, if items like radar antennas, spotlights and other accessories are mounted in the wrong location, the warranty can be voided. If you intend to add equipment or make modifications to the hardtop, contact Pursuit Customer Relations to make sure the equipment you would like to add or the intended modification will not void the warranty on the top.

Sun Roof

The hardtop is equipped with a sun roof. To operate, rotate the locking handle forward and move the sun roof to the desired position. Ensure that the locking pins are fully engaged into one of the five hole positions in the side track. Do not attempt to operate the sun roof while the vessel is underway. The sun roof is not designed to be weight bearing. Do not stand, sit or store items on top of it. Do not allow persons to sit on the open sun roof at any time.

Electric Sunshade (Optional)

The optional sunshade offers an extendable awning top to the aft end of the hardtop. This shade is deployed by the Shade switch at the helm. Care should be used when opening and closing to make sure that nothing is in the way.

⚠ CAUTION

Opening and closing the sunshade must be done with care. If items or hands are pinched while retracting serious injury could result. Make sure nothing is in the way when retracting.

The sunshade is not intended to be deployed while the boat is underway. If it is left deployed while the boat is underway damage could occur to the unit or the surrounding area.

NOTICE

Failure to stow the sunshade while underway could result in damage to the shade and the surrounding area.

Hardtop Canvas

Because the aluminum frames vary slightly, the side curtains and drop curtain are custom made to each boat at the factory. Slide the side curtains into the slide tracks on top of the windshield wings. Zip into the hardtop.

Snap the side curtains to the hardtop legs. The side curtains will have to be stretched slightly to pull out the wrinkles and reach the snaps.

Cold weather can make the clear vinyl material on the curtains stiff and difficult to stretch to the snaps. This can be particularly difficult with new canvas that has been stored off the boat. Lay the curtains in the sun for 30 minutes during the heat of the day to make installation easier in cold weather.

There is a rigging hole drilled in the starboard hardtop leg base to provide wire routing for accessories. A smaller hole is drilled in the tubing at the base of the other legs to allow water to drain. Keep the hardtop leg drains clean, especially before winter lay-up.

7.2 Cockpit

Swim Platform

Your Pursuit boat is equipped with port and starboard aft integrated boarding platforms. A foldaway boarding ladder is located in the aft corner of the port side boarding platform.

DO NOT use the boarding platforms or ladder while an engine is running. The engines must be “OFF” before allowing anyone to enter or exit the boat or when they are in the water.

Stow ladder before starting an engine.

⚠ DANGER

CARBON MONOXIDE POISONING AND/OR ROTATING PARTS HAZARD

Poisonous CO gases are present at the rear of the boat when an engine is running. A rotating propeller can cut or entangle swimmers. Both of these hazards will cause death or serious injury. DO NOT use the swim/boarding platform when the engine is running.

Cockpit Shower

A fresh water shower is located under the port side gunnel in the cockpit. It is supplied with hot and cold water by the fresh water system and works much like the shower in the head.

Side Boarding Door

Do not use or leave the hull side boarding door open when the boat is underway. DO NOT leave the hull side boarding door unlatched. To open the door, rotate the hand latch and swing the door open until it engages with the door stop catch. When closing the door, ensure that the latch is fully engaged with the latch plate.

Transom Door

Do not use the transom door when the boat is in motion. DO NOT leave the transom door unlatched. Latch it in the full “OPEN” or full “CLOSED” position.

⚠ WARNING

UNSAFE BOAT HAZARD

Failure to close and secure the side boarding door while underway can expose passengers to rotating propellers, throw them overboard or swamp the boat which can cause death or serious injury. Close and secure the side boarding door before getting underway.

NOTICE

Inspect transom door fittings periodically for wear, damage or loose fit. Repair or replace before using your boat.

Below Deck Fishbox

The fishboxes located in the cockpit are drained by a diaphragm pump located in the bilge. Pump out and clean the fishboxes after each use. Refer to Drainage Systems for more information on the fishbox drainage.

Aft Foldout Bench Seats


⚠ CAUTION

Keep clear of the seat mechanism when opening and closing. Injury could occur.

The aft and port side bench seats are hinged and open to provide additional seating space. To open, grasp both handles and pull outward from the stowed position. The seat will lock into its horizontal position. To stow,

lift the forward edge with the handles and return to the stowed position.

Cockpit Grill



Cockpit Grill

A 240/220V electric grill is installed in the cockpit. To use, turn on the cockpit grill breaker located on the cabin AC breaker panel. Temperature controls are located on the grill control panel behind the door below the grill. Open the door to access the grill control panel.

Turn the breaker off whenever the grill is not being used. The grill should not be used under or inside any kind of enclosure.

The grill must be allowed to cool before the cover is shut to avoid damage to the gel coated surfaces of the cover. Never clean the grill with any form of pressurized water or other types of cleaners. Use only a cloth and a stainless steel or glass surface cleaner. This grill like all appliances has the potential to create safety hazards through careless or improper use. Please observe all of the safety precautions listed in the grill manufacturer's owner's manual. Refer to the grill owner's manual.

⚠ CAUTION

Severe burns can occur from the improper use of the cockpit grill. Do not leave the grill unattended when is hot. Close supervision is required when the grill is being used or is hot. DO NOT use the grill while underway.

Cooler

A cooler plate is located under the seat. This unit can be controlled by the thermostat located under the seat.

Downriggers (Dealer Installed)

Downriggers must be installed on the deck area aft of the gunwale boards. DO NOT install or insert downriggers in the rod holders mounted in the gunwale boards; damage can occur.

Operator Notes

Interior Equipment

8.1 Companionway Door

The port cabin is accessed through the port cabin fiberglass door. A lockable latch secures the door in the closed position. There is also a latch mechanism on the inside of the door. This is used to open the door from the inside. A magnetic base located in the starboard side of the deck walkway is used to hold the door in the fully opened position. Rotate the door open until the two magnets engage. DO NOT leave the door opened and unlatched with the boat under way. Before operating the boat, latch the cabin door in the full “CLOSED” position.

⚠ CAUTION

Keep the port cabin door latched in the open or closed position. The door is heavy and can rotate closed easily. If the door is unlatched, it could rotate unexpectedly as the boat rocks, causing injury or damage.

8.2 Mid-Berth

The mid-berth is located aft of the port side cabin steps. There is a removable hatch below the berth cushion to provide access to the fresh water tank, fresh water pump, raw water washdown pump and forward bilge pump. Remove the starboard side outboard access panel to access the vacuum generator for the head system. The stereo amplifier, TV antenna control box and Fireboy® module are located in the aft port side cabinet.

8.3 Head Compartment

The head compartment is equipped with a tempered glass sink and a hot and cold faucet. An independent hot and cold shower mixer and wand are located within the shower enclosure. For care and cleaning information on the sink, refer to Routine Maintenance Section. An opening port light above the sink provides daylight and ventilation. An AC G.F.I. duplex outlet is also provided inside the vanity.

Marine Head System

Your boat is equipped with a VacuFlush® marine head system as standard equipment. This system uses a small amount of water and vacuum, which is generated by the 12-volt vacuum pump to flush. The toilet is connected to the pressurized fresh water system. Fresh water is used to reduce odor in the head compartment.

To use the toilet, make sure the “VacuFlush” breaker on the MDP is on; lift the foot flush lever slightly to wet the bowl with the desired water level. Depress the flush lever all the way for approximately three seconds or until the bowl is clear. A sharp popping noise is normal when the vacuum seal is broken and flushing action begins. It is also normal for a small amount of water to remain in the bowl after flushing.

The waste is directed to the holding tank until it is pumped out by a waste dumping station or the overboard macerator discharge system. The waste moves through a one-inch opening in the toilet base. Incoming air fragments mix with the waste as it passes through the base opening. This process eliminates the need for macerators or mechanical motors in the toilet base. When the tank is full, the tank monitor will show full and the vacuum pump will not run.

NOTICE

DO NOT operate the macerator dry; damage to the pump can occur.

The vacuum generator is mounted on the holding tank and contains stored vacuum. System vacuum is monitored by a vacuum switch, which is located on the vacuum generator tank. When the switch senses a drop in vacuum in the system, it automatically signals the pump to energize and bring the vacuum back to operating level. This process is

normally completed in less than two minutes.

It is normal for the stored vacuum to leak down slightly between flushes, causing the vacuum pump to run for a short period. The pump should not run more than once every three hours after the last flush for recharging the system. A holding tank fluid level monitor and macerator pump-out switch are located in a panel near the toilet. Refer to the head manufacturer owner's manual for more information on the operation of the marine head system.

Holding Tank

Monitor tank level and have it pumped out before it is completely full. If the tank is allowed to overfill, the waste will overflow out the tank vent and overboard.

Emptying the Holding Tank

When the tank is full, pump it out using an approved waste dumping station through the waste deck fitting or use the macerator discharge pump, when it is legal to do so.

NOTICE

In some waters it is illegal to discharge waste overboard. Remove the seacock handle or use another method to prevent accidental discharge.

To operate the macerator pump, open the ball valve at the thru-hull fitting. The thru-hull fitting and valve are accessed through the cockpit machinery space hatch. The valve is labeled MACERATOR DISCHARGE. Activate the macerator switch until the tank is empty. Release the switch and close the discharge ball valve when pumping is complete.

Maintenance

Clean and inspect the head for leaks regularly. Periodically add chemical to the head to help control odor and to chemically break down the waste. Refer to the head owner's manual for additional operating and maintenance information.

NOTICE

The head and macerator systems must be winterized before winter lay-up; refer to Winterizing.

8.4 Galley

Microwave Oven

A microwave oven is standard equipment. The microwave operates on AC power and is protected by a breaker on the AC panel. Refer to the microwave owner's manual for additional operating and maintenance information.


8.5 Carbon Monoxide Detector

The Safety Section in this manual contains important information on carbon monoxide and the carbon monoxide detector. Read section titled Carbon Monoxide.

8.6 Air Conditioner

Your boat is equipped with a cabin air conditioning unit. It is mounted inside the cabinet assembly inboard of the port cabin companionway stairs. It can be accessed through the forward facing centerline door in the midberth. If the optional cockpit air unit is installed it will be located under the helm seat.

These reverse cycle air conditioners can be operated to cool or heat. They are controlled by a thermostat and protected by a breaker in the AC breaker panel. To operate, turn the cabin or cockpit air conditioner switches to the "ON" position.



Cabin & Cockpit Air Controls

Set desired temperature and fan speeds using the control panels located in the cabin AC distribution panel. Refer to the owner's manual for more information and setting options.

The cold air return is located on the forward facing centerline access door to the cabin air conditioning unit in the mid-berth. There is also an adjustable cold air return in the forward berth. The port cabin has a non-adjustable return just aft of the microwave. The head has a non-adjustable cold air return adjacent to the cabin steps. Do not obstruct the return to obtain maximum efficiency from the air conditioner. Be careful when storing items in this compartment. Items stored next to the return can obstruct air flow and possibly damage the unit.

The air conditioner is self-contained and sea water cooled. The cooling pump supplies sea water to the unit and cools the condensing unit and is discharged overboard. The pump is located in the mechanical space. Sea water is supplied to the pump from a thru-hull fitting located in the hull near the pump. A sea strainer between the pump and thru-hull fitting protects the system from contaminants that can damage the pump or the air conditioning system. Periodically clean the sea strainer basket to make sure the sea water pump receives adequate water.

Air locks can occur in the cooling pump water supply at the time of launching. If your boat has been recently launched and water is not flowing from the overboard thru-hull when the air conditioner is activated, air may have to be purged from the system. This can be achieved by making sure the valve at the cooling pump intake thru-hull is open. Then run the boat at cruise speed for several minutes. This will pressurize the system and force the air through the pump. Refer to the air conditioner owner's manual for additional operating and maintenance information.

NOTICE

Air conditioners use surface water to cool. DO NOT operate the air conditioner out of the water or without the raw water supply or damage to the system will occur. Make sure there is a water supply before operating the air condition. No water supply can also trip the circuit breaker.

8.7 Audio and Video Systems

Stereo

The main stereo control unit is located at the console helm. The stereo can use an iPod® connection, an MP3 USB input, or a streaming Bluetooth® signal. A secondary remote is also located in the bow seating area for convenience. The remote can control several functions of the stereo, but not all. An optional satellite radio system, made up of a receiver and an antenna can be installed by a qualified electronics installer. Refer to the stereo owner's manual for additional operating information.

Stereo Amplifier

The stereo amplifier is located inside the port side aft cabin cabinet. To access, open the blank turn latch and open. The amplifier has controls to adjust the sound system response. Refer to the amplifier owner's manual for additional operating information.

TV

A flat screen TV is installed in the cabin. Refer to the TV owner's manual for additional operating information.

TV Antenna

A TV antenna is installed on the hardtop. The antenna has an amplifier box located in the aft port locker in the cabin. A red light on the antenna box indicates the antenna is activated.

Safety Equipment

9.1 General

Your boat and outboard engines have been equipped with safety equipment designed to enhance the safe operation of the boat and to meet U.S. Coast Guard safety standards. The Coast Guard or state, county, and municipal law enforcement agencies require certain additional accessory safety equipment on each boat. This equipment varies according to length and type of boat and type of propulsion. Most of the accessory equipment required by the Coast Guard is described in this Section. Some local laws require additional equipment. It is important to obtain “Federal Requirements And Safety Tips for Recreational Boats” published by the Coast Guard, and copies of state and local laws, to make sure you have the required equipment for your boating area. You should also read the book entitled “Sportfish, Cruisers, Yachts - Owner's Manual” included with this manual.

Your Pursuit boat could be equipped with engine alarms and cabin monitoring equipment. These systems are designed to increase your boating safety by alerting you to potentially serious problems in the primary power systems, the engine compartment and the cabin. Alarm systems are not intended to lessen or replace good maintenance and “Pre-Cruise System Check.”

This Section also describes safety related equipment that could be installed on your boat. This equipment will vary depending on the type of engines and other options installed by you or your dealer.

9.2 Engine Alarms

Most outboards are equipped with an audible alarm system mounted in the helm area that monitors selected critical engine systems. The alarm will sound if one of these systems begins to fail. Refer to the engine owner’s manual for information on the alarms installed with your engines and additional operating and maintenance information.

If the alarms sounds:

- throttle the engines back to idle immediately.
- shift to neutral.
- monitor the engine gauges to determine the cause of the problem.
- if necessary, shut off the engines and investigate until the cause of the problem is found.
- if the boat is equipped with water sensors in the fuel filters, make sure to check them for excessive water.

9.3 Neutral Safety Switch

Every throttle/shift control system has a neutral safety switch. The switch allows the engines to be started in NEUTRAL only. If engines will not start, make sure controls are in NEUTRAL. Control adjustments may be required to correct this condition should it persist. See your Pursuit Dealer for necessary control adjustments. Refer to the Plumbing Systems for more information on the neutral safety switch.

9.4 Engine Stop Switch

Your Pursuit boat is equipped with an engine stop switch, clip and lanyard. When the lanyard is pulled, it will shut off the engines.

⚠ WARNING

LOSS OF CONTROL AND UNSAFE BOAT HAZARD

An engine stop switch system that is not used or does not function correctly can cause death or serious injury. DO NOT operate the boat if the stop switch system does not function properly.

The stop switch will stop an engine whenever the lanyard is pulled far enough to disconnect the clip from the switch. Attach the lanyard to the boat operator whenever an engine is running, but be aware of loss of engine power if the switch is activated. If the operator is thrown from the seat, or moves

too far from the helm, the lanyard will disconnect the clip from the switch, shutting off the engine.

To attach a lanyard, connect the clip to the emergency stop switch and the hook to a strong piece of clothing on the operator, such as a belt loop.

If the engines will not start, the clip may not be inserted into the engine stop switch properly or the control is not in neutral. Make sure the clip is properly attached to the engine stop switch before attempting to start the engine.

Always carry a spare stop switch clip and lanyard and instruct at least one other person onboard the operation of the stop switch and location of the spare.

9.5 Automatic Fire Extinguishing System

⚠ WARNING

FIRE/EXPLOSION HAZARD
The gas of the fire extinguisher system displaces oxygen to "smother" the fire. DO NOT open the hatch. Oxygen can feed a fire and flashback can occur which can cause death or serious injury. If the onboard fire system discharges, wait at least 15 minutes before opening engine hatch.

The generator is equipped with an automatic fire extinguishing system. The extinguisher has been chosen and located to provide sufficient coverage of the generator compartment. While the system helps ensure bilge fire protection, it does not eliminate the U.S. Coast Guard requirement for hand held fire extinguishers.

The system is equipped with an engine shutdown circuit to automatically shut down the generator. The red light on the fire extinguisher control panel will light and an alarm will sound if this should occur. When sufficient time has elapsed for the fire to be extinguished and a flashback is no longer possible, find and fix the problem, then the override switch on the control panel can be moved to the "OVERRIDE" position and the engines can be restarted. Refer to the Automatic Fire Extinguisher System in the Plumbing Systems.

If the extinguisher system is activated, shut down all engines immediately. Turn off all electrical systems, powered ventilation and extinguish all smoking materials. DO NOT open the engine compartment hatch, this will feed oxygen to the fire and a flashback can occur. Allow the extinguishing agent to soak the generator compartment for at least 15 minutes and wait for hot metals or fuels to cool before inspecting for cause or damage. Have an approved portable fire extinguisher at hand and ready for use and DO NOT breathe fumes or vapors caused by the fire.

It is extremely important that you read, understand and know how this system works, refer to the manufacturer's literature.

9.6 Carbon Monoxide Hazards

⚠ DANGER

CARBON MONOXIDE HAZARD
Exposure to CO will cause death or serious injury. CO is colorless, odorless and extremely dangerous. Avoid CO exposure and make sure the CO detector is working properly.

Carbon monoxide (CO) poisoning is lethal and should not be confused with seasickness, intoxication or heat exhaustion. If someone complains of irritated eyes, headache, nausea, weakness or dizziness, or you suspect carbon monoxide poisoning, immediately move the person to fresh air, investigate the cause, and take corrective action. Seek medical attention if necessary.

All engines and fuel burning appliances produce CO as exhaust. Direct and prolonged exposure to CO will cause BRAIN DAMAGE or DEATH.

Other symptoms that may signal exposure to CO: dizziness, flushed face, ears ringing, headaches, tightness of chest or hyperventilation, drowsiness, fatigue or weakness, inattention or confusion, lack of normal coordination, nausea and unconsciousness. The victim's skin also may turn red. A slight buildup of CO in the human body over several hours causes headache, nausea and other symptoms similar to food poisoning, motion sickness or the flu. Anyone with these symptoms should immediately be moved to an area of fresh air. Have the victim breath deeply and seek immediate medical attention. To learn more about CO poisoning, contact your local health authorities.

Carbon Monoxide Detector

If the carbon monoxide detector is activated, this indicates the presence of CO, which can be fatal. Evacuate the cabin immediately. Make sure all passengers are accounted for. DO NOT enter the cabin until you know it is safe and the problem found and corrected.

CO detectors warn occupants of dangerous accumulation of CO gas. It is automatically activated whenever the house battery switch panel feed breaker is "ON." When powered, the green indicator will flash for ten to fifteen minutes, indicating the unit is in its warm-up stage. The green power indicator will stop flashing when the sensor has reached optimum operating temperature. The indicator will then switch from flashing green to solid green, indicating the detector is activate.

Make sure the battery switch is on and the power light is lit whenever the cabin is occupied.

This device uses a micro controller to continuously measure and accumulate CO levels. Should a very high level of CO exist, the alarm will sound within a few minutes. If small quantities are present or high levels are short-lived, the detector will accumulate the information and determine when an alarm level has been reached.

While a CO detector enhances your protection from CO poisoning, it does not guarantee it will not occur. Do not use CO detectors as a replacement for ordinary precautions or periodic inspections of equipment. Never rely on alarm systems to save lives; common sense is still the best form of protection. Remember, the boat operator carries the ultimate responsibility to make sure the boat is properly ventilated and passengers are not exposed to dangerous levels of CO. Be alert to the symptoms and early warning signs of carbon monoxide.

CO detectors are very reliable and rarely sound false alarms. If the alarm sounds, DO NOT think it is false. If anyone has been exposed to CO, move them into fresh air immediately. Never disable the CO detector because you think the alarm may be false.

Carbon Monoxide Poisoning

Carbon monoxide (CO) is a by-product of combustion, is invisible, tasteless, odorless and is produced by all engines and most heating and cooking appliances. It exists wherever fuels are burned to generate power or heat. The most common sources of CO on boats are combustion engines, auxiliary generators and propane or butane stoves.

These produce large amounts of CO and should never be operated while sleeping. High concentrations of CO can be fatal within minutes. Many cases of CO poisoning indicate that while victims are aware they are not well, they become so disoriented they are unable to save themselves by either exiting the area or calling for help. Also, young children, elderly persons and pets may be the first affected. Drug or alcohol use increases the effect of CO exposure. Individuals with cardiac or respiratory conditions are very susceptible to the dangers of CO. CO poisoning is especially dangerous during sleep while victims are unaware of any side effects.

Low levels of CO over an extended period of time can be just as lethal as high doses over a short period. Therefore, low levels of CO can cause the alarm to sound before persons notice any symptoms.

Contact the detector manufacturer, the Pursuit Customer Relations Department or your local fire department for assistance in finding and correcting the situation.

In certain situations, boats can have a problem due to the “station wagon effect” where engine exhaust fumes are captured in the vessel by the vacuum or low pressure area, usually the cockpit, bridge deck and cabin, that can be created by the forward speed of the boat. Boats that are underway should close all aft facing portholes, hatches and doors. The forward facing deck hatches should be open whenever possible to help pressurize living spaces of the boat. Sleeping, particularly in aft cabins, should not be permitted while underway. Proper ventilation must be maintained on the bridge deck by opening a forward window or windshield to drive fumes away from the occupants. The canvas drop or aft curtain must be removed and side curtains should be opened or removed to increase airflow and maintain proper ventilation whenever the engines are running.

DO NOT operate the engines with side curtains closed and the aft or drop curtain installed.

Use extreme caution while anchored or in a slip and an auxiliary power generator is operating. Calm wind nights can easily allow fumes to enter the boat. Inspect the exhaust systems of propulsion and the auxiliary generators, if equipped, frequently for possible leaks. High concentrations of CO in your boat can originate from an adjacent boat through open hatches or windows.

Failure to properly ventilate the boat while the engines are running can cause CO to accumulate within the cabin. Make sure to ventilate the boat and to avoid CO from accumulating in the boat whenever an engine is running.

Read the book entitled, “Sportfish, Cruisers, Yachts - Owner's Manual” and the owner's manual supplied by the CO detector manufacturer for additional information regarding the hazards and symptoms of CO gas, CO poisoning and operation instructions. If you did not receive these manuals, contact the Pursuit Customer Relations Department.

Read the book entitled, “Sportfish, Cruisers, Yachts - Owner's Manual” and the owner's manual supplied by the CO detector manufacturer for additional information regarding the hazards and symptoms of CO gas, CO poisoning and operation instructions. If you did not receive these manuals, contact the Pursuit Customer Relations Department.

Carbon monoxide detectors have a limited life span. The End of Life (EOL) date, 5 years after the manufactured date, can be found on a sticker adhered to the body of the unit. Plan on replacing this unit prior to the EOL date comes. See the carbon monoxide detector manual for more information.

9.7 First Aid

It is the boat operator's responsibility to be familiar with proper first-aid procedures and be able to care for minor injuries or illnesses of your passengers. In an emergency, you could be far from professional medical assistance, so be prepared. We recommend you be prepared by receiving training in basic first aid and CPR, through classes given by the Red Cross or your local hospital.



Equip your boat with at least a simple marine first-aid kit and a first-aid manual. The marine first-aid kit should be designed for the marine environment and be well supplied. Keep it accessible so each person onboard knows where it is located. As sup-

plies are used, replace them. Some common drugs and antiseptics can lose their strength or become unstable as they age. Ask a medical professional about the supplies you should carry and the safe shelf life of prescription drugs or other medical supplies you carry. Replace old supplies whether they have been used or not.

In many emergency situations, the Coast Guard can provide assistance in obtaining medical advice for treatment of serious injuries or illness. If you are within VHF range of a Coast Guard Station, make the initial contact on channel 16 and follow their instructions.

9.8 Required Safety Equipment

In addition to items installed by Pursuit, certain other equipment is required by the U.S. Coast Guard to help ensure passenger safety. Items like a sea anchor, working anchor, extra dock lines, flare pistol, life vests, a line permanently secured to your ring buoy, etc., could at some time save your passengers' lives, or save your boat from damage. Refer to the "Federal Requirements and Safety Tips for Recreational Boats" pamphlet for a more detailed description of the required equipment. You can also contact the U.S. Coast Guard Boating Safety Hotline, 800-368-5647, for information on boat safety courses and brochures listing the Federal equipment requirements. Also, check your local and state regulations.

The Coast Guard Auxiliary offers a "Courtesy Examination." This inspection will help ensure your boat is equipped with all of the necessary safety equipment.

The following is a list of the accessory equipment required on your boat by the U.S. Coast Guard:

Personal Flotation Devices (PFD's)

PFD's must be Coast Guard approved, in good and serviceable condition, and of appropriate size for the intended user. Wearable PFD's must be readily accessible, meaning you must be able to put them on in a reasonable amount of time in an emergency. Though not required, the Coast Guard emphasizes that PFD's should be worn at all times when the vessel is underway. Throwable devices must be immediately available for use. All Pursuit boats must be equipped with at least one Type I, II or III PFD for each person onboard, plus one throwable device (Type IV).

Visual Distress Signals

All Pursuit boats used on coastal waters, the Great Lakes, territorial seas, and those waters connected directly to them, must be equipped with Coast Guard approved visual distress signals. These signals are either Pyrotechnic or Non-Pyrotechnic devices.

Pyrotechnic Visual Distress Signals

Pyrotechnic visual distress signals must be Coast Guard approved, in serviceable condition and readily accessible. They are marked with a date showing the service life, which must not have expired. A minimum of three are required. Some pyrotechnic signals meet both day and night use requirements. They should be stored in a cool, dry location. They include:

- pyrotechnic red flares, hand held or aerial.
- pyrotechnic orange smoke, hand-held or floating.
- launchers for aerial red meteors or parachute flares.

Pyrotechnics are universally recognized as excellent distress signals. However, there is potential for injury and property damage if not handled properly. These devices produce a very hot flame and the residue can cause burns and ignite flammable material. Pistol launched and hand-held parachute flares and meteors have many characteristics of a firearm and must be handled with caution. In some states they are considered a firearm and prohibited from use. Make sure you are careful and follow the manufacturer's instructions when using pyrotechnic distress signals.

⚠ WARNING

FIRE/EXPLOSION HAZARD
Pyrotechnic signaling devices can cause fire and/or explosion, death, serious injury and property damage if misused. Follow the manufacturer's directions in the use of these signaling devices.

Non-Pyrotechnic Devices

Non-Pyrotechnic visual distress signals must be in serviceable condition, readily accessible, and certified by the manufacturer as complying with U.S. Coast Guard requirements. They include:

Orange Distress Flag, day use only.

The distress flag is a day signal only. It must be at least 3 x 3 feet with a black square and ball on an orange background. It is most distinctive when attached and waved from a paddle or boat hook.

Electric Distress Light, night use only.

The electric distress light is accepted for night use only and must automatically flash the international SOS distress signal. Under Inland Navigation Rules, a high intensity white light flashing at regular intervals from 50-70 times per minute is considered a distress signal.

Sound Signaling Devices

The navigation rules require sound signals to be made under certain circumstances. Recreational vessels are also required to sound fog signals during periods of reduced visibility. Therefore, you must have some means of making an efficient sound signal.

Navigation Lights

Recreational boats are required to display navigation lights between sunset and sunrise and other periods of reduced visibility (fog, rain, haze, etc.) Navigation lights are intended to keep other vessels informed of your presence and course. Your Pursuit boat is equipped with the navigation lights required by the U.S. Coast Guard at the time of manufacture. It is up to you to make sure they are visible, operational and turned on when required.

Fire Extinguishers

Pursuit Boats provides locations for two fire extinguishers on boats under 26 feet. Boats over 26 feet have provisions for up to three fire extinguishers. Boats equipped with cabins have one fire extinguisher located in the cabin, cockpit and helm areas. Center console boats have fire extinguishers mounted in the vicinity of the helm and passenger cockpit. Coast Guard approved fire extinguishers are hand-portable, either B-I or B-II classification and have a specific marine type mounting bracket. It is recommended the extinguishers be mounted in a readily accessible position.

Fire extinguishers require regular inspections to ensure:

- seals and tamper indicators are not broken or missing.
- pressure gauges or indicators read in the operable range.
- no obvious physical damage, corrosion, leakage or clogged nozzles.

For information on the type and size fire extinguisher required for your boat, refer to the "Federal Requirements and Safety Tips for Recreational Boats" pamphlet or contact the U.S. Coast Guard Boating Safety Hotline, 1-800-368-5647.

For instructions on the proper maintenance and use of your fire extinguisher, refer to the information provided by the fire extinguisher manufacturer.

Information for halon or agent FE-241 extinguishers is provided by the manufacturer. It is extremely important that you read, understand and know how this system works; refer to the manufacturer's literature.

Bilge and Fuel Fires

Fuel compartment and bilge fires or explosions are dangerous because of the presence of fuel. You must make the decision to fight the fire or abandon the boat. If the fire cannot be extinguished quickly or it is too intense to fight, abandoning the boat may be your only option. You must consider your safety, the safety of your passengers, the intensity of the fire and the possibility of an explosion in your decision.

If you find yourself in this situation, make sure all passengers have a life preserver on and go over the side and swim well upwind of the boat, to keep clear of any burning fuel that could be released and spread on the water as the boat burns or in the event of an explosion. When clear of the danger, check and account for all passengers who were onboard. Give whatever assistance you can to anyone in need or in the water without a buoyant device. Keep everyone together for morale and to aid rescue operations.

⚠ WARNING

BURN HAZARD

Fuel floating on water which is ignited can cause death or serious injury. Fuel will float on top of water and can burn. If the boat is abandoned, swim upwind, far enough to avoid fuel that can spread over the surface of the water.

9.9 Additional Safety Equipment

Besides meeting the legal requirements, prudent boaters carry additional safety equipment. This is particularly important if you operate your boat offshore. You should consider the following items, depending on how you use your boat.

Satellite EPIRB 'S

EPIRB's (Emergency Position Indicating Radio Beacon) operate as part of a world wide distress system. When activated, EPIRB's will send distress code homing beacons that allow Coast Guard aircraft to identify and find them quickly. The satellites that receive and relay EPIRB signals are operated by the National Oceanic and Atmospheric Administration (NOAA) in the United States. The EPIRB should be mounted and registered according to the instructions provided with the beacon, so the beacon's unique distress code can be used to quickly identify the boat and owner.

Additional Equipment to Consider:

- ❑ VHF Radio
- ❑ Life Raft
- ❑ Spare Anchor
- ❑ Spare Keys
- ❑ Heaving Line
- ❑ Fenders
- ❑ First Aid Kit
- ❑ Portable Radio
- ❑ Flashlight and Batteries
- ❑ Mirror
- ❑ Searchlight
- ❑ Sunburn Lotion
- ❑ Tool Kit
- ❑ Ring Buoy
- ❑ Whistle or Horn
- ❑ Anchor
- ❑ Chart and Compass
- ❑ Boat Hook
- ❑ Spare Propellers
- ❑ Mooring Lines
- ❑ Food and Water
- ❑ Binoculars
- ❑ Sunglasses
- ❑ Marine Hardware
- ❑ Extra Clothing
- ❑ Spare Parts

Operator Notes

Operation

10.1 General

Before you start, become familiar with the various component systems and their operation, and perform a “Pre-Cruise System Check.” A thorough understanding of the component systems and their operation is essential to operate the boat safely. This manual and the associated manufacturers’ information have been provided to enhance your knowledge of your boat. Read them carefully, and also, read the book titled “Sportfish, Cruisers, Yachts - Owner's Manual.”

Your boat must have the necessary safety equipment onboard and be in compliance with the U.S. Coast Guard, local and state safety regulations. There should be one Personal Floatation Device (PFD) for each person. Non-swimmers and small children should wear PFD's at all times. You should know and understand the “Rules of the Road” and have had an experienced operator brief you on the general operation of your new boat. At least one other person should be instructed on the proper operation of the boat in case the operator is suddenly incapacitated.

The operator is responsible for his safety and the safety of his passengers. When boarding or loading the boat, always step onto the boat, never jump.

⚠ WARNING

DROWNING OR LOSS OF CONTROL HAZARD

Ejection or sudden loss of control can cause death or serious injury from improper use of seating. DO NOT stand while driving above engine idle speeds and make sure cockpit seat is locked/secured and all passengers are seated when boat is underway.

DO NOT allow passengers to sit on the seat backs, gunwales, bows, transoms or on fishing seats whenever the boat is underway. Passengers should be seated to properly balance the load and must not obstruct the operator's view, particularly to the front.

Overloading and improper distribution of weight can cause the boat to become unstable and are significant causes of accidents. Know the weight capacity and horsepower rating of your boat. Do not overload or overpower your boat.

⚠ WARNING

OVERLOAD HAZARD

Overloading the boat beyond maximum load or altering the stability, buoyancy or center-of-gravity can result in death or serious injury. DO NOT exceed the maximum load or alter the center-of-gravity of the boat.

Remember, it is the operator's responsibility to use good common sense and sound judgment in loading and operating the boat.

⚠ WARNING

SLIPPERY SURFACE HAZARD

Wet surfaces can generate slippery conditions which can result in death or serious injury. Use caution on wet surfaces.

10.2 Homeland Security Restrictions

- Recreational boaters have a role in keeping our waterways safe and secure. Violators of the restrictions below can expect a quick and severe response.
- Do not approach within 100 yards, and slow to minimum speed within 500 yards of any U.S. Naval vessel. If you need to pass within 100 yards of a U.S. Naval vessel, for safe passage you must contact the U.S. Naval vessel or the Coast

Guard escort vessel on VHF-FM channel 16.
- Observe and avoid all security zones. Avoid commercial port areas, especially those that involve military, cruise-line or petroleum facilities. Observe and avoid other restricted areas near dams, power plants, etc.
- Do not stop or anchor beneath bridges or in channels.


America's Waterway Watch

America's Waterway Watch, a combined effort of the Coast Guard and its Reserve and Auxiliary, wants your help in keeping America's waterways safe and secure. America's Waterway Watch urges you to adopt a heightened sense of sensitivity toward unusual events or individuals you may encounter in or around ports, docks, marinas, riversides, beaches or waterfront communities. To report suspicious activities, call the National Response Center at 1-877-24WATCH or 1-800-424-8802. If there is immediate danger to life or property call 911 or call the Coast Guard on Marine channel 16.

10.3 Rules of the Road

As in driving an automobile, there are a few rules you must know for safe boating operation. The following information describes the basic navigation rules and action to be taken by vessels in a crossing, meeting or overtaking situation while operating in inland waters. These are basic examples and not intended to teach all the rules of navigation. For further information consult the "Navigation Rules" or contact the Coast Guard, Coast Guard Auxiliary, Department of Natural Resources, or your local boat club. These organizations sponsor courses in boat handling, including rules of the road. We strongly recommend such courses. Books on this subject are also available from your local library.

When two motor boats are crossing, the boat on the right has the right of way and should maintain its course and speed. The other vessel should slow down and permit it to pass. Both boats should sound appropriate signals.




⚠ CAUTION

Avoid collisions by following navigation rules. If a collision appears unavoidable, both vessels must act. Prudence takes precedence over right-of-way rules if a crash is imminent. Less maneuverable boats generally have the right of way. Steer clear of the right-of-way boat and pass to its stern.

When two motor boats are crossing, the boat on the right has the right of way and should maintain its course and speed. The other vessel should slow down and permit it to pass. Both boats should sound appropriate signals.

Crossing situations




* Response not sounded on International Waters

Meeting Head-On Or Nearly-So Situations

When two motorboats are approaching each other head-on or nearly head-on, neither boat has the right of way. Both boats should reduce their speed and turn to the right, passing port side to port side and provide enough clearance for safe passage. Both boats should sound appropriate signals.

Overtaking Situations

When one motorboat is overtaking another motorboat, the boat being passed has the right of way. The overtaking boat must make adjustments necessary to provide clearance for a safe passage of the other vessel and should sound appropriate signals.




The General Prudential Rule

In obeying the Rules of the Road, due regard must be given to all dangers of navigation and collision and to any special circumstances, including the limitations of the vessels, which may justify a departure from the rules that is necessary to avoid immediate danger or a collision.

Navigation Aids

Aids to navigation are placed along coasts and navigable waters as guides to mark safe water and to assist mariners in determining their position in relation to land and hidden dangers. Each aid to navigation is used to provide specific information. Become familiar with these and any other markers used in your boating area.



⚠ CAUTION

Storms and waves can move buoys, do not rely on buoys alone to determine your position.

10.4 Pre-Cruise Check

Before Starting The Engines:

- Check the weather forecast. Decide if your planned cruise can be made safely.
- Make sure all required documents are onboard.
- Make sure all necessary safety equipment is onboard and operative; items like running lights, spotlight, life saving devices, etc. Refer to Safety Equipment for additional information.

Each person onboard must have at least one personal flotation device onboard and one throwable device. Check the U.S. Coast Guard standards for the correct type required for your boat.

- Make sure signal kits are onboard and are in good operating condition and are not expired.
- Make sure you have sufficient water and other provisions for the planned cruise.
- Leave a written message listing details of your planned cruise (Float Plan) with a close friend ashore. Include a description of your boat, where you intend to cruise, schedule of your arrival in the cruising area and when you expect to return.
- Keep the person informed of any changes in your plan to prevent false alarms. This information can tell authorities where to look and your boat type in the event you fail to arrive.
- Check the amount of fuel onboard. Observe the “rule of thirds”: one third of the fuel for the trip out, one third to return and one third in reserve. An additional 15% may be consumed in rough seas.
- Check the water separating fuel filters for water.
- Turn on the battery switches.
- Check for bilge water and for other signs of potential problems. Monitor for the scent of fuel fumes.
- Test the automatic and manual bilge pump switches to make sure the system is working properly.
- Have a tool kit and spare parts onboard.

The kit should include basic tools:

- ❑ Spark Plug Wrench
- ❑ Hammer
- ❑ Spark Plug Gap Gauge
- ❑ Electrician’s Tape
- ❑ Screwdrivers
- ❑ Lubricating Oil
- ❑ Pliers
- ❑ Jackknife
- ❑ Adjustable Wrench
- ❑ Vise Grip Pliers
- ❑ Needle Nose Pliers
- ❑ Wire Crimping Tool
- ❑ End Wrench Set
- ❑ Wire Connector Set

The spare parts kit should include:

- ❑ Extra Light Bulbs
- ❑ Spark Plugs
- ❑ Fuses and Circuit Breakers
- ❑ Flashlight and Batteries
- ❑ Drain Plugs
- ❑ Engine Oil
- ❑ Propellers
- ❑ Fuel Filters
- ❑ Propeller Nuts
- ❑ Fuel Hose and Clamps
- ❑ Make sure all fire extinguishers are in position and in good operating condition.
- ❑ Make sure the shift control is in NEUTRAL.
- ❑ Make sure the emergency engine stop lanyard is attached to the operator and the stop switch.

10.5 Operating your Boat

The operator must be seated, and ready with the controls (steering/throttle) when the engine is started or running.

After Starting the Engines:

- Check engine gauges. Make sure all are reading normally.
- Visibly check engines to be sure there are no apparent water, fuel or oil leaks.
- Check operation of engine cooling systems.
- Check controls and steering for smooth and proper operation.
- Allow engines to warm up for 10 to 15 minutes before operating them above idle speeds.
- Make sure all lines, cables, anchors, etc. for securing the boat are onboard and in good condition. All lines should be coiled, secured and off the decks when underway.
- Have a safe cruise and enjoy yourself.

REMEMBER:

When operating a boat, you accept the responsibility for the boat, safety of passengers and others out enjoying the water.

- Alcohol and any mind altering chemicals can severely reduce your reaction time and affect your better judgment.
- Alcohol reduces the ability to react.
- Alcohol makes it difficult to judge speed and distance or track moving objects.
- Alcohol reduces night vision and ability to distinguish red from green.

STAY ALERT. The use of alcohol or any other mind altering chemicals that impair judgment, pose a serious threat to you and others. The boat operator is responsible for their consequences and behavior of passengers.

⚠ WARNING

IMPAIRED OPERATION HAZARD
Operating any boat while intoxicated or under the influence of other drugs can cause death or serious injury. DO NOT operate any boat under the influence of any mind-altering chemical.

Avoid sea conditions that are beyond the skill and experience of you and your crew.

Make sure at least one other person onboard is instructed in the operation of the boat and it is operated in compliance with all state and local laws.

DO NOT operate the boat unless it is completely assembled. Make sure all fasteners are tight and adjustments are to specifications.

Before operating the boat for the first time, read the engine break-in procedures. Refer to the engine owner's manual. Since different types of engines are used, have your dealer describe the operating procedures for your boat. For more instructions on "How to Operate the Boat," read the instructions given to you for your engines.

For more instructions on safety, equipment and boat handling, enroll in one of the several free boating courses offered. For information on the courses offered in your area, call the “Boating Safety Hotline,” 800-368-5647.

If the drive unit hits an underwater object, stop the engine. Inspect drive unit for damage. If damaged contact your dealer for a complete inspection and repair of the unit.

Stopping the Boat

- Allow engines to drop to the idle speed.
- Shift controls to NEUTRAL.

If the engines have been run at high speed for a long period of time, allow engines to cool by running at idle for 3 to 5 minutes.

- Turn the ignition keys “OFF.”
- Raise the trim tabs to full “UP” position.

NOTICE

Turn off engines at idle speed. Racing the engine before switching it off can draw water into the engine through the exhaust, resulting in internal damage.

After operation:

- If operated in saltwater, wash the boat and all equipment with soap and water. Flush the engines using fresh water. Refer to the engine owner's manual for instructions on flushing.
- Check the bilge area for debris and excess water.
- Fill the fuel tanks to near full to reduce condensation. Allow room in the tanks for the fuel to expand without being forced out the vent.
- Turn off all electrical equipment except the automatic bilge pumps.
- If you are going to leave the boat unattended for a long period of time, put the battery main switches to “OFF” and close all seacocks.
- Make sure the boat is securely moored.

NOTICE

To prevent damage, close all seacocks before leaving the boat.

10.6 Fishing

Fishing can be very exciting and distracting for the operator of the boat when the action gets intense. Be conscious that your primary responsibility is operating the boat safely to protect yourself, your passengers and other boats around you.

Make sure the helm is properly manned and is never left unattended while trolling.

If you are fishing in an area that is crowded with other fishing boats, it may be difficult to follow the rules of the road. This situation can become especially difficult when most boats are trolling. Be courteous and exercise good common sense. Avoid trying to assert your right of way and stay clear to preventing tangled or cut lines and other unpleasant encounters. Also, keep in mind that fishing line wrapped around a propeller shaft can cause damage to the lower unit seal.

10.7 Docking, Anchoring and Mooring

Docking and Docklines

Maneuvering a boat near a dock and securing it requires skill and techniques that are unique to water and wind conditions, and the dock layout. If possible, position a crew member at the bow and stern to assist with the lines and docking. While maneuvering close to the dock, compensate for wind and current, and anticipate how you can use them to help docking. Practice in open water using an imaginary dock to develop a sense for how the boat handles in different scenarios. You must be able to understand docking techniques before problems occur.

Approaching a dock or backing into a slip in high winds or strong currents requires skill. If you are new to handling a boat, take lessons

from an experienced pilot and learn to maneuver in tight quarters in less than ideal conditions. Also, practice away from the dock during windy conditions.

Dock lines are generally twisted or braided nylon. Nylon is strong and stretches to absorb shock. Nylon also has a long life and is soft and easy on the hands. The size of the line, will vary with the size of the boat. Typically a 30 to 40 feet boat will use 5/8-inch line and a 20 to 30 feet boat will use 1/2-inch line. The number of lines and their configuration will vary depending on the dock, the range of the tide, and other factors. Usually a combination of bow, stern and spring lines is used to secure the boat.

Maneuvering to the Dock

Approach the dock slowly at a 30 to 40 degree angle. When possible, approach against the wind or current. Turn the engines straight and shift to neutral when you feel you have enough momentum to reach the dock. Use reverse to slow the boat and pull the stern toward the dock as the boat approaches. If you approached properly, the boat will lightly touch the pilings at the same time forward momentum is stopped. Have the dock lines ready and secure the boat as soon at it stops. Use fenders to protect the boat while it is docked. Keep the engines running until the lines are secured.

Backing into a Slip

Approach the slip with the stern against the wind or current and the engines straight ahead. Use the engines and turn the steering wheel to maneuver the boat into alignment with the slip. Reverse the engines and slowly back into the slip. Shift from reverse to neutral frequently at idle to prevent the boat from gaining too much speed. Move the stern right and left by shifting the engines in and out of gear or turning the wheel. When nearly in the slip all the way, straighten the engines and shift to forward to stop. Keep the engines running until the lines are secured.

Securing Docklines

Securing a boat along side the dock typically requires a bow and stern line and two spring lines. The bow and stern lines are usually secured to the dock at a 40 degree angle aft of the stern cleat and forward of the bow cleat. The after bow spring line is secured to the dock at a 40 degree angle aft of the after bow spring cleat. The forward quarter spring is secured to the dock at a 40 degree angle forward of the stern cleat. The spring lines keep the boat square to the dock and reduce fore and aft movement while allowing the boat to move up and down with the tide.

Securing a boat in a slip is somewhat different. It typically requires two bow lines secured to pilings on each side of the bow, two stern lines secured to the dock and two spring lines that prevent the boat from hitting the dock. The bow lines are typically secured with enough slack to allow the boat to ride the tide. The stern lines are crossed. One line runs from the port aft boat cleat to the starboard dock cleat and the other line runs from the starboard aft boat cleat to the port cleat on the dock. The stern lines center the boat, control the forward motion and allow the boat to ride the tide. Two forward quarter spring lines typically are secured to the stern cleats and to mid ship pilings or cleats. The spring lines keep the boat from backing into the dock while allowing it to ride the tide.

Leaving the Dock

Start the engines and let them warm up for 10 to 15 minutes before releasing the lines. Boats steer from the stern and it is important you achieve enough clearance at the stern to maneuver the boat as quickly as possible. Push the stern off and maneuver to gain stern clearance quickly. Proceed slowly until the boat has cleared the dock and other boats.

Mooring

Approach the mooring buoy heading into the wind or current. Shift to neutral when you have just enough headway to reach the buoy. Position a crew member on the bow to retrieve the buoy with a boat hook and secure the line. Keep the engines running, until the line is secure.

Leaving a Mooring

Start the engines and let them warm up before releasing the mooring line. The boat will already be headed into the wind, so move it forward enough to loosen the line and untie it. Back the boat away until you can see the buoy and slowly move away.

Anchoring

Make sure the bitter end of the anchor rode is attached to the boat before dropping the anchor. Bring the bow into the wind or current and put the engine in neutral. When the boat comes to a stop, lower the anchor. Allow enough rode so that it is at least 5 to 7 times the depth of the water and secure the line to a cleat. Use caution to avoid getting your feet or hands tangled in the line. Additional scope of 10 times the depth may be required for storm conditions. Check landmarks on shore to make sure the anchor is not dragging. If it is dragging, start over. It is prudent to use two anchors if you are anchoring overnight or in rough weather.

⚠ WARNING

SINKING OR DROWNING HAZARD
Anchoring at the stern can pull a boat under water. DO NOT anchor at the stern.

Releasing the Anchor

Release the anchor by traversing to the point where the anchor line becomes vertical. It should release when you pass that point. If the anchor does not release, stop the boat directly above the anchor and tie the line to a cleat as tight as possible. The up and down movement of the boat will usually loosen the anchor. Make sure the anchor is secured and stowed before getting underway.

10.8 Controls, Steering or Propulsion System Failure

⚠ WARNING

MOVING PARTS HAZARD
Contact with moving parts can entangle, cut and cause death or serious injury. DO NOT come close enough to make contact with any running machinery moving parts, i.e., engine or propeller. Contact can result in loss of body parts, strangulation, burns and/or severe loss of blood resulting in serious injury or death.

The engine covers are machinery guards and must be in place whenever the engines are running. DO NOT operate the boat without the covers in place unless you are performing a check or maintenance.

If the propulsion, control or steering system fails while you are operating the boat, bring both throttles to idle and shift to neutral. Determine if the boat should be anchored to prevent the boat from drifting or to hold the bow into the seas. Investigate and correct the problem if possible. Make sure the engines are off before investigating the problem. If you are unable to correct the problem, call for help.

If only one engine has failed, you can operate on one engine. Do not to apply too much power to the running engine. When running one engine to power a twin engine boat, the engine is “over propped” and can be overloaded if too much throttle is applied. Contact your dealer or the engine manufacturer for the maximum power settings when running on one engine.

Collision

If your boat is involved in a collision with another boat, dock, piling or a sandbar, your first priority is to check passengers for injuries and administer first aid if necessary. Once all passengers' situations are stabilized, thoroughly inspect the boat for damage. Check below decks for leaks and all control systems for proper operation. Plug all leaks or make the necessary repairs to the control systems before proceeding. Operate slowly and carefully, but take all necessary precautions to be safe. Request assistance if necessary. Haul the boat and make a thorough inspection of the hull, lower unit and control system for damage.

10.9 Grounding, Towing and Rendering Assistance

The law requires the owner or operator of a vessel to render assistance to any individual or vessel in distress, as long as his vessel is not endangered in the process.

If the boat should become disabled, or if another craft that is disabled requires assistance, be careful. The stress applied to a boat during towing can become excessive. Excessive stress can damage the structure and create a safety hazard for all onboard.

Freeing a grounded vessel, or towing a disabled boat requires specialized equipment and knowledge. Line failure and structural damage caused by improper towing have resulted in fatal injuries. To safely accomplish the towing task, we recommend this to be reserved for those with the right equipment and knowledge, e.g., the U.S. Coast Guard or a commercial towing company.

The mooring cleats or bow/stern eyes on Pursuit boats are not designed or intended to be used for towing or lifting. These cleats are designed as mooring cleats for securing the boat to a dock, pier, etc. only. DO NOT use these fittings for towing, lifting or attempting to free a grounded vessel.

When towing operations are underway, have everyone on both vessels stay clear of the tow line and surrounding area. **DO NOT allow anyone to be in line with the tow rope; a dangerous, recoil can occur if the rope should break or pull free.**

Running aground can cause serious injury to passengers and damage the boat and its underwater gear.

If your boat runs aground, evaluate the damage, then proceed at low speed to the nearest service facility and have an immediate inspection made before further use. A damaged boat can also take on water; keep all life saving devices close while heading to a dock area. If the boat cannot be immediately removed from the water, thoroughly inspect the bilge area for leaks.

Flooding or Capsizing

Boats can become unstable if they become flooded or completely swamped. Always be aware of the position of the boat to the seas and the amount of water in the bilge. Water entering the boat over the transom can usually be corrected by turning the boat into the waves. If the bilge is flooding because of a hole in the hull, the engine bracket or a defective hose, you may be able to plug it with rags, close the thru-hull valve or assist the pumps by bailing with buckets. Put a mayday call into the Coast Guard or nearby boats and distribute life jackets as soon as you discover your boat is in trouble.

If the boat becomes swamped and capsizes, you and your passengers should stay with the boat as long as you can. It is much easier for the Coast Guard, aircraft, or other boats to spot, than people in the water.

Transporting your Boat

Your Pursuit boat is a large boat and should only be trailered by professionals with the right equipment and knowledge to transport large boats without causing damage. Contact your dealer or the Pursuit Customer Relations Department if you are planning to transport your boat and have any questions in regard to the proper equipment and support for the hull.

Damaged from trailers can occur if the boat hull is not supported properly. Make sure the trailer bunks and pads are adjusted so they provide enough support for the hull and are not putting excessive pressure on the lifting strakes. Hull damage resulting from improper trailer support is not covered by the Pursuit warranty.

Trailering your Boat

The boat trailer is an important part of your boating package. The trailer must be matched to the weight of the boat. A trailer with a capacity too low will be unsafe on the road and cause abnormal wear. A trailer with a capacity too high, can damage the boat. Contact your dealer to evaluate your towing vehicle and hitch, and to make sure you have the correct trailer for your boat.

NOTICE

Your Pursuit is heavy and the selection of your trailer is very important. We recommend using a bunk style trailer that incorporates a combination of heavy duty rollers to support the keel and long bunks running under and parallel to the stringers to support the hull. Trailers without bunks can cause damage and have a tendency to put extreme pressure points on the hull, especially on the lifting strakes. The situation worsens when launching or retrieving. Damage resulting from improper trailer support or the use a full roller trailer will not be covered by the Pursuit Warranty.

If you trailer your boat, make sure your tow vehicle is capable of towing the weight of the trailer, boat and equipment and the weight of the passengers and equipment inside the vehicle. This may require the tow vehicle to be specially equipped with a larger engine, transmission, brakes and trailer tow package.

The following safety tips and a book titled “Sportfish, Cruisers, Yachts - Owner's Manual,” provide additional information you should know before trailering your boat.

DO NOT use bow or stern eyes, cleats or any other hardware for the purpose of towing, being towed or lifting, they are not designed for that purpose.

Contact your dealer to evaluate your towing vehicle and hitch, and to make sure you have the correct trailer for your boat.

- Make sure the trailer is a match for the weight and hull design of the boat. More damage can occur by the stresses of road travel than by normal water operation. A boat hull is designed to be supported evenly by water. So, when it is transported on a trailer it should be supported as evenly across the hull as possible allowing for even distribution of the weight of the hull, engine and equipment.
- Make sure the trailer bunks and rollers properly support the hull and do not put pressure on the lifting strakes. The rollers and bunks must be kept in good condition to prevent scratching and gouging of the hull.
- The capacity rating of the trailer should be greater, but not to an extreme, than the combined weight of the boat, motor, and equipment. The gross vehicle weight rating must be shown on the trailer. Make sure the weight of the boat, engine, gear and trailer is not more than the gross vehicle weight rating.
- DO NOT use your boat and trailer as a means for hauling excess gear.
- Make sure the boat is securely fastened on the trailer to prevent movement between the boat and trailer. The bow rope, chain or turnbuckle in addition to the winch cable. Additional straps may be required across the beam of the boat. If these types of straps are used, protect your boat from chaffing or from the straps “slapping” the gelcoat. Cover area where straps are secured and twisting the straps before they are secured will help reduce the “slapping” affect. Your dealer can provide instructions on how to load, fasten and launch your boat.

Before Going out on the Highway:

- **Canvas Enclosures** - must be removed when trailering. Canvas enclosures will be damaged, they are not designed to withstand the extreme wind pressure encountered while trailering. Remove and properly store enclosures before trailering.
- **Tow Ball And Trailer Coupler** - make sure they are the same size and bolts and nuts are tightly secured.
- The coupler **MUST BE** completely over the ball and the latching mechanism **LOCKED DOWN**.
- **Load Trailer Evenly** - make sure load is evenly distributed from front to rear, as well as side to side and has the correct distribution of weight on the hitch. Too much weight on the hitch will cause the rear of the tow vehicle to drag and may make steering more difficult. Too little weight on the hitch will cause the rig to fishtail and will make controlling the tow vehicle difficult. Contact your Pursuit dealer or the trailer manufacturer for the correct weight on the hitch for your trailer.
- **Safety Chains** - attach crisscrossing under the coupler to the frame of the tow vehicle. If the ball breaks, the trailer would follow in a straight line and prevent the coupler from dragging on the road. Make sure the trailer emergency brake cable or chain is also installed to the tow vehicle frame.
- **Lights** - make sure they are functioning properly.
- **Brakes** - check on a level parking area; roll forward and apply the brakes several times at increasing speeds to determine if the brakes on the tow vehicle and trailer are working properly.
- **Side View Mirrors** - make sure the tow vehicle mirrors are large enough to provide an unobstructed rear view on both sides of the vehicle.
- **Tires and Wheel Bearings** - check before getting on the road.

Make sure your tow vehicle and trailer are in compliance with all state and local laws for the area you will be trailering. Contact your state motor vehicle bureau for laws governing the towing of trailers.

Water Skiing

Your Pursuit can be equipped for water skiing. If you have never pulled skiers, you should observe, learn and practice from an experienced driver. If you are an experienced driver, become familiar with the boat and the way it handles before pulling a skier. The driver should also know the ability of the skiers and drive accordingly. The following safety precautions should be observed while towing water skiers.

- Water ski only in safe areas, away from other boats and swimmers, out of channels and in water free of underwater obstructions and water ski only during daylight hours.
- Make sure that anyone who skis can swim. DO NOT allow people who cannot swim to water ski.
- Make sure all skiers wear a proper life jacket. A water skier is considered onboard the boat and a Coast Guard approved life jacket is required. A skier should wear a flotation device designed to withstand the impact of hitting the water at high speed. A second person must be onboard to observe the skier so your attention can be directed to the safe operation of the boat.
- Approach a skier in the water from the downwind side and STOP THE ENGINE and forward motion of the boat before coming in close proximity to the skier.
- Give immediate attention to a fallen skier. A fallen skier is very hard to see by other boats and is extremely vulnerable. When a skier falls, be prepared to turn the boat immediately and return to the skier. Never leave a fallen skier alone in the water for any reason.

For additional information on water skiing, including hand signals and water skiing manuals, contact the American Water Skiing Association - 863-324-4341 or visit their Web Site at www.usawaterski.org.

⚠ DANGER

CARBON MONOXIDE POISONING AND/OR ROTATING PARTS HAZARD
Poisonous CO gases are present at the rear of the boat when an engine is running. A rotating propeller can cut or entangle swimmers, both of these hazards will cause death or serious injury. DO NOT use the swim/boarding platform when the engine is running.

Remove and store the ladder properly before starting the engines.

Man Overboard

If someone falls overboard, be prepared to react quickly, especially when you are offshore. The following procedures will help you in recovering a person that has fallen overboard.

- Immediately stop the boat and sound a man overboard alarm and have all passengers point to the person in the water.
- Circle around quickly and throw a throwable PFD, cushion or life jacket to the person and if possible, another to use as a marker.
- Keep the person on the driver side of the boat to keep them in sight.
- Approach the person from the downwind side and maneuver the boat so the propellers are well clear of the person in the water.
- Turn off the engines when person is alongside and use a ring buoy or a boat cushion with a line attached, a paddle or boathook to assist person to the boat; make sure you do not hit them with the ring buoy or the boat.
- Pull person to the boat and assist onboard.
- Check person for injuries and administer first aid if necessary, if the injuries are serious, call for help immediately.

Refer to Safety Equipment for more information on first aid and requesting emergency medical assistance.

Trash Disposal

The discharge of plastic trash or trash mixed with plastic is illegal anywhere in the marine environment. It is also illegal to discharge garbage in the navigable waters of the United States including the great lakes.

Regional, State, and local restrictions on garbage discharges also may apply. Vessels of 26 feet or longer must display in a prominent location, a durable placard at least 4 by 9 inches notifying the crew and passengers of the discharge restrictions.

Responsible boaters store refuse in bags and disposed of it properly on shore. Make sure your passengers are aware of the local waste laws and the trash management procedure on your boat.

Routine Maintenance

11.1 General

⚠ WARNING

FIRE/EXPLOSION/ASPHYXIATION HAZARD

Cleaning agents and paint ingredients can be flammable and/or explosive, or dangerous to inhale. Make sure ventilation is adequate, wear proper personal protection and dispose of rags properly ashore.

Vapors from flammable solvents can cause fire, explosion or asphyxiation resulting in death or serious injury. Keep open flame or spark away from work area. DO NOT paint unless in a well-ventilated area.

Before using a cleaning product, refer to the product directions and specifications.

If urethane foam is used in the construction of your boat, be careful with high temperatures or flames in these areas. Urethane foam can ignite. DO NOT smoke, weld or burn. Avoid the use of space heaters and lights in areas where urethane foam is present. If ignited, urethane foam burns rapidly, produces extreme heat, releases hazardous gases and consumes much oxygen.

11.2 Exterior Hull and Deck

Hull Cleaning - Below the Waterline

When the boat is removed from the water, clean the outer bottom surface immediately. Algae, grass, dirt and other marine growth can be removed easier while the hull is still wet. Use a pressure cleaner or a hard bristle brush to clean the surface.

Bottom Painting

If the boat is to be left in the water for more than sixty (60) days in any ninety (90) day period an epoxy barrier coat should be applied to prevent blistering or osmosis prior to applying antifouling paint. Because of variations in water temperature, marine growth and pollution in different regions, your dealer and/or a qualified boat yard in your area should be consulted when deciding what bottom paint system to apply to your hull, because pollution and marine growth can damage fiberglass hulls.

Sanding or sandblasting the hull bottom will damage the fiberglass. Only use standard antifouling paints and fiberglass wax removers and primers recommended by the antifouling paint manufacturer when preparing the hull for bottom paint. Sanding or sandblasting and the use of a coating other than standard antifouling paint or epoxy barrier coatings are not recommended and will void the hull blister warranty.

DO NOT allow antifouling paint to contact the outboard engine. Most antifouling paints contain copper which will cause severe galvanic damage to the motor. Leave a 1/2 inch (12,7 mm) barrier between the hull bottom paint and outboard engine.

Most bottom paints require maintenance, especially when the boat is in saltwater or not used for extended periods, or after dry storage. If the hull bottom has been painted with antifouling paint, contact your dealer for the recommended maintenance procedures.

Sacrificial Anodes

Sacrificial zinc anodes are installed on the trim tabs, transom and outboard engines. The transom anode is connected to the bonding system and protects the underwater hardware that is bonded.

The anodes are less noble than copper based alloys and aluminum and will deteriorate first, protecting the more noble underwater hardware against galvanic corrosion. Anodes should be checked monthly and changed when they are 75% of their original size. When replacing the anodes, make sure the contact surfaces are clean, shiny metal and free of paint and corrosion. Never paint over the anode or protect it.

Boats stored in saltwater will require anodes to be replaced at least every 6 months to one year. Anodes requiring replacement more frequently may indicate a stray current problem within the boat or at the slip or marina. Anodes that do not need to be replaced after one year may not be providing the proper protection. Loose or low quality anodes could be the problem. Contact your dealer for the proper size and type of anodes to be used and the specific installation procedure.

Fiberglass Gelcoat Surfaces

Normal maintenance requires only washing with mild soap and water. A stiff brush can be used on the nonskid areas. Kerosene or commercially prepared products will remove oil and tar which could be a problem on trailered boats. DO NOT use harsh abrasive and chemical cleaners because they can damage or dull the gelcoat, reducing its life and making it more susceptible to stains. When the boat is used in saltwater, wash it thoroughly with soap and water after each use.

Sudden changes in temperature can affect gelcoat. When planning on moving your boat from outdoors to a heated location, allow the change of temperature to be gradual. Warm the location slowly after the boat is brought inside to allow the boat to change temperature slowly as the location is warmed. Or, if you are moving your boat from a warmer area to a colder one, wait for the temperature to be closer to the temperature of the warmer area or allow the warmer area and the boat to cool down.

At least once a season, wash and wax all exposed fiberglass surfaces. Use a high quality marine wax ONLY. Follow the procedure recommended by the wax manufacturer. Washing and waxing of your boat will have the same beneficial effects as they have on an automobile finish. The wax will fill minute scratches and pores which help prevent soiling and will extend the life of the gelcoat.

NOTICE

Use only a good quality marine wax (carnauba or equivalent). Never use a polymer or silicone based product on gelcoat surfaces as these products can cause irreparable damage and staining.

After the boat is exposed to the direct sunlight for a period of time, the color in the gelcoat tends to fade, dull or chalk from oxidation of the gel. This condition will be more apparent with dark colors, which require more frequent maintenance. A heavier buffing is required to bring the gelcoat back to its original luster. For power cleaning use a light cleaner. To clean the boat by hand, use a heavier automotive cleaner. Before cleaning the surfaces, read the instructions given with the cleaner. After cleaning the surfaces, apply wax and polish all fiberglass surfaces except the nonskid areas.

If the fiberglass should become damaged and need repair, contact your dealer for an authorized repair person to make the repairs.

⚠ WARNING

SLIPPERY SURFACE HAZARD
Cleaning surfaces can generate slippery conditions which can result in death or serious injury. Use caution when cleaning with detergents. Rinse thoroughly.

Be careful when walking on wet gelcoat surfaces.

DO NOT wax nonskid surfaces, these could make them slippery and increase the possibility of injury.

Stainless Steel Hardware

When using the boat in saltwater, wash hardware with soap and water after each use. When your boat is used in a higher corrosive environment, such as saltwater, water with a higher sulfur content or polluted water, stainless steel will periodically develop surface rust stains; this is normal under these conditions.

Clean and protect by using a high quality boat or automotive wax or a commercial metal cleaner and protectant.

DO NOT use citrus-based, abrasive materials such as sandpaper, bronze wool, or steel wool on stainless steel as damage will result.

Anodized Aluminum Surfaces

Wash periodically with soap and water to keep it clean. If the boat is used in saltwater or polluted water, wash with soap and water after each use. Saltwater allowed to remain on anodized aluminum will penetrate the anodized coating and attack the aluminum.

Hardtops with aluminum parts, bimini tops and towers with canvas and/or fiberglass tops require special attention to the anodized aluminum just below the top. This area is subject to salt build-up from salty condensation and sea spray. It is often overlooked when the boat is washed and will not be rinsed by the rain. The aluminum just below the top is more likely to become pitted than the exposed aluminum on the structure. Make sure these areas are washed frequently with soap and water and rinsed thoroughly. Pay particular attention to places where the top material and lacing contact the frame. Coat any anodized aluminum with a metal protector made for anodized aluminum once a month to protect against pitting and corrosion caused by the harsh effects of saltwater. The anodized aluminum used on your Pursuit was coated with a metal protector called Aluma Guard at the factory. Aluma Guard is a nonabrasive marine metal protector that protects anodized aluminum, stainless steel, brass and chrome. It also protects color anodizing from fading and discoloring due to harmful ultraviolet rays. Aluma Guard is available from your dealer or Rupp Marine Inc., 4761 Anchor Avenue, P.O. Drawer F, Port Salerno, FL 34992.

Aluma Guard and other metal protectors can make the metal slippery and should not be used on tower ladders, steering wheels and other areas for gripping or stepping.

Stains can be removed with a metal polish or fine polishing compound. To minimize corrosion, use a caulking compound to bed hardware and fasteners mounted to aluminum fabrications. If the anodized coating is badly scratched it can be touched up with paint. With proper care, anodized aluminum will provide many years of service.

Contact Pursuit Customer Relations before making any modifications to aluminum fabrications. Unauthorized modifications can void the warranty.

Powder Coated (Painted) Aluminum Surfaces

Regular care is necessary to maintain the appearance of the powder coat finish. Build-up of salt and grime can hold moisture and damage powder coatings. This buildup can cause a corrosive condition that can damage the coating, especially in a salt air or coastal environment.

- Wash the finish regularly with warm water containing a pH neutral detergent (i,e., mild dish soap).
- Use a non-abrasive fiber cloth.
- Rinse thoroughly after cleaning.

Chrome Hardware

Rinse with fresh water and wipe dry with towel or chamois after each use. Use a good chrome cleaner and polish on all chrome hardware. **Clean and wax chrome prior to extended storage. In saltwater or other harsh environments, clean and wax more often.**

Acrylic Plastic

Acrylic plastic scratches easily. DO NOT use a dry cloth or glass cleaning solutions on acrylic. Use a soft cloth and mild soap and water for routine cleaning. Solvents and products containing ammonia can permanently damage acrylic plastic.

Fine scratches can be removed with a fine automotive clear coat polishing compound. A coat of automotive or boat wax is beneficial to protect the surface.

DO NOT use the following on acrylic plastic:

- Abrasive cleaners
- Acetone
- Solvents
- Alcohol
- Glass cleaners
- Cleaners containing ammonia.

Engines

Proper engine maintenance is essential to performance and reliability of your outboard engines. Maintenance schedules and procedures are outlined in your engine owner's manual, follow them exactly.

Flush the system when the boat is out of the water. If the boat is used in saltwater, flush daily.

The age of gasoline can affect engine performance. Chemical changes occur as the gasoline ages, causing deposits and varnish in the fuel system and reduces the octane rating of the fuel. Degraded fuel can damage the engine and boat fuel tank and lines. If your boat does not require at least one full tank of fresh fuel a month, add a fuel stabilizer to the gasoline to protect the fuel from degradation. Use only a fuel stabilizer recommended by your dealer or the engine manufacturer. Operate the boat at least 15 minutes after adding the stabilizer to allow the treated fuel to reach the engine. Your dealer or engine manufacturer can provide additional information on fuel degradation. For more recommendations for your specific area, check with your local Pursuit dealer.

Avoid using fuels with alcohol additives. Gasoline, extended with an alcohol blend, will absorb moisture from the air which can reach such concentrations that “phase separation” can occur where the water and alcohol mixture becomes heavy enough to settle out of the gasoline to the bottom of the tank. Since the fuel pick-up tube is near the bottom of the tank, phase separation can cause the engine to run poorly or not at all. This condition is more severe with methyl alcohol and will worsen as the alcohol content increases. Water or a jelly like substance in the fuel filters is an indication of possible phase separation from the use of alcohol blended fuels.

Contact your Pursuit dealer or engine manufacturer for additional information regarding fuels and additives.

Corian® Surfaces

Corian® is resistant to heat, but you should always use a hot pad or a trivet with rubber feet to protect Corian®. Avoid exposing Corian® to strong chemicals, such as paint removers, oven cleaners, etc. If contact occurs, flush the surface with water immediately. Soapy water or ammonia-based cleaners will remove most dirt and stains from all types of finishes.

DO NOT use the Corian® countertop as a cutting board.

Minor damage, scratches, general or chemical stains, scorches or burns and minor

impact marks can be repaired on-site with a light abrasive cleanser and a product such as a Scotch-Brite® pad. For heavier damage, light sanding may be necessary. Heavy damage should be repaired by a Corian® licensed professional.

Tempered Glass Sink

For best results:

- DO NOT use strong/abrasive cleaner. Test your cleaning solution on an unnoticeable area first, before applying to the entire surface.
- Wipe surfaces clean, immediately after applying cleaner.
- DO NOT allow cleaner to sit or soak on the surface.
- DO NOT use an abrasive brush or scouring pad to clean surfaces as damage will occur. Use only a soft, dampened sponge and cloth.
- Rinse and wipe the fixtures to prevent soap build-up.

11.3 Seats, Upholstery, Canvas and Enclosures

Seat Slides and Swivel Bases

Perform the following periodically:

- Inspect and tighten mounting screws between seat slides and seat bottom.
- Inspect and tighten the mounting screws attaching seat bases to boat.
- Keep a light film of grease on manual seat slides.
- Keep a light film of grease on manual seat adjusting mechanism.
- Clean electric seat slides. DO NOT use harsh chemicals or abrasives. Lubrication is not required.

Vinyl Upholstery

The vinyl upholstery used on the exterior seats and bolsters should be cleaned with soap and water periodically. Stains, spills or soiling should be cleaned up immediately to prevent the possibility of permanent staining. When cleaning, rub gently. DO NOT use products containing ammonia, powdered abrasive cleaners, steel wool, strong solvents, acetone and lacquer solvents or other harsh chemicals as they can permanently damage or shorten the life of vinyl. Never use steam heat, heat guns or hair dryers.

Stronger cleaners, detergents and solvents may be effective in stain removal, but can cause either immediate damage or slow deterioration. Lotions, sun tan oil, waxes and polishes, etc., contain oils and dyes that can cause stiffening and staining of vinyls.

- **Dry soil, dust and dir**t - remove with a soft cloth.
- **Dried on dirt** - wash with a soft cloth dampened with water.
- **Variations in surface gloss** - wipe with a water-dampened soft cloth and allow to air dry.
- **Stubborn dirt** - wash with a soft cloth, dampened with Ivory Flakes® and water. Rinse with clean water.
- **Stubborn spots and stains** - spray with either Fantastik Cleaner® or Tannery Car Care Cleaner® and rub with a soft cloth. Rinse with clean water.
- **Liquid spills** - wipe with a clean absorbent cloth immediately. Rinse with clean water.
- **Food grease and oily stains** - spray with either Fantastik Cleaner® or Tannery Car Care Cleaner®, wiping with a soft cloth immediately. Be careful not to extend the area of contamination beyond its original boundary. Rinse with clean water.

Canvas and Side Curtains

Acrylic canvas should be cleaned periodically by using a mild soap and water. Scrub lightly and rinse thoroughly to remove the soap. Do not use detergents. The top or accessories should never be folded or stored wet.

After several years, the acrylic canvas may lose some of its ability to shed water. If this occurs, wash the fabric and treat it with a commercially available water proofing designed for this purpose. Some leakage at

the seams is normal and unavoidable with acrylic enclosures.

Side curtains and clear connectors can be cleaned with mild soap and water. Do not allow them to become badly soiled. Dirt, oil, mildew, and cleaning agents containing ammonia will shorten the life of the vinyl that is used for clear curtains. After cleaning the curtains and allowing them to dry, apply a non-lemon furniture polish or an acrylic plastic and clear plastic protector to extend the life of the curtains.

Vinyl curtains should be stored either rolled or flat, without folds or creases. Folding the curtains will make permanent creases that could cause the vinyl to crack.

DO NOT use any polish containing lemon or lemon scents; lemon juice attacks vinyl and shorten its life.

Lubricate snaps periodically with petroleum jelly or silicone grease. Lubricate zippers with silicone spray or paraffin.

Remove the bimini top, side curtains, clear connector, back drop and aft curtain when trailering. Canvas enclosures are not designed to withstand the extreme wind pressure encountered while trailering and will be damaged. Always remove and store properly before trailering.

11.4 Cabin Interior

Clean cabin interior just like you would clean a home interior.

- **Interior woodwork** - use damp cloth to wipe clean. A gentle furniture cleaner can be used for stubborn areas.
- **Bedding materials** - Most covers can be removed and cleaned outside the boat.
- **Ceramic stovetop** - Use damp cloth for minor spills. Use a cleaner designed for ceramic cooktops. Take care not to leave it on wood or Corian surfaces.
- **Corian** - Damp cloth. Do not use abrasive cleaners.

Air and sunlight are very good cleansers. Periodically, place cushions, sleeping bags, etc. on deck, under the sun and fresh air to dry and air out. If cushions or equipment get wet with saltwater, remove and use clean, fresh water to rinse off the salt crystals. Salt retains moisture and will cause damage. Dry thoroughly and reinstall.

If you leave the boat for a long period of time, put all cushions on their sides, open all interior cabin and locker doors, and hang a commercially available mildew protector in the cabin.

Read the label carefully on mildew protectors and remove the protector and allow the cabin to ventilate completely before using the cabin.

11.5 Bilge

To keep the bilge clean and fresh, use a commercial bilge cleaner regularly. Follow the directions carefully. All exposed pumps and metal components should be sprayed with a protector periodically to reduce the corrosive effects of the high humidity present in these areas.

⚠ WARNING

FIRE/EXPLOSION OR ASPHYXIATION HAZARD

Fumes from flammable solvents can cause fire, explosion or asphyxiation resulting in death or serious injury. DO NOT use flammable solvents to clean the bilge.

11.6 Generator (Optional)

The engine maintenance required on the generator is similar to an inboard engine. The engine incorporates a pressure-type lubrication system and a fresh water cooled engine block which is thermostatically controlled. The most important factors to the longevity of the generator is proper ventilation and maintenance of the fuel system, ignition system, cooling system, lubrication system and the AC alternator.

Maintenance schedules and procedures are outlined in the generator owner's manual; follow them exactly.

Operator Notes

Seasonal Maintenance

12.1 Storage and Lay-up

Before Hauling:

- Pump out the head. Flush the holding tank using clean soap, water, deodorizer and pump out cleaning solution.
- Leave the fuel tank nearly full to reduce condensation that can accumulate in the tank. Allow enough room for fuel to expand without leaking from the vents.
- Algae can grow in the accumulated water in diesel fuel tanks, especially in warm climates. Adding a high quality diesel fuel additive containing an algaecide may be required to control algae during storage in your area.
- Drain fresh water system.
- Refer to the engine owner's manual for detailed information on preparing the engines for storage.

Lifting

It is essential that care be used when lifting your boat. Make sure the spreader bar at each sling is at least as long as the distance across the widest point of the boat that the sling will surround. Put the slings in position. Refer to the drawing in the Schematics for the correct position of the lifting slings. The positions are marked with small labels on each side of the boat under the rubrails. Tie fore and aft slings together to prevent slings from sliding on the hull.

Elevating lifts are commonly used to store boats for extended periods. To provide proper support, the bunks that support the hull should be aligned with and run parallel to the hull stringers. The bow and stern eyes, if equipped should not be used as sole support for storage.

Your boat can be damaged from improper lifting and rough handling when being transported by lift trucks. Care and proper handling procedures must be used when using a lift truck to move your boat. DO NOT attempt to lift boat with a substantial amount of water in the bilge.

Severe gelcoat cracking or more serious hull damage can occur during hauling and launching if pressure is created on the gunwales (sheer) by the slings. Use flat, wide slings and spreaders long enough to keep pressure from the gunwales. DO NOT allow your boat to be hauled when the spreaders on the lift are not wide enough to take the pressure off the gunwales.

Supporting The Boat for Storage

A trailer, elevating lift or a well-made cradle is the best support for your boat during storage.

When storing the boat on a trailer for a long period:

- Make sure the rollers and pads support the hull of the boat and the trailer is on a level surface with the bow high enough so water will drain from the bilge and cockpit. The trailer must properly support the hull. The bunks and rollers should match the bottom of the hull and should not be putting pressure on the lifting strakes.
- Make sure the hitch is properly supported.
- Check the tires once each season. Add enough air for the correct amount of inflation for the tires.
- Make sure the engines are in the down position.

When storing the boat on a lift or cradle:

- The cradle must be specific for boat storage. Make sure lift or cradle is well supported with the bow high enough to provide proper drainage of the bilge. The cradle or lift must be in the proper fore and aft position to properly support the hull. When the cradle or lift is in the correct location, the bunks should match the bottom of hull and should not be putting pressure on the lifting strakes.
- Make sure the engines are in the down position.
- Make sure bunks and rollers are adjusted so they are not putting pressure on lifting strakes and are providing enough support for the hull. Hull damage

resulting from improper cradle or trailer support is not covered by the Pursuit warranty.

Preparing The Boat For Storage:

- Remove the bilge drain plug(s), if installed.
- Thoroughly wash fiberglass exterior, especially the antifouling portion of the bottom. Remove as much marine growth as possible. Lightly wax the exterior fiberglass components.
- Remove all oxidation from the exterior hardware and apply a light film of moisture displacing lubricant.
- Remove propellers and grease the propeller shafts using light waterproof grease.
- Remove batteries and clean using clear, clean water. Make sure batteries have sufficient water and terminals are clean. Keep the batteries charged and stored in a cool, dry place and safe from freezing throughout the storage period.
- Refer to the Electrical System for information on the maintenance of the AC and OS electrical systems.
- Coat all faucets and exposed electrical components in the cabin and cockpit with a protecting oil.
- Clean, drain and completely dry the fishboxes, sinks and livewells.
- Thoroughly clean the interior of the boat; clean all upholstery.
- Remove cushions, open the refrigerator/cooler door and as many locker doors as possible. Leaving as many of these areas open as possible will improve fresh air ventilation during the storage period.
- Place a mildew preventive system in the cabin area before it is closed for storage.
- Clean the exterior upholstery with a good vinyl cleaner and dry thoroughly. Spray the weather covers and boat upholstery with a spray disinfectant. Enclosed areas such as the refrigerator, shower basin, storage locker areas, etc. should also be sprayed with a disinfectant.

12.2 Winterizing

Fresh Water System

The entire fresh water system must be completely drained. Disconnect all hoses, check valves, etc. and blow all the water from the system. Make sure the water heater and fresh water tank are completely drained. Use very low air pressure only when blowing water from the system to prevent damage to components. The check valve mechanism built in the fresh water pump will not remove the water from the pump. Remove the outlet hose on the pump, turn it on and allow it to pump out any remaining water, approximately a cupful.

An alternate method is to use commercially available nontoxic, fresh water system antifreeze. After draining the potable water tank, lines and water heater, pour the antifreeze mixture into the fresh water tank, prime and operate the pump until the mixture flows from all fresh water faucets. Be sure to open ALL faucets, including the fresh water spray head in the cockpit and the water supply valve for the head. Make sure antifreeze has flowed through all of the fresh water drains. Allow the antifreeze to fill the sink traps to trap odors from the waste tank.

The shower/cabin drain sump system must be winterized also. Clean debris from the drain and sump and flush for several minutes with fresh clean water. After the system is clean, pump the drain sump as dry as possible. Then pour a potable water antifreeze mixture into the shower drain until antifreeze has been pumped through the entire system and out of the thru-hull.

For additional information, refer to Plumbing Systems.

Raw Water System

Drain the raw water systems completely. Disconnect all hoses and blow the water from the system. Use very low air pressure only when blowing water from the system to prevent damage to components. The check valve mechanism built in the raw water washdown pump, will not remove the water from the pump. Remove the outlet hose on the pump, turn it on and allow it to pump out any remaining water, approximately a cupful.

An alternate method is to use commercially available nontoxic, potable water system antifreeze. If antifreeze is used, pour the mixture into a pail and put the raw water intake lines into the solution. Run the pumps one at a time until the antifreeze solution is visible at all raw water faucets, discharge fittings and drains. Make sure antifreeze has flowed through all of the raw water drains.

Run the fishbox macerator pump until all the water is removed from the fishboxes and the pump. To avoid damage to the pump, DO NOT run pump dry for more than ten seconds.

Generator Raw Water Systems

Drain sea strainer, heat exchangers and raw water supply and discharge lines for the optional generator raw water supply pumps. Make sure all sea water has drained from the exhaust system. Some generator engine mufflers have a drain plug that must be removed to properly drain the muffler. Once this is accomplished, pour a nontoxic marine engine antifreeze mixture into a large pail and put the generator raw water intake lines into the solution. Run the generator until the antifreeze solution is visible at the exhaust port, then shut the engine off.

Winterize the generator engine and fuel system by following the generator manufacturer's winterizing procedures. Refer to generator's owner's manuals or contact a Pursuit dealer.

Marine Toilet

Winterize the marine toilet following the manufacturer's winterizing procedures; follow the procedures exactly. Refer to the toilet owner's manual. Drain the intake and discharge hoses completely using low air pressure if necessary. The head holding tank and macerator discharge pump must be pumped dry and one gallon of potable water antifreeze poured into the tank through the deck waste pumpout fitting. After the antifreeze has been added to the holding tank, open the overboard discharge valve and activate the macerator pump until the antifreeze solution is visible at the discharge thru-hull.

Air Conditioner (Optional)

Disconnect and drain the air conditioner intake and discharge hoses. Remove all water from the sea strainer and thru-hull fitting. Allow all water to drain from the system. An alternate method is the use of commercially available nontoxic, potable water system antifreeze. If antifreeze is used, drain the sea strainer and pour the mixture into a pail and put the raw water intake line into the solution. Run the air conditioner until the antifreeze solution is visible at the discharge fitting on the hull side.

Air conditioner components must be winterized also; follow winterizing procedure in the air conditioner owner's manual.

The air conditioning, engine control system, head, and steering systems have specific lay-up requirements. Refer to the owner's manuals for recommended winterizing procedures.

Bilge

Coat all metal components, wire busses, connector plugs (in the bilge), all strainers, seacocks and steering components with a protecting oil. The bilge pumps and bilge pump lines must be completely free of water and dried out when the boat is laid up for the winter in climates where freezing occurs. Compartments in the bilge that will not drain completely should be pumped out and then sponged until completely free of water. Dry the hull bilge and self-bailing cockpit troughs. Water freezing in these areas could cause damage.

Hardtop

Makes sure all drain holes in the legs are open and legs are completely free of water. Remove the canvas and thoroughly clean and store in a safe, dry place. Remove all electronics. Coat all wire connectors and bus bars in the helm compartment with a protecting oil.

Clean the powder coated frame with soap and water and dry thoroughly.

NOTICE

Make sure the leg drain holes are clear when the boat is laid up for the winter. Water trapped inside the hardtop, tower or radar arch legs can freeze and cause the legs to split.

Covering for Winter Storage

Proper storage is very important to prevent serious damage to the boat. If the boat is stored outside, support and secure a storage cover properly over the boat. It is best to have a frame built over the boat to support the cover. It should be a few inches wider than the boat so the cover will clear the rails and allow passage of air. If this cover is fastened too tightly there will be inadequate ventilation and can lead to mildew, moisture accumulation, etc. Fasten the cover down securely so wind cannot remove it or cause chafing of the hull superstructure. DO NOT store the boat in a damp storage enclosure. Excessive dampness can cause electrical problems, corrosion, and excessive mildew.

DO NOT use the factory canvas top in place of the winter storage cover. The life of these tops can be shortened if exposed to harsh weather elements for long periods.

DO NOT use an electric or fuel burning heating unit in the bilge area.

If the boat is to be stored indoors, make sure the building has enough ventilation and there is enough ventilation both inside the boat and around the boat. If the boat is to be stored indoors or outdoors, open all drawers, clothes lockers, cabinets, and doors a little. If possible, remove the upholstery, mattresses, clothing, and rugs.

12.3 Recommissioning

DO NOT operate the boat unless it is completely assembled. Keep all fasteners tight. Keep adjustments according to specifications.

Before launching the boat, make sure to install hull drain plug(s).

Reactivating the Boat After Storage:

- Charge and install the batteries.
- Install hull drain plug(s).
- Check the engines and generator for damage and follow the manufacturer's instructions for recommissioning.
- Check the mounting bolts of engines to make sure they are tight.
- Perform all routine maintenance.
- Check all hose clamps for tightness.
- Pump antifreeze from any systems winterized with antifreeze and flush several times with fresh water. Make sure all antifreeze is flushed from the water heater and it is filled with fresh water before it is activated.
- Check and lubricate the steering system.
- Clean and wash the boat.
- Install all upholstery, cushions and canvas.

After Launching:

- Check all water systems and the engine mounting bolts for leaks. Operate each system one at a time and check for leaks and proper operation.
- Check the bilge pump, manual and automatic switches.
- When the engines start, check the cooling system port below the engine cowling for a strong stream of water to ensure cooling pump is operating.
- Carefully monitor the gauges and check for leakage and abnormal noises.
- Operate boat at slow speeds until engine temperature stabilizes and all systems are operating normally.

Operator Notes

Glossary of Terms

Aft: In, near, or toward the stern of a boat.

Aground: A boat stuck on the bottom.

Amidships: In or toward the part of a boat midway between the bow and stern.

Anchor: A specially shaped heavy metal device designed to dig efficiently into the bottom under a body of water and hold a boat in place.

Anchorage: An area specifically designated by governmental authorities in which boats may anchor.

Ashore: On shore.

Astern: Behind the boat, to move backwards.

Athwartship: At right angles to the center line of the boat.

Barnacles: Small, hard-shelled marine animals which are found in salt water attached to pilings, docks and bottoms of boats.

Beam: The breadth of a boat usually measured at its widest part.

Bearing: The direction of an object from the boat, either relative to the boat's direction or to compass degrees.

Berth: A bunk or a bed on a boat.

Bilge: The bottom of the boat below the flooring.

Bilge Pump: A pump that removes water that collects in the bilge.

Boarding: Entering or climbing into a boat.

Boarding Ladder: Set of steps temporarily fitted over the side of a boat to assist persons coming aboard.

Boat Hook: Short shaft of wood or metal with a hook fitting at one end shaped to aid in extending one's reach from the side of the boat.

Bow: The front end of a boat's hull.

Bow Line: A line that leads forward from the bow of the boat.

Bow Rail: Knee high rails of solid tubing to aid in preventing people from falling overboard.

Bridge: The area from which a boat is steered and controlled.

Bridge Deck: A deck forward and usually above the cockpit deck.

Broach: When the boat is sideways to the seas and in danger of capsizing; a very dangerous situation that should be avoided.

Bulkhead: Vertical partition or wall separating compartments of a boat.

Cabin: Enclosed superstructure above the main deck level.

Capsize: When a boat lays on its side or turns over.

Chock: A deck fitting, usually of metal, with inward curving arms through which mooring or anchor lines are passed so as to lead them in the proper direction both onboard and off the boat.

Cleat: A deck fitting, usually of metal with projecting arms used for securing anchor and mooring lines.

Closed Cooling System: A separate supply of fresh water that is used to cool the engine and circulates only within the engine.

Coaming: A vertical piece around the edges of cockpit, hatches, etc. to stop water on deck from running below.

Cockpit: An open space, usually in the aft deck, outside of the cabin.

Companionway: Opening in the deck of a boat to provide access below.

Compartment: The interior of a boat divided off by bulkheads.

Cradle: A framework designed to support a boat as she is hauled out or stored.

Cutlass Bearing: A rubber bearing in the strut that supports the propeller shaft.

Deck: The floor-like platform of a boat that covers the hull.

Displacement: The volume of water displaced by the hull. The displacement weight is the weight of this volume of water.

Draft: The depth of water a boat needs to float.

Dry Rot: A fungus attack on wood areas.

Dry-dock: A dock that can be pumped dry during boat construction or repair.

Electrical Ground: A connection between an electrical connector and the earth.

Engine Beds: Sturdy structural members running fore and aft on which the inboard engines are mounted.

EPIRB: Emergency Position Indicating Radio Beacon. Operates as a part of a worldwide satellite distress system.

Even Keel: When a boat floats properly as designed.

Fathom: A measure of depth. One Fathom = 6 feet.

Fender: A soft object of rubber or plastic used to protect the topsides from scarring and rubbing against a dock or another vessel.

Fend off: To push or hold the boat off from the dock or another boat.

Flying Bridge: A control station above the level of the deck or cabin.

Flukes: The broad portions of an anchor which dig into the ground.

Following Sea: A sea that comes up from the stern and runs in the same direction that the boat is going.

Fore: Applies to the forward portions of a boat near the bow.

Foundering: When a boat fills with water and sinks.

Freeboard: The height from the waterline to the lowest part of the deck.

Galley: The kitchen of a boat.

Grab Rail: Hand-hold fittings mounted on cabin tops or sides for personal safety when moving around the boat, both on deck and below.

Ground Tackle: A general term including anchors, lines, and other gear used in anchoring.

Grounds: A boat touches the bottom.

Gunwale: The upper edge of a boat's side.

Hand Rail: Rail mounted on the boat, for grabbing with your hand, to steady you while walking about the boat.

Harbor: An anchorage which provides reasonably good protection for a boat, with shelter from wind and sea.

Hatch: An opening in the deck with a door or lid to allow for access down into a compartment of a boat.

Head: A toilet on a boat.

Heat Exchanger: Used to transfer the heat that is picked up by the closed cooling system to the raw cooling water.

Helm: The steering and control area of a boat.

Hull: The part of the boat from the deck down.

Inboard: A boat with the engine mounted within the hull of the boat. Also refers to the center of the boat away from the sides.

Inboard/outboard: Also stern drive or I/O. A boat with an inboard engine attached to an outboard drive unit.

Keel: A plate or timber plate running lengthwise along the center of the bottom of a boat.

Knot: Unit of speed indicating nautical miles per hour. 1 knot = 1 nautical mile per hour (1.15 miles per hour). A nautical mile is equal to one minute of latitude: 6076 feet. Knots times 1.15 equals miles per hour. Miles per hour times .87 equals knots.

Lay-up: To decommission a boat for the winter (usually in northern climates).

Leeward: The direction toward which the wind is blowing.

Length On The Waterline (l.w.l.): A length measurement of a boat at the waterline from the stern to where the hull breaks the water near the bow.

Limber Hole: A passage cut into the lower edges of floors and frames next to the keel to allow bilge water to flow to the lowest point of the hull where it can be pumped overboard.

Line: The term used to describe a rope when it is on a boat.

Lists: A boat that inclines to port or starboard while afloat.

L.O.A.: Boat length overall.

Locker: A closet, chest or box aboard a boat.

Loran: An electronic navigational instrument which monitors the boat's position using signals emitted from pairs of transmitting stations.

Lunch hook: A small light weight anchor typically used instead of the working anchor. Normally used in calm waters with the boat attended.

Midships: The center of the boat.

Marina: A protected facility primarily for recreational small craft.

Marine Ways or Railways: Inclined planes at the water's edge onto which boats are hauled.

Moored: A boat secured with cables, lines or anchors.

Mooring: An anchor permanently embedded in the bottom of a harbor that is used to secure a boat.

Nautical Mile: A unit of measure equal to one minute of latitude. (6076 feet)

Nun Buoy: A red or red-striped buoy of conical shape.

Outboard: A boat designed for an engine to be mounted on the transom. Also a term that refers to objects away from the center line or beyond the hull sides of a boat.

Pad Eye: A deck fitting consisting of a metal eye permanently secured to the boat.

Pier: A structure which projects out from the shoreline.

Pile or Piling: A long column driven into the bottom to which a boat can be tied.

Pitching: The fore and aft rocking motion of a boat as the bow rises and falls.

Pitch: The measure of the angle of a propeller blade. Refers to the theoretical distance the boat travels with each revolution of the propeller.

P.F.D: Personal Flotation Device.

Port: The left side of the boat when facing the bow.

Porthole (port): The opening in the side of a boat to allow the admittance of light and air.

Propeller: A device having two or more blades that is attached to the engine and used for propelling a boat.

Propeller Shaft: Shaft which runs from the back of the engine gear box, aft, through the stuffing box, shaft log, struts, and onto which the propeller is attached.

Pyrotechnic Distress Signals: Distress signals that resemble the brilliant display of flares or fireworks.

Raw Water Cooled: Refers to an engine cooling system that draws sea water in through a hull fitting or engine drive unit, circulates the water in the engine, and then discharges it overboard.

Reduction Gear: Often combined with the reverse gear so that the propeller turns at a slower rate than the engine.

Reverse Gear: Changes the direction of rotation of the propeller to provide thrust in the opposite direction for stopping the boat or giving it sternway.

Roll: A boat's sideways rotational motion in rough water.

Rope Locker: A locker, usually located in the bow of a boat, used for stowing the anchor line or chain.

Rubrail: Railing (often rubber or hard plastic) that runs along the boat's sheer to protect the hull when coming alongside docks, piers, or other boats.

Rudder: A moveable flat surface that is attached vertically at or near the stern for steering.

Sea anchor: An anchor that does not touch the bottom. Provides drag to hold the bow in the most favorable position in heavy seas.

Scupper: An opening in the hull side or transom of the boat through which water on deck or in the cockpit is drained overboard.

Seacock: Safety valves installed just inside the thru-hull fittings and ahead of the piping or hose running from the fittings.

Shaft Log: Pipe through which the propeller shaft passes.

Sheer: The uppermost edge of the hull.

Sling: A strap which will hold the boat securely while being lifted, lowered, or carried.

Slip: A boat's berth between two pilings or piers.

Sole: The deck of a cockpit or interior cabin.

Spring Line: A line that leads from the bow aft or from the stern forward to prevent the boat from moving ahead or astern.

Starboard: The right side of a boat when facing the bow.

Steerageway: Sufficient speed to keep the boat responding to the rudder or drive unit.

Stem: The vertical portion of the hull at the bow.

Stern: The rear end of a boat.

Stow: To pack away neatly.

Stringer: Longitudinal members fastened inside the hull for additional structural strength.

Strut: Mounted to the hull which supports the propeller shaft in place.

Strut Bearing: See “cutlass bearing.”

Stuffing Box: Prevents water from entering at the point where the propeller shaft passes through the shaft log.

Superstructure: Something built above the main deck level.

Swamps: When a boat fills with water from over the side.

Swimming Ladder: Much the same as the boarding ladder except that it extends down into the water.

Taffrail: Rail around the rear of the cockpit.

Thru-hull: A fitting used to pass fluids (usually water) through the hull surface, either above or below the waterline.

Topsides: The side skin of a boat between the waterline or chine and deck.

Transom: A flat stern at right angles to the keel.

Travel Lift: A machine used at boat yards to hoist boats out of and back into the water.

Trim: Refers to the boat's angle or the way it is balanced.

Trough: The area of water between the crests of waves and parallel to them.

Twin-Screw Craft: A boat with two propellers on two separate shafts.

Underway: When a boat moves through the water.

Wake: Disrupted water that a boat leaves astern as a result of its motion.

Wash: The flow of water that results from the action of the propeller or propellers.

Waterline: The plane of a boat where the surface of the water touches the hull when it is afloat on even keel.

Watertight Bulkhead: Bulkheads secured so tightly so as not to let water pass.

Wharf: A structure generally parallel to the shore.

Working Anchor: An anchor carried on a boat for most normal uses. Refers to the anchor used in typical anchoring situations.

Windlass: A winch used to raise and lower the anchor.

Windward: Toward the direction from which the wind is coming.

Yacht Basin: A protected facility primarily for recreational small craft.

Yaw: When a boat runs off her course to either side.

Operator Notes

Maintenence Schedule

Maintenance	Each Use	Weekly	Monthly	Semi-Annually	Yearly	As Nedeed
Clean hull below the waterline				X		
Bottom paint					X	X
Check sacrificial anodes			X			
Replace sacrificial anodes					X	
Wash boat canvas& hardware	X		X			
Wax exterior gelcoat				X		X
Clean & protect hardware						X
Polish & protect plastic glass					X	X
Clean exterior upholstery	X					X
Clean cabin & interior upholstery						X
Flush engine with fresh water	X					
Spray metal components in bilge with a protector			X			
Clean bilge				X		X
Check bilge for leaks	X		X			
Inspect & operate thru-hull valves			X			
Inspect steering & control systems	X					
Service steering & control systems				X		
Inspect fuel system for leaks	X					
Inspect & service fuel system				X		
Inspect fuel tank vents & screens					X	
Replace fuel filters					X	
Lubricate fuel fill O-rings			X			
Inspect fire extinguisher			X			
Test bilge pump auto switches	X					
Inspect & protect electrical components, wire & battery connections				X		
Check battery electrolyte & service			X			
Test and inspect AC electrical system & shore power cord				X		
Inspect water systems for leaks				X		
Check neutral safety switch	X					
Check trim tab operation			X			

Maintenance Log

Date	Hours	Dealer	Service/Repairs

Date	Hours	Dealer	Service/Repairs

Date	Hours	Dealer	Service/Repairs

Boating Accident Report

DEPARTMENT OF HOMELAND SECURITY
U.S. Coast Guard
RECREATIONAL BOATING ACCIDENT REPORT

OMB Control Number: 1625-0003
Expires: 12/31/2015

INSTRUCTIONS: Use "Report required because" section below to determine if a report is required for your accident. If required, please have each vessel owner or operator involved in the accident submit a report to their state reporting authority. Each boat operator/owner involved in an accident should submit a separate report. For each question below, please provide answers if applicable and if known; otherwise leave blank. Privacy Act Notice: Authority- 46 U.S.C. 6102 and 33 CFR 173 & 174 authorize the collection of information on boating accidents. Purpose-The Coast Guard uses this information for statistical purposes, chiefly to inform the public, to measure the Program's efforts, and to regulate issues relating to boating safety. Routine Uses-The Coast Guard shares this information within the agency, and if state and federal law permit it, to the public.

REPORT SUBMISSION

Report required because *(select all that apply):*

- ☐ At least one person in this accident *died*: If so, how many? _____
- ☐ At least one injured person in this accident *required or was in need of treatment beyond first aid*: If so, how many? _____
- ☐ At least one person in this accident *disappeared* and has not yet been recovered: If so, how many? _____
- ☐ *All* boat and other property *damage (e.g., fishing/hunting gear)* caused by this accident *totaled (or likely totaled)* $2,000 or more:
  - Approximate value of damage to *your* boat: $_____
  - Approximate value of damage to *your* other property: $_____
- ☐ Your or another *boat* in this accident was *(or likely was)* a *total loss*

Report submitted by *(select all that apply)*:

- ☐ Boat Operator *(required if possible)*
- ☐ Boat Owner *(if operator unable, or same as operator)*
- ☐ Other *(describe)*: _____

To be submitted within:

48 hours *(if injury, disappearance or death)*
10 days *(if boat/property damage only)*

To be submitted to: *(Local State Reporting Authority)*

Phone:

You may submit any comments concerning the accuracy of the burden estimate or any suggestions for reducing the burden to: Commandant (CG-5422), U.S. Coast Guard, Washington, DC 20593-0001 or Office of Management and Budget, Paperwork Reduction Project (1625-0003), Washington, DC 20503. Questions relating to the collection of this data should be sent to the Coast Guard.

For State Agency Use Only

First Name	*Last Name*
Phone:	

First Name	Last Name	Phone	*Primary Cause of Accident*

ACCIDENT SUMMARY

WHEN

Date: *(mm/dd/yyyy)* Time: am ☐ pm ☐ *(select one)*

WHERE

Body of Water Name

Location *(on water)* description

Nearest city/town

County: State:

***YOUR* BOAT – PEOPLE**

# people *on board (including operator)*:	
# people *being towed (e.g., on tubes, skis)*:	
# people *wearing lifejackets (on board or towed)*:	

***OTHER* BOATS INVOLVED IN ACCIDENT**

# of *other* boats involved:	

ACCIDENT DESCRIPTION: *Briefly* describe this accident *(attach extra pages if necessary)*

DAMAGE TO *YOUR* BOAT: *Briefly* summarize any damage to your boat

DAMAGE TO *YOUR* OTHER PROPERTY: *(NOT BOAT)*
Briefly summarize any damage to your other property *(not boat)*

CG-3865 (6/13)

Reset

For each question below, please provide answers IF APPLICABLE AND IF KNOWN, otherwise leave blank.

YOUR BOAT

BOAT IDENTIFICATION

Your Boat Name:	Manufacturer:
Model Name:	Model Year:
Registration #:	Documentation #:
Hull Identification # *(HIN)*	Rented: ☐ Yes ☐ No

SIZE ESTIMATES

Length: ft.	Depth from transom *(stern)* to keel *(bottommost point)*: ft. in.	Beam width at widest point: ft.

HULL MATERIAL

Type of Hull Material *(select one)*

☐	Fiberglass	☐	Wood	☐	Rubber/vinyl/canvas	☐	Other *(describe):*
☐	Aluminum	☐	Steel	☐	Plastic		

BOAT TYPE

Boat Type *(select one)*

☐	Cabin motorboat	☐	Inflatable	☐	Canoe	☐	Personal watercraft *(PWC) (e.g., Wave Runner™, Jet Ski™, Sea-Doo™)*
☐	Open motorboat	☐	Houseboat	☐	Rowboat		
☐	Auxiliary sail	☐	Sail *(only)*	☐	Air boat	☐	Other *(describe)*
☐	Pontoon boat	☐	Kayak				

Available Propulsion *(select all that apply)*

☐	Propeller	☐	Air thrust
☐	Sail	☐	Other *(describe):*
☐	Manual		
☐	Water jet		

ENGINE

# Engines	**Engine type and horsepower** *(select one)*								**Fuel type** *(select all that apply)*						
Manufacturer	☐	Outboard	☐	Sterndrive *(I/O)*	☐	Inboard	☐	None	☐	Gasoline	☐	Diesel	☐	Electric
	Total horsepower: hp													

SAFETY MEASURES

Organizations that have conducted a vessel safety check *(VSC)* on board your boat within the past year *(including carriage of safety equipment, e.g., lifejackets, anchor and line, fire extinguishers):*

US Coast Guard Auxiliary: VSC Decal? ☐ Yes ☐ No		☐	Federal Agency *(Name)*		
US Power Squadrons: VSC Decal? ☐ Yes ☐ No		☐	State Agency (*Name)*		
		☐	Other Agency *(Name)*		

# Life jackets on board:		# Fire extinguishers on board:		Type of fire extinguishers *(e.g., ABC)*:	
		# Fire extinguishers used:		Amount of fire extinguishers used:	

ACCIDENT DETAILS – EXTERNAL CONDITIONS

WEATHER

Overall weather was *(select one)*				**It was** *(select one)*		**Visibility was** *(select one)*		**Wind was** *(select one)*	
☐	Clear	☐	Raining	☐	Day	☐	Good	☐	0 mph *(none)*
☐	Cloudy	☐	Snowing	☐	Night	☐	Fair	☐	Over 0, up to 12 mph *(light)*
☐	Foggy	☐	Hazy			☐	Poor	☐	Over 12, up to 25 mph *(moderate)*
☐	Other *(describe):*			Approximate air temperature:	°F			☐	Over 25, up to 55 mph *(strong)*
☐								☐	Over 55 mph (stormy)

WATER

Overall water conditions *(select one)*:		**Other water conditions:**				
☐	Up to 6 in. waves *(calm)*	Approximate water temperature:	°F			
☐	Over 6 in., up to 2 ft. waves *(choppy)*	Strong current?	☐	Yes	☐	No
☐	Over 2 ft., up to 6 ft. waves *(rough)*	Hazardous waters? *(e.g., rapid tidal flow, currents)*	☐	Yes	☐	No
☐	Over 6 ft. waves *(very rough)*	Congested waters?	☐	Yes	☐	No

Reset

For each question below, please provide answers IF APPLICABLE AND IF KNOWN, otherwise leave blank.

ACCIDENT DETAILS – ACTIVITIES AND OPERATIONS ON *YOUR* BOAT

OPERATOR/PASSENGER ACTIVITIES

Operator/passenger activities on *your* boat at time of accident:

Activities were *(select one)*

- ☐ Recreational
- ☐ Commercial

Operator/Passenger activities *(select all that apply)*

☐ Fishing	☐ Tubing	☐ Starting engine	
☐ Hunting	☐ Water Skiing	☐ Making repairs	
☐ White water activity *(e.g., rafting)*	☐ Relaxing	☐ Other *(list):*	

BOAT OPERATIONS

***Your* boat operations at time of accident** *(select all that apply)*

☐ Cruising *(underway under power)*	☐ Drifting	☐ Racing	☐ Towing another vessel
☐ Changing direction	☐ At anchor	☐ Rowing/paddling	☐ Launching
☐ Changing speed	☐ Being towed	☐ Docking/undocking	☐ Tied to dock/mooring
☐ Sailing	☐ Other *(list)*		

ACCIDENT DETAILS – CONTRIBUTING FACTORS ON *YOUR* BOAT

CONTRIBUTING FACTORS

Indicate factors on *your* boat which may have contributed to this accident *(select all that apply)*

☐ Alcohol use	☐ Improper lookout	☐ Dam/lock	☐ Starting in gear
☐ Drug use	☐ Operator inattention	☐ Force of wake/wave	☐ Sharp turn
☐ Excessive speed	☐ Operator inexperience	☐ Hazardous waters	☐ Restricted vision *(e.g., fog)*
☐ Improper anchoring	☐ Language barrier	☐ Heavy weather	☐ Mission/inadequate aids to navigation *(e.g., buoy, daymarker)*
☐ Improper loading	☐ Navigation rules violation	☐ Ignition of fuel or vapor	☐ Inadequate on-board navigation lights
☐ Overloading	☐ Failure to vent	☐ Hull failure	☐ People on gunwale, bow or transom

☐ Other *(describe)*:

ACCIDENT DETAILS –*YOUR* BOAT

MACHINERY/EQUIPMENT FAILURE

Failure of the following machinery/equipment on *your* boat contributed to this accident *(select all that apply)*

☐ Engine	☐ Onboard lights	☐ Shift	☐ Sound equipment *(e.g., horn, whistle)*
☐ Electrical system	☐ Seats	☐ Radio	☐ Auxiliary equipment
☐ Fuel system	☐ Steering	☐ Fire extinguisher	☐ Other (*list*):
☐ Sail/mast	☐ Throttle	☐ Ventilation	

☐ Onboard navigation aids *(e.g., GPS)*

ACCIDENT DETAILS – EVENTS ON *YOUR* BOAT

ACCIDENT EVENTS

Types of events occurring to/on *your* boat during accident *(select all that apply)*

☐ Collision with recreational boat	☐ Flooding/swamping	☐ Person fell overboard
☐ Collision with commercial boat *(e.g., tug, barge)*	☐ Fire/explosion – fuel	☐ Person fell on/within boat
☐ Collision with fixed object *(e.g., dock, bridge)*	☐ Fire/explosion – non-fuel	☐ Sudden medical condition
☐ Collision with submerged object *(e.g., stump, cable)*	☐ Carbon monoxide exposure	☐ Person struck by boat
☐ Collision with floating object *(e.g., log, buoy)*	☐ Mishap of skier, tuber, wake boarder, etc.	☐ Person struck by propeller or propulsion unit
☐ Capsizing	☐ Person left boat voluntarily	☐ Person electrocuted
☐ Grounding	☐ Person ejected from boat *(caused by collision or maneuver)*	
☐ Sinking	☐ Other *(describe)*	

CG-3865 (6/13) Page 3 of 6

Reset

For each question below, please provide answers IF APPLICABLE AND IF KNOWN, otherwise leave blank.

ACCIDENT DETAILS – *YOUR* BOAT- INJURED PEOPLE RECEIVING *OR IN NEED OF* TREATMENT BEYOND FIRST AID

Report only injured people on, struck by, or being towed by *your boat*, receiving *or in need of* treatment beyond first aid. *Do not report* injured people on, struck by, or being towed by *another boat or no boat* (e.g., swimmers, people on a dock). *If more than one* injured person to report, attach additional copies of this page. *If none*, SKIP INJURED PEOPLE section.

INJURED PERSON

First Name	MI	Last Name
Street		
City	State	Zip
Phone	Date of Birth *(mm/dd/yyyy)*	Age

INJURY DETAILS

Injury caused when person *(select all that apply)*		**Nature of most serious injury** *(select one)*			
☐	Struck the *(e.g., boat, water):*	☐	Scrape/bruise	☐	Dislocation
☐	Was struck by a *(e.g., boat, propeller):*	☐	Cut	☐	Internal organ injury
☐	Was exposed to carbon monoxide poisoning	☐	Sprain/strain	☐	Amputation
☐	Received an electric shock	☐	Concussion/brain injury	☐	Burn
☐	Other *(describe):*	☐	Spinal cord injury	☐	Other *(describe):*
Person was wearing lifejacket?	☐ Yes ☐ No	☐	Broken/fractured bone		
Person received treatment beyond first aid?	☐ Yes ☐ No	Body part of *most serious* injury *(e.g., head, trunk, leg):*			
Person was admitted to a hospital?	☐ Yes ☐ No				

ACCIDENT DETAILS – *YOUR* BOAT – DEATHS/DISAPPEARANCES

Only report deaths/disappearances of people on, struck by, or being towed by *your boat*.
If more than one death/disappearance to report, attach additional copies of this page.
If none, SKIP DEATHS/DISAPPEARANCES section.

PERSON WHO DIED/DISAPPEARED

First Name	MI	Last Name
Street		
City	State	Zip
Phone	Date of Birth *(mm/dd/yyyy)*	Age

DETAILS OF DEATH/DISAPPEARANCE

Injury caused when person *(select all that apply)*		**Nature of death/disappearance** *(select one)*					
☐	Struck the *(e.g., boat, water):*	☐	Death – by drowning				
☐	Was struck by a *(e.g., boat, propeller):*	☐	Death – other likely cause *(describe)*				
☐	Was exposed to carbon monoxide poisoning						
☐	Received an electric shock	☐	Disappeared and not yet recovered				
☐	Other *(describe):*	**Person was wearing lifejacket?**	☐	Yes	☐	No	

Reset

For each question below, please provide answers IF APPLICABLE AND IF KNOWN, otherwise leave blank.

ACCIDENT DETAILS – *YOUR* BOAT OPERATOR

OPERATOR INSTRUCTION		OPERATOR SAFETY MEASURES				
Boating safety instruction completed *(select all that apply)*		**On board, prior to accident, was operator wearing:**				
☐	None	A lifejacket?	☐	Yes	☐	No
☐	State course	An engine cut-off switch *(Lanyard or wireless device)* if equipped?	☐	Yes	☐	No
☐	USCG Auxiliary course	On board, prior to accident, was operator using:				
☐	US Power Squadrons course	Alcohol?	☐	Yes	☐	No
☐	Internet *(name of sponsoring organization)*	Drugs?	☐	Yes	☐	No
☐	Other *(describe)*	Operator arrested for Boating Under the Influence?	☐	Yes	☐	No
		Weather reports consulted prior to accident?	☐	Yes	☐	No

OPERATOR EXPERIENCE

Experience operating this type of boat *(select one)*

☐	0 to 10 hours	☐	Over 10, up to 100 hours	☐	Over 100, up to 500 hours	☐	Over 500 hours

ACCIDENT DETAILS – OTHER KEY PEOPLE

Only report other key people *not already documented* as injured, died, disappeared or operator/owner of *your* boat.
If more than two other key people to report, attach additional copies of this page.

NAME/ADDRESS

This other key person was a(n) *(select all that apply)*

☐ *Other* boat operator ☐ *Other* boat owner ☐ Owner of *other* damaged property ☐ Passenger on *your* boat ☐ Witness

First Name	MI	Last Name	
Street			
City	State	Zip	Phone
Other boat name *(if any)*		*Other* boat registration # *(if any)*	

NAME/ADDRESS

This other key person was a(n) *(select all that apply)*

☐ *Other* boat operator ☐ *Other* boat owner ☐ Owner of *other* damaged property ☐ Passenger on *your* boat ☐ Witness

First Name	MI	Last Name	
Street			
City	State	Zip	Phone
Other boat name *(if any)*		*Other* boat registration # *(if any)*	

Reset

For each question below, please provide answers IF APPLICABLE AND IF KNOWN, otherwise leave blank.

YOUR BOAT OPERATOR

NAME/ADDRESS

First Name	MI	Last Name
Street		
City	State	Zip

AGE/GENDER/PHONE

Date of Birth *(mm/dd/yyyy)*	Age	Gender		Male		Female	Phone

YOUR BOAT OWNER

If same as *your* boat *operator* SKIP rest of YOUR BOAT OWNER section.

NAME/ADDRESS/PHONE

First Name	MI	Last Name	
Street			
City	State	Zip	Phone

PERSON SUBMITTING THIS REPORT

If same as *your* boat *operator* OR *owner*, SKIP rest of PERSON SUBMITTING THIS REPORT section.

NAME/ADDRESS/PHONE/ROLE

First Name	MI	Last Name	
Street			
City	State	Zip	Phone

I was a(n) *(select one)*

	Other person on board *this* boat
	Accident witness *not* on board *this* boat
	Other *(describe):*

SIGNATURE OF PERSON SUBMITTING THIS REPORT

Your signature	**Date** *(mm/dd/yyyy)*

An Agency may not conduct or sponsor and a person is not required to respond to an information collection, unless it displays a currently valid OMB Control Number.

The Coast Guard estimates that the average burden for this report form is 30 minutes. You may submit any comments concerning the accuracy of this burden estimate or any suggestions for reducing the burden to: Commandant (CG-5422), U.S. Coast Guard, Washington, DC 20593-0001 or Office of Management and Budget, Paperwork Reduction Project (1625-0003), Washington, DC 20503.

CG-3865 (6/13) Page 6 of 6

Reset

Float Plan

Pursuit recommends filling out a float plan each time you use your boat for an offshore day trip or a long cruise. Leave this information with a responsible person ashore, like a close friend or relative that you know well.

1. Name of person reporting and telephone number.

   _____

2. Description of boat.
   Type _____ Color _____ Trim _____
   Registration No. _____ Length _____
   Name _____ Make _____ Other Info _____

3. Engine type _____ H. P. _____
   No. of Engines _____Fuel Capacity _____

4. Survival equipment: (Check as appropriate)

☐ PFD'S	☐ Flares	☐ Mirror
☐ Smoke Signals	☐ Flashlight	☐ Food
☐ Paddles	☐ Water	☐ Others
☐ Anchor	☐ Raft of Dinghy	☐ EPIRB

5. Radio ☐ Yes ☐ No Type _____

6. Automobile license_____
   Type _____ Trailer License _____
   Color _____ and make of auto _____

7. Persons aboard_____
   Name _____ Age _____Address & telephone No. _____
   _____
   _____
   _____

8. Do any of the persons aboard have a medical problem?
   ☐ Yes ☐ No If yes, what?_____

9. Trip Expectations: Leave at _____
   From _____Going to _____
   Expect to return by_____(time)
   and no later than _____

10. Any other pertinent info. _____

11. If not returned by_____ (time)
    call the COAST GUARD, or (Local authority) _____

12. Telephone Numbers.

_____	_____
_____	_____
_____	_____
_____	_____

Operator Notes

Troubleshooting Guide


Problem	Cause and Solution
Control Systems	
Hydraulic Steering is slow to respond and erratic.	• Steering system is low on fluid. Fill and bleed system. • Steering system has air in it. Fill and bleed system. • A component in the steering system is binding. • Check and adjust or repair binding component. • Engine steering cylinder is binding. Grease spindle.
The boat wanders and will not hold a course at cruise speeds.	• There could be air in the steering system. Fill & bleed the system. • The engine steering tab is corroded or out of adjustment. Replace or adjust steering tab. • Engine steering cylinder is binding. Grease spindle.
The engine will not start with the shift control lever in neutral.	• The control cable is out of adjustment & not activating the neutral safety cut out switch. • The shift control lever is not in the neutral detent. Try moving the shift lever slightly. • There is a loose wire on the neutral safety switch on the transmission. Inspect wires and repair loose connections. • The starter or ignition switch is bad.
Performance Problems	
Boat is sluggish and has lost speed and RPM.	• The boat may be need to have marine growth cleaned from hull and running gear. • Propeller may be damaged & need repair. • Weeds or line around the propeller. Clean propeller. • Boat is overloaded. Reduce load. • Check for excessive water in the bilge. Pump out bilge & find & correct the problem. • The throttle adjustments has changed and the engine is not getting full throttle. Adjust the throttle cable.


Problem	Cause and Solution
The boat vibrates at cruising speeds.	• Propeller may be damaged and need repair. • The propeller or propeller shaft is bent. Repair or replace damaged components. • The running gear is fouled by marine growth or rope. Clean running gear. • The engine is not trimmed properly. Trim the engine.
Engine Problems	
The engine is running too hot.	• The engine raw water pick-up strainer up is clogged with marine growth. Clean pick-up. • The engine raw water pump impeller is worn or damaged. Repair the pump. • The engine thermostat is faulty and needs to be replaced.
The engine alternator is not charging properly.	• The battery cable is loose or corroded. Clean and tighten battery cables. • The alternator is not charging and must be replaced. • The engine battery isolator in the charging system is not working properly. Replace the isolator. • The battery is defective. Replace the battery.
The engine suddenly will not operate over 2000 RPM.	• The engine emergency system has been activated. The onboard computer has sensed a problem and has limited the RPM to protect the engine. Find & correct the problem. • The tachometer is bad and needs to be replaced.


Problem	Cause and Solution
The engine is loosing RPM. The boat is not overloaded and the hull bottom and running gear are clean and in good condition.	• The engine may be having a problem with a sticky anti-siphon valve, located in the fuel line near the fuel tank, that is restricting the fuel flow. Remove & clean or replace the anti-siphon valve. • The remote gasoline fuel filter could be dirty. Inspect and replace the fuel filter. • The primary fuel filter on the engine may be dirty. Inspect and replace the fuel filter. • The electronic engine control system on the engine is malfunctioning. Repair the engine control system. • The fuel injection system on the engine is malfunctioning. Repair the fuel injection system.
Accessory Problems	
The livewell pump runs, but does not pump water.	• The strainer on the intake scoop is clogged preventing the water from getting to the pump. Put the boat in reverse to clean the strainer. • There is an air lock in the system. Run the boat above 15 m.p.h. and the pick-up scoop will force the air lock past the pump and prime the system. • The thru-hull valve is not open. Open valve. • The valve in the livewell is not open. Open the valve in the livewell.
The automatic float switch on the bilge pump raises but does not activate the pump.	• The in-line fuse near the battery switch has blown. Replace the fuse. • The pump impeller is jammed by debris. Clean pump impeller housing. • The pump is defective. Replace pump.


Operator Notes


Schematics



PORT & STBD ENGINES
CENTER ENGINE & GENERATOR
ELECTRONICS & HOUSE
OFF
ON
COMBINE BATTERIES
10-32x2-3/4" SS SCREWS
#10 FLAT WASHERS
#10 NYLON NUTS
BOW THRUSTER
HOUSE
ELECTRONICS
12.40
STEREO AMP
60
10-32x1" SS SCREWS
#10 SPLIT-LOCK WASHERS
#10 HEX NUT
WINDLASS
BUSS
MRCB
OFF
ON
70A
10-32x3/4" SS SCREWS
#10 SPLIT-LOCK WASHERS
#10 HEX NUT
ELECTRONICS MAIN
HOUSE MAIN
HELM MAIN
SPARE
VACUFLUSH
MACERATOR HEAD
COCKPIT COOLER
COCKPIT FRIDGE
ELECTRONICS BATTERY CHARGER
PORT ISOLATOR
HOUSE STBD ISOLATOR
HOUSE CENTER ISOLATOR
HOUSE BATTERY CHARGER
PORT BATTERY CHARGER
CENTER BATTERY CHARGER
STBD BATTERY CHARGER
ELECTRONICS BATTERY METER
HOUSE BATTERY METER
CABIN LIGHTS
HEAD LIGHTS
ACCENT LIGHT
FWD BILGE
MID BILGE
AFT MANUAL BILGE
AFT AUTO BILGE
HIGH WATER BILGE
SUMP
FWD CO DETECTOR
AFT CO DETECTOR
STEREO MEMORY
PORT DOWN RIGGER
STBD RIGGER
TRIM TABS
MACH SPACE LIGHT
CABIN 1
CABIN 2
12 VOLT RECEPTACLE
FWD
HELM 1
HELM 2
CABIN 1
CABIN 2
USB RECEPTACLE
FWD
HELM
TV
ANTENNA
STEREO
HIGH WATER ALARM
HORN
NAV / ANCHOR
WASHER
FRESH WATER
RAW WATER
FISHBOX PUMP OUT
LIVEWELL
PORT WIPER
STBD WIPER
GENERATOR BLOWER
COCKPIT GRILL RELAY
COCKPIT SHADE
SPARE
SPOT LIGHT
WINDLASS
ACC
COCKPIT LIGHTS
MID LEVEL LIGHTS
HARDTOP LIGHTS
SPREADER LIGHT
UNDER WATER LIGHTS
ACC
ACC
ACC
ACC
SHORE POWER REEL
12 INCHES
BACK PANEL (X2 FLAT PRINTER)
-RED SCREEN PRINT (5A)
-YEL SCREEN PRINT (10A)
-GRN SCREEN PRINT (15A)
-BLU SCREEN PRINT (20A)
-ORG SCREEN PRINT (25A)
-VIO SCREEN PRINT (30A)
-CYN SCREEN PRINT (40A)
-GRY SCREEN PRINT (50A)
-BLACK TEXT PRINT (BREAKER VALUES)



ELECTRONICS & HOUSE
CENTER ENGINE & GENERATOR
PORT & STBD ENGINES
10 ORG
10 ORG/RED
10 ORG/GRN
14 RED
8 RED
4 RED
10 RED
WINDLASS
STEREO AMP
ELECTRONICS
HOUSE
50A
15A
25A
10A
LOAD
LINE


ELECTRONICS & HOUSE
CENTER ENGINE & GENERATOR
PORT & STBD ENGINES
2/0 RED
1/0 RED
4 RED
9.5000
HANG THESE PLUGS HERE 24 INCHES
ELECTRONICS BATT
HOUSE BATTERY
WINDLASS
CENTER BATTERY
STBD BATTERY
PORT BATTERY
GENERATOR
PORT ENGINE
CENTER ENGINE
STBD ENGINE
AUTO PILOT
ELECTRONICS
AMPLIFIER
37822 & 37797
37822
AMPLIFIER
ELECTRONICS
AUTO PILOT
3WAY DEUTSCH RECEPT. w/POC
(HDP26-24-7SN-C038)



HARNESS CONNECT #1 (GRAY)
16GA ORANGE / WHITE #1
16GA GREY #2
14GA BLACK #3
16GA BLUE / BLACK #4
14GA BROWN / BLACK #5
14GA RED #6
14GA BROWN / PINK #13
14GA BROWN / VIOLET #12
14GA RED #11
CAVITY SEAL
16GA BLUE / GREY #9
CAVITY SEAL
12WAY DEUTSCH DT RECEPTACLE
CONNECTOR (DT04-12PA)
WEDGE LOCK (W12P)
HARNESS CONNECT #2 (BLACK)
14GA WHITE / YELLOW #14
16GA WHITE / RED #15
CAVITY SEAL
16GA WHITE / GREEN #17
CAVITY SEAL
CAVITY SEAL
16GA BLUE / WHITE #25
16GA BLUE #24
16GA ORANGE #23
14GA RED #22
14GA RED #21
16GA RED / GREY #20
12WAY DEUTSCH DT RECEPTACLE
BLACK CONNECTOR (DT04-12PB)
WEDGE LOCK (W12P)
HARNESS CONNECT #3 (GREEN)
16GA BLUE/PINK #26
16GA BLUE/PINK #27
16GA BLUE / GREY #28
14GA BROWN / WHITE #29
14GA BROWN #30
14GA BROWN / ORANGE #31
14GA RED #39
16GA RED / WHITE #36
16GA RED / WHITE #35
14GA WHITE #34
14GA BROWN / GREEN #33
14GA BROWN / VIOLET #32
12WAY DEUTSCH DT RECEPTACLE
LT. GREEN CONNECTOR (DT04-12PC)
WEDGE LOCK (W12P)
HARNESS CONNECT #4 (BROWN)
14GA RED / BLACK #40
14GA RED / BLACK #41
14GA RED / BLACK #42
14GA RED #73A
14GA ORANGE / BLUE #48
SEALING PLUG
14GA RED #69
14GA RED #68
16GA BLUE/ORANGE #66
16GA BLUE/ORANGE #65
16GA YELLOW #58
14GA BR/VI #53C
12WAY DEUTSCH DT RECEPTACLE
BROWN CONNECTOR (DT04-12PD)
WEDGE LOCK (W12P)
HARNESS CONNECT #5
14 BROWN / ORANGE #53
14 BROWN #54A
14GA RED #61
16GA VIOLET/WHITE #73S
14 BROWN / YELLOW #121
16 ORANGE / WHITE #79A
16GA BLUE/PINK #75
14GA RED #74
8WAY DEUTSCH DT RECEPTACLE
CONNECTOR (DT04-8PA)
WEDGE LOCK (W8P)
HARNESS CONNECT #6(GRAY)
14GA RED #70
14GA RED #150
14GA RED / WHITE #160
14GA RED #170
14GA RED #171
14GA RED #172
CAVITY SEAL
CAVITY SEAL
CAVITY SEAL
14GA BROWN #176
14GA BL/PK #77
14GA RED #173
12WAY DEUTSCH DT RECEPTACLE
CONNECTOR (DT04-12PA)
WEDGE LOCK (W12P)
PORT DOWNRIGGER
8GA RED #37
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
STBD DOWNRIGGER
8GA RED #38
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
REFRIGERATOR
8GA RED #50
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
CENTER ENGINE ISOLATOR
8GA RED #51
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
PORT ENGINE ISOLATOR
8GA RED #52
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
STBD ENGINE ISOLATOR
8GA RED #53
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
COCKPIT COOLER
10GA RED #78
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
HOUSE CHARGER
10GA ORANGE / BLACK #54
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
ELECTRONICS CHARGER
10GA ORANGE / WHITE #55
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
PORT CHARGER
10GA ORANGE / RED #56
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
STBD CHARGER
10GA ORANGE / GREEN #57
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
CENTER CHARGER
10GA ORANGE #59
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
SPOT LIGHT
10GA BLUE/ORANGE #67
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
SHORE REEL
10GA RED #81
1WAY DEUTSCH 8-10 DTHD RECPT
CONNECTOR (DTHD-04-1-8-P)
HC7
12 OR #10
12 RD #7
SEALING PLUG
12 RD/GN #49
4WAY DEUTSCH DT PLUG
CONNECTOR (DTP04-4P)
WEDGE LOCK (WP4P)
BILGE RELAY
14 BROWN / ORANGE #53B
14 BROWN #54A
16GA YELLOW #58E
14 RED #60B
4 Way Plug 630s P2s Relay Base
1206-5686
REAR VIEW
HORN RELAY
14 BROWN / ORANGE #53A
16 ORANGE / WHITE #79A
16GA YELLOW #58D
14 RED #60A
4 Way Plug 630s P2s Relay Base
1206-5686
REAR VIEW
NOTE:
ADD DT04-4P-EP13
HW ALARM FEEDBACK
14 RED #61
14 RED #60B
14 RED #60
14 RED #60A
4WAY DEUTSCH DT PLUG
CONNECTOR (DT06-4S)
WEDGE LOCK (W4S)
NOTE:
ADD DT04-4P-EP13
HW BILGE FEEDBACK
14 BROWN / VIOLET #53C
14 BROWN / ORANGE #53B
14 BROWN / ORANGE #53
14 BROWN / ORANGE #53A
4WAY DEUTSCH DT PLUG
CONNECTOR (DT06-4S)
WEDGE LOCK (W4S)
NOTE:
ADD DT04-6P-EP13
GND FEEDBACK
16GA YELLOW #58E
16GA YELLOW #58D
16GA YELLOW #58C
16GA YELLOW #58
16GA YELLOW #58A
16GA YELLOW #58B
6WAY DEUTSCH DT PLUG
CONNECTOR (DT06-6S)
WEDGE LOCK (W6S)



PORT & STBD ENGINES
CENTER ENGINE & GENERATOR
ELECTRONICS & HOUSE
NOTE: SOME SCREENING DELETED TO SHOW WIRE NUMBERS
USE MAIN PRINT FOR BACK SCREENING



BLUE SEAS DIGITAL
MULTI-METER AC 10195
GENERATOR
SHORE
POWER
TWIST WIRES
WATER
HEATER
COCKPIT
GRILL
SPARE
MICROWAVE
CABIN
OUTLET
HEAD
OUTLET
COCKPIT
OUTLET
SPARE
120 VOLTS AC
CABIN AIR
COND.
HELM AIR
COND.
COOLING
PUMP
HOUSE
CHARGER
ENGINE
CHARGER
SPARE
CONTINUES TO PAGE 3 OF 3
WIRE PATH FOR PANELS





CONTINUES TO PAGE 3 OF 3



WARNING
ELECTRIC SHOCK HAZARD. UNPLUG SHORE POWER AND DISENGAGE GENERATOR BEFORE REMOVING COVER OR SERVICING PANEL.
NEUTRAL BUSS 120V
GROUNDING BUSS
install covers on buss bars
24"
CONTINUES TO PAGE 1 OF 3



4WAY DT ENHANCED PLUG WITH RECPT FEEDBACK BUSS CONN (DT06-4S-P012) FEEDBACK (DT04-4P-CP10)
NFB - NAV FEED BUSS
16 BLUE #88 — 16 GREY #70A
16 GREY #71 — 16 GREY #70
4WAY DEUTSCH DT PLUG CONNECTOR (DT06-4S-P012) LOCKING WEDGE (W4S-P012)
4WAY DT ENHANCED PLUG WITH RECPT FEEDBACK BUSS CONN (DT06-4S-P012) FEEDBACK (DT04-4P-CP10)
NFB - HARDTOP FEED BUSS
16 BLUE / WHITE #124 — 16 BLUE / WHITE #122
16 BLUE / WHITE #123 — 16 BLUE / WHITE #122A
4WAY DEUTSCH DT PLUG CONNECTOR (DT06-4S-P012) LOCKING WEDGE (W4S-P012)
HARNESS CONNECT #1 (GRAY)
14 BROWN / BLACK #6 — 14 BROWN / PINK #30
14 ORANGE / #14 — 14 WHITE / GREEN #28
14 ORANGE / WHITE #15 — 14 BROWN / VIOLET #28
14 RED #16 — 14 RED #24
14 RED #19 — 14 RED #22
16 GREY #20 — 14 RED #21
12WAY DEUTSCH DT RECEPTACLE CONNECTOR (DT04-12PA) WEDGE LOCK (W12P)
HARNESS CONNECT #2 (BLACK)
16 WHITE / RED #31 — 16 BLUE #178
14 BLACK #33 — 14 RED #150
14 WHITE / YELLOW #34 — 16 BLUE / BLACK #103
16 RED / GREY #35 — 16 BLUE / BLACK #101
14 BROWN / RED #47 — 14 YELLOW #99D
14 BROWN #48 — 16 BLUE / WHITE #82
12WAY DEUTSCH DT RECEPTACLE BLACK CONNECTOR (DT04-12PB) WEDGE LOCK (W12P)
HARNESS CONNECT #3 (GREEN)
14 BROWN / ORANGE #53 — 14 ORANGE / WHITE #78
14 BROWN #54 — 16 GREY / BLACK #72
14 BLACK #55 — 16 GREY #71
14 BROWN / RED #58 — 16 GREY #70
14 BROWN / WHITE #59 — 16 BLUE #6B
16 RED / YELLOW #61 — 16 RED / BLUE #62
12WAY DEUTSCH DT RECEPTACLE LT. GREEN CONNECTOR (DT04-12PC) WEDGE LOCK (W12P)
HARNESS CONNECT #4 (BROWN)
14 BROWN / BLACK #91 — 16 BLUE / RED #98
14 WHITE / YELLOW #84 — 16 BLUE / RED #97
14 WHITE / VIOLET #85 — 16 BLUE / RED #95
14 BROWN / VIOLET #86 — 16 BLUE / GREEN #94
14 BROWN / VIOLET #87 — 16 BLUE / GREEN #93
16 BLUE / GREEN #91 — 16 BLUE / GREEN #92
12WAY DEUTSCH DT RECEPTACLE BROWN CONNECTOR (DT04-12PD) WEDGE LOCK (W12P)
HARNESS CONNECT #5 (GRAY)
14 BROWN / PINK #100 — 14 BLUE #181
14 BLUE #182 — 14 BLUE #180
16 ORANGE / RED #107 — 14 BLUE #179
16 ORANGE / GREEN #108 — 16 WHITE / BLUE #152
16 BLUE / WHITE #122A — 16 WHITE / GREEN #151
16 BLUE / WHITE #123 — 16 BLUE / WHITE #124
12WAY DEUTSCH DT RECEPTACLE CONNECTOR (DT04-12PA) WEDGE LOCK (W12P)
HARNESS CONNECT #6
16 WHITE / BLACK #26 — 16 WHITE / RED #67
16 WHITE / BLACK #27 — 16 WHITE / RED #66
16 WHITE / BROWN #44B — 16 WHITE / GREEN #57
16 WHITE / BROWN #45B — 16 WHITE / GREEN #56
8WAY DEUTSCH DT RECEPTACLE CONNECTOR (DT04-08PA) WEDGE LOCK (W8P)
GROUND FEEDBACK
SEALING PLUG — 14 YELLOW #99D
16 YELLOW #99C — 16 YELLOW #99
16 YELLOW #99B — 16 YELLOW #99A
6WAY DEUTSCH DT PLUG CONNECTOR (DT06-6S)-P012 WEDGE LOCK (W6S)
RECPT FEEDBACK BUSS CONN (DT04-6P-CP13)
MID LEVEL FEEDBACK
SEALING PLUG — 14 BLUE #41
14 BLUE #182 — 14 BLUE #179
14 BLUE #181 — 14 BLUE #180
6WAY DEUTSCH DT PLUG CONNECTOR (DT06-6S)-P012 WEDGE LOCK (W6S)
RECPT FEEDBACK BUSS CONN (DT04-6P-CP13)
POWER STEERING
14 VIOLET #111 — 14 VIOLET #11
2WAY DEUTSCH DTP RECEPTACLE CONNECTOR (DTP04-2P) WEDGE LOCK (WP2P)
UW - UNDERWATER LIGHTS
12RD #77 — 12RD #8
2WAY DEUTSCH DTP RECEPTACLE CONNECTOR (DTP04-2P) LOCKING WEDGE (WP2P)
LOGO LTS
16BL/RD #98 — 16BL/GN #95A
2WAY DEUTSCH DT RECEPTACLE CONNECTOR (DT04-2P) WEDGE LOCK (W2P)
RECPT FEEDBACK BUSS CONN (DT04-12PA-P016)
CFB - COCKPIT FEEDBACK
SEALING PLUG — 16BL/BK #90
SEALING PLUG — 16BL/GN #91
16BL/RD #95B — 16BL/GN #92
16BL/GN #95A — 16BL/GN #93
16BL/RD #98 — 16BL/GN #94
16BL/RD #97 — 16BL/RD #96
12WAY DEUTSCH DT PLUG CONNECTOR (DT06-12SA-P012) WEDGE (W12S-P012)
STBD WIPER COMMON DIODE
16 WHITE / BROWN #44A — 16 WHITE / BROWN #44B
2WAY DEUTSCH DT PLUG CONNECTOR (DT06-2S) LOCKING WEDGE (W2S)
PORT WIPER COMMON DIODE
16 WHITE / BROWN #45A — 16 WHITE / BROWN #45B
2WAY DEUTSCH DT PLUG CONNECTOR (DT06-2S) LOCKING WEDGE (W2S)
WINDLASS RETRIEVE DIODE
16 RED / BLUE #44 — 16 YELLOW #99C
2WAY DEUTSCH DT PLUG CONNECTOR (DT06-2S) LOCKING WEDGE (W2S)
WINDLASS DEPLOY DIODE
16 RED / YELLOW #45 — 16 YELLOW #99B
2WAY DEUTSCH DT PLUG CONNECTOR (DT06-2S) LOCKING WEDGE (W2S)
WASHER DIODE
14 BLACK # 32 — 16 YELLOW #99A
2WAY DEUTSCH DT PLUG CONNECTOR (DT06-2S) LOCKING WEDGE (W2S)



INSTALL SWITCH UPSIDE DOWN!
HANG PIG TAIL HERE
12 INCHES
HORN
NAV/ANC
COCKPIT
MID LEVEL LIGHTING
FRESH WATER
WASHDOWN
AFT BILGE
FWD BILGE
POWER STEERING
HARDTOP LIGHTS
FISHBOX
SPREADER LIGHTS
LIVEWELL
UNDER WATER LIGHTS
ACC
DEPLOY
RETRIEVE
IN
SHADE
OUT
STBD WIPER
PORT WIPER
WASHER
DPLY RET
NAV/ANC
COCKPIT
HORN
UW LTS
SPREADER
MID LEVEL
FRSH WTR
AFT BLG
FWD BLG
SHADE
ACCY 1
LIVEWELL
FISHBX
WSHDWN
ACCY 4
ACCY 3
ACCY 2
WSHR
STBD WPR
PORT WPR
ACCY 5
PWR STRNG



INSTALL BOOT OVER 50A BREAKER
#ENCL806W
SHORE POWER REEL
240VAC
#CT1020 BREAKER BOOT INSTALL BETWEEN BOX AND BREAKER
USE ONLY SCREWS THAT ARE PROVIDED W/BOOT
AFT MDP * HDP24-24-7PN-C038
1) 114017 CAVITY SEAL
2) 114017 CAVITY SEAL
3) 6GA BLACK - BREAKER LINE
4) 6GA RED - BREAKER LINE
5) 114017 CAVITY SEAL
6) 6GA GREEN - (6/3 CABLE)
7) 114017 CAVITY SEAL
CUT RED AND BLACK WIRES IN HALF TERMINATE WITH 1/4" RINGS MOUNT WIRES INTO BREAKER
ENCLOSURE LID BACKVIEW
50A 50A
6Ga BLK
6Ga RED
6Ga BLK
6Ga RED
USE WASHER #2414-001-2486 NUT #2411-001-2405
LIQUID TIGHT CONN #BSLC-1 LOCING NUT #BSLN-1
7FT WR6/3BRG
STRIP 6" BACK (NO HEAT SHRINK ON GREY JACKET)
1/4 RINGS ALL 3 WIRES
6Ga RED
6Ga BLK
6Ga GRN
6"
6Ga BLK
6Ga RED
6Ga BLK
6Ga RED
6Ga GRN
TERMINATE THESE 3 WIRES WITH 0460-204-0490
ENCLOSURE INSIDE TOPVIEW


NOTE: NO WIRE INSULATION
TO SHOW - LOOM ALL
1/0 RED
"HOUSE MDP"
1/0 RED
"ELECTRONICS
MDP"
37822 &
37797
37822 &
37797
12"
12"
FLIPPED COVER
BATTERY SWITCH
PANEL FEEDS
HOUSE
200A MAIN
ELECTRONICS
100A MAIN
ELECTRONICS
MDP
HOUSE
MDP
LOAD
100A
200A
200A
LINE
ELECTRONICS
BATTERY
HOUSE
BATTERY
36"
36"
1/0 RED
"HOUSE
BATTERY"
5/16" RING
1/0 RED
"ELECTRONICS
BATTERY"
5/16" RING


3300100
D5 PORT CABIN LIGHT PANEL
INTERIOR LIGHTS
ACCENT LIGHTS
OFF / ON
VADJBCOB
OFF / ON
V1D1S00B
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
88
89
9
ACCENT LIGHTS
INTERIOR LIGHTS
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
90
91
11
95
93
94
92
HANG PIG TAIL HERE
12 INCHES
16 BL/PK #90
16 BL/PK #91
16 BL/PK #89
16 BL/PK #88
16 BL/PK #11
16 BL/PK #9
16 BL/PK #92
16 PL/PK #93
16 BL/PK #94
16 BL/PK #95
SEALING PLUG
SEALING PLUG
DEUTSCH
12WAY DEUTSCH DT RECEPTACLE
CONNECTOR (DT04-12PA)
WEDGE (W12P)



3300110
D5 STBD. HEAD LIGHT PANEL
ACCENT LIGHTS
HEAD LIGHTS
OFF / ON
V1D1S00B
OFF / ON
VADJBC0B
HEAD LIGHTS
ACCENT LIGHTS
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
16 BLUE / PINK
9
89
90
91
11
92
93
94
HANG PIG TAIL HERE
12 INCHES
HC
DEUTSCH
16 BL/PK #9
16 BL/PK #11
16 BL/PK #89
16 BL/PK #90
16 BL/PK #94
16 BL/PK #93
16 BL/PK #92
16 BL/PK #91
8WAY DEUTSCH DT RECEPTACLE
CONNECTOR (DT04-08PA)
WEDGE LOCK (W8P)


GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE FUEL SYSTEM ONLY. REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURES OF COMPONENTS.
2. ALL FLEXIBLE HOSE SHALL BE SAE J1527 AND USCG TYPE A1, A1-15, A-2 / ISO 7840:1994.
3. ALL HOSES SHALL BE SECURED WITH CORROSION RESISTANT MATERIALS AND ROUTED SO THEY WILL NOT CHAFE ON BOAT STRUCTURE.
4. ALL CLAMPS TO BE INSTALLED BEYOND THE FLARE OR BEAD AND AT LEAST 1" FROM HOSE END.
5. HOSE SHALL BE SECURED TO FITTINGS WITH AT LEAST TWO 316 STAINLESS STEEL CLAMPS WITH A NOMINAL BAND WIDTH OF AT LEAST 1/2".
6. FUEL HOSES SHALL BE INSTALLED WITHOUT ANY DIPS OR LOW SPOTS.
7. ALL METALLIC COMPONENTS OF THE FUEL FILL SYSTEM SHALL BE GROUNDED TO VESSEL GROUNDING SYSTEM.
8. COMPLETED FUEL SYSTEM TO BE PRESSURE TESTED AT A MINIMUM OF 3 PSI FOR A DURATION OF 20 MINUTES PER TANK.
1
2, 5
6
6'
3
4
5
6C PLAN VIEW - FILL SCHEMATIC
SCALE: 1"=1'0"
2C TABLE - FILL SCHEMATIC
SCALE: 1"=1'0"
ISSUED FOR PRODUCTION
PART # COMPONENT MANUFACTUER QTY. UNIT
1 3344531 FILL,DECK 1-1/2" W/VENT FUEL CH/PL #0661 PERKO INC 1 EA
2 3285420 HOSE,FUEL,TYPE A1-15/ A2-15 TRIDENT RUBBER 6 LFT
3 3196170 TANK,FUEL,323 GAL, EPA D5 #FT0621218D MOELLER MARINE PRODUCTS 1 EA
4 5323897 BCAM,FUEL TANK HOLD DOWN STBD D5 BAUSCH ENTERPRISES 1 EA
5 5323898 BCAM,FUEL TANK HOLD DOWN CENTER D5 BAUSCH ENTERPRISES 1 LFT
6 3285500 HOSE,VENT 3/4" NMMA/CE TYPE A1 #20FT/RL TRIDENT RUBBER 7 LFT
- 3283440 CONDUIT,PLT BLACK 1" 300FT/BOX MPT PRODUCTS INC. 10 LFT
- 5295591 GASKET, NEOPRENE 7MM 1/4"X2"X 80'/ROLL PAK-LITE INC. 30 LFT
- 5295610 PAD,CHAFING 2"X6"X3/8" V/UHMW ADHESIVE PAK-LITE INC. 12 EA
REFERENCES
ZONE DESCRIPTION DATE APPR'D
RESERVATIONS
ZONE DESCRIPTION DATE APPR'D
REVISIONS
REV ZONE DESCRIPTION DATE APPR'D
PURSUIT BOATS ©2018
MODEL D5 – 365 DUAL CONSOLE
DESCRIPTION
FUEL SYSTEM
FUEL SCHEMATIC
SIZE D DRAWN BY: DWG NO. D5-261-001 REV -
SCALE: 1" = 1' 0" DATE: 3/9/18 SHEET 1 OF 3





#	PART #	COMPONENT	MANUFACTURER	QTY.	UNIT
1	3401079	HEAD,WATER IN/OUT SS	YAMAHA	3	EA
2	3401080	FILTER,FUEL/WATER #MAR-FUELF-LT-12	YAMAHA	3	EA
3	326e100	ELBOW,45 DEG 3/8X1/2 FLARE,BRASS,8-6	GRAINGER - PO 813765899	3	EA
4	3220150	FITTING,BRASS 3/8"MPX3/8"FP #28-158	ACR INDUSTRIES	3	EA
5	326i130	CONNECTOR,MALE 3/8"MPTX3/8"MFL #448-6-6	ORLANDO HOSE & FLUID POWER	3	EA
6	326e320	FITTING,BRASS HOSE 1/2" #502-2828	TRIDENT RUBBER INC.	6	EA
7	326e330	FITTING,BRASS HOSE 3/8" #502-2838	TRIDENT RUBBER INC.	2	EA

#	PART #	COMPONENT	MANUFACTURER	QTY.	UNIT
8	3285540	HOSE,FUEL 1/2" NMMA/CE TYPE A1 250FT/RL	TRIDENT RUBBER INC.	38	LFT
9	3285530	HOSE,FUEL 3/8" NMMA/CE TYPE A1 250FT/RL	TRIDENT RUBBER INC.	24	LFT
-	326e350	FERRULE,BRASS HOSE 850 #700-0850-SP1	TRIDENT RUBBER INC.	8	EA
-	326e340	FERRULE,BRASS HOSE 718" #700-0718-SP1	TRIDENT RUBBER INC.	2	EA



#	PART #	COMPONENT	MANUFACTURER	QTY	UNIT
1	3344680	CANISTER,2 LITER,5/16" HB X 5/8" HB	PERKO	1	EA
2	3344485	VENT P-TRAP 5/8" BLACK	PERKO	1	EA
3	3285500	HOSE,VENT,5/8",NMMA/CE TYPE A1 250FT/RL	TRIDENT RUBBER INC.	3	LFT
4	3285520	HOSE,FUEL 5/16" NMMA/CE TYPE A1 250FT/RL	TRIDENT RUBBER INC.	5	LFT


GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE GENERATOR ARRANGEMENT ONLY. REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURES OF COMPONENTS.
TABLE - DIESEL FUEL SYSTEM
SCALE: N/A
PLAN VIEW - DIESEL FUEL SYSTEM
SCALE: 1" = 1'0"
10'6" FUEL RETURN
ISSUED FOR PRODUCTION
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION
DIESEL GENERATOR ARRNGEMENT
DWG NO. D5-310-001
DATE: 3/19/18
SCALE: 1" = 1'0"
SHEET 1 OF 2



14C PLAN VIEW - DIESEL GENERATOR ARRANGEMENT

SCALE: 1" = 1'0"

10C TABLE - DIESEL GENERATOR ARRANGEMENT

SCALE: N/A

#	PART #	COMPONENT	MANUFACTURER	QTY.	UNIT
1	3348020	SCUBP:PICKUP LDV 1"HMPTX1"HB #PTH-1000	MARINE HARDWARE INC.	1	EA
2	3226770	VALVE:BALL BRASS 1" BVL/V1000-FPHL	MARINE HARDWARE INC.	1	EA
3	3260027	ELBOW, 1" 45DEG BRONZE #PTHD-1000	GROSS MECHANICAL LABORATORIES	1	EA
4	3284610	HOSE:WATER HARDWALL 1"ID 50FT/RL	MPI PRODUCTS INC.	2	LFT
5	3332040	ADAPTER:STRAIGHT BR 1"MPTX1"HB #PTH-1000	GROSS MECHANICAL LABORATORIES	1	EA
6	3202500	STRAINER:SEA WATER 1" MARS-1000-P	GROSS MECHANICAL LABORATORIES	1	EA
7	3338670	BUSHING,HEX BRZ 1"MPTX3/4"FPT #44-513	ACR INDUSTRIES	1	EA
8	3261991	ELBOW, 3/4" 45DEG BRONZE #PTHD-750	GROSS MECHANICAL LABORATORIES	1	EA
9	3280050	HOSE:WATER HARDWALL 3"ID 50FT/RL	MPI PRODUCTS INC.	4	LFT
10	3129000	GENSET,18KW/24KW/60 HZ,208V/240V/60	FISCHER PANDA GENERATORS	1	EA
11	3401370	MOUNT:MOTOR FOR GENSET #CFT6423MIDSSM	FISCHER PANDA GENERATORS	1	EA
12	3285390	HOSE:EXHAUST 1-1/2" MUFFLER:GENSET LH #CE1602572	MPI PRODUCTS	13	LFT
13	3401365	THRU-HULL,BRZ,1.5"MPT W/FLNG,1.75"OD	FISCHER PANDA GENERATORS	1	EA
14	3229260	ELBOW,BRZ,1½"FPTX1½" #PTHAF-150	MARINE HARDWARE INC.	1	EA
15	3332180	ELBOW,BRZ,1½"FPTX1½" #PTHAF-150	MARINE HARDWARE INC.	1	EA

PURSUIT BOATS

MODEL D5 – DC 365 DUAL CONSOLE


DESCRIPTION DIESEL GENERATOR ARRANGEMENT

DWG NO. D5-310-001 REV -


SCALE 1" = 1'0" DATE 3/19/18 SHEET 2 OF 2

PURSUIT BOATS ... THESE ITEMS ARE AND SHALL REMAIN THE PROPERTY OF PURSUIT BOATS, INC. AND SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF PURSUIT BOATS, INC.

OWNER'S PRODUCT DEVELOPMENT DATA\Pursuit Prototypes\D Series\1 Master Drawing Files\001 - ELECTRIC PLANT\D5-310-001_Rev1\1_Generator Arrangement\1_110111.dwg



#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	3348020	SCOOP,PICKUP LOW 1"#THMRL100-B-HSVP	MARINE HARDWARE INC.	1	EA
2	3226770	VALVE,BALL BRASS 1" BV-1VLVDC-FULL	MARINE HARDWARE INC.	1	EA
3	3260027	ELBOW,1" AXIOTIC BRONZE #PTHD-100	GRUSS MECHANICAL LABORATORIES	1	EA
4	3284610	HOSE,WATER HARDWALL 1"ID SMFT/RL	MPI PRODUCTS INC.	4	LFT
5	3332040	ADAPTER,STRAIGHT BR 1"MPTX1"HB #PTH-1000	GRUSS MECHANICAL LABORATORIES	1	EA
6	3202500	STRAINER,SEA WATER 1" #ARG-1000-P	GRUSS MECHANICAL LABORATORIES	1	EA
7	3220009	NIPPLE,CLOSE 1" RED BRASS #PTNM-100	MARINE HARDWARE INC	1	EA
8	5558030	PUMP ASY PM41000C 230/50-60/1 #2255000240	MARINE AIR SYSTEMS, INC.	1	EA
9	3332650	ELBOW,1/2"FPT X 3/4"HB PVC #1407-10	ACR INDUSTRIES	1	EA
10	3283560	HOSE,2 #1407-10 PVC LIVEWELL 100FT/RL	MPI PRODUCTS INC.	12	LFT
11	5559610	MANIFOLD,COOLING SYSTEM 3SM #2203300003	MARINE AIR SYSTEMS, INC.	1	EA
12	3226040	PLUG,SQUARE HEAD 1/2" #SQ-807 BRASS	ACR INDUSTRIES	1	EA
13	5558400	UNIT,AC DTUD-22S1 230V/60HZ #2051162100	MARINE AIR SYSTEMS, INC.	1	EA
14	3222550	ADAPTER 1/2MP X3/4HB 90DEG TLS-64	ACR INDUSTRIES	2	EA



11-C PLAN VIEW - CABIN COOLING SCHEMATIC

SCALE: 3/4"= 1'0"

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	5047950	GRILL,KHAYA LOUVERED 12X14	MARINE AIR SYSTEMS INC	1	EA
2	5550003	GRILL, 4"XB"VH AFMHG/BKZ	MARINE AIR SYSTEMS INC	1	EA
3	5559731	BOX,PLENUM/V84/ESOB 22"X50"X25"/ 4"XB"	MARINE AIR SYSTEMS INC	1	EA
4	5559290	GRILL,BLACK #2071002	MARINE AIR SYSTEMS INC	2	EA
5	5047630	GRILL,PLASTIC AC SUPPLY 5X5 #21731601G	MARINE AIR SYSTEMS INC	1	EA
6	3285270	DUCT,FLEX 3" #22660087	MARINE AIR SYSTEMS INC	10	LFT
7	3285303	DUCT,FLEX 4" NON-ONE #22660088 (25'/BX)	MARINE AIR SYSTEMS INC	3	LFT
8	3285302	DUCT,FLEX 5" NON-ONE #22660089 (25'/BX)	MARINE AIR SYSTEMS INC	24	LFT
9	5559730	VE66/A6B33C5E4 (NRP)	MARINE AIR SYSTEMS INC	1	EA
10	5559732	DUCT,TRANS ABS "Y" 4/4/3 228700864	MARINE AIR SYSTEMS INC	1	EA
–	3285301	DUCT,FLEX 6" NON-ONE #22660090 (25'/BX)	MARINE AIR SYSTEMS INC	2	LFT

15-A TABLE - COOLING SCHEMATIC


SCALE: N/A

ISSUED FOR PRODUCTION


PURSUIT BOATS ©2016

C:\NEW PRODUCT DEVELOPMENT\DS\2017\A\3 Prototype Design\4 x Master Drawing\Mech\01-AUXILIARY SYSTEMS\DS-514-001_Rev1\[LHVAC System Schematic_170711.dwg

MODEL	D5 – DC 365 DUAL CONSOLE
DESCRIPTION	D5 HVAC SYSTEM SCHEMATIC
SIZE	D
DRAWN BY	
CHECKED BY	
DWG NO.	D5-514-001
REV	–
SCALE	3/4" = 1'0"
DATE	3/19/18
SHEET	2 OF 3



#	PART #	COMPONENT	MANUFACTURER	QTY	UNIT
1	5047610	GRILL,PLASTIC AC RETURN 12X14 #2217316018	MARINE AIR SYSTEMS INC	1	EA
2	5559290	GRILL,GLOBAL ROUND 3" BLACK #2071002	MARINE AIR SYSTEMS INC	1	EA
3	5562866	PLENUM,FOOT/AIR COND YS 2295018R3	MARINE AIR SYSTEMS INC	1	EA
4	5047864	GRILL,PLASTIC ADJ LVERS 10X4 #2217316057	MARINE AIR SYSTEMS INC	2	EA
5	5562350	PLENUM,DUCT 4" OVAL SIDE 10X4 #2290108	MARINE AIR SYSTEMS INC	1	EA
6	5562070	PLENUM,DUCT 5" OVAL SIDE 10X4 #2290101209	MARINE AIR SYSTEMS INC	1	EA
7	3285270	DUCT,FLEX 3" #2266600087 (25'/BOX)	MARINE AIR SYSTEMS INC	12	LFT
8	3285300	DUCT,FLEX 4" W/INSUL #2266600078 (25'/BX)	MARINE AIR SYSTEMS INC	3	LFT
9	3285290	DUCT,FLEX 5" W/INSUL #2266600079 (25'/BX)	MARINE AIR SYSTEMS INC	20	LFT
10	5559592	UNIT,AC DTU16F36J 230V/1PH/60HZ #E2066247	MARINE AIR SYSTEMS INC	1	EA
11	3345630	THRUHULL,RESIN W/SS CAP 5/8" STRAIGHT	MARINE AIR SYSTEMS INC	1	EA
12	3345660	THRUHULL,RESIN W/SS CAP 3/4" STRAIGHT	MARINE AIR SYSTEMS INC	1	EA



7-A TABLE - RAW WATER SYSTEM COMPONENTS

SCALE: NA

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	3345370	SCUPP,PICKUP, LOW PROF #THMR 0.750-3-HSVP	HARDWARE, INC.	1	EA
2	3826780	VALVE,BALL, BRASS/SS 3/4" BVLV0750-FPHL	MARINE HARDWARE, INC.	1	EA
3	3828970	ADAPTER,BRONZE STRAIGHT 3/4" #P1H-750	MECHANICAL LABORATORIES	1	EA
4	3829440	SWTV,VEL,WINGNUT EL 1/2"EXTRUDED #1414-5946	SHURFLO LLC	1	EA
5	3451930	STRAINER,WATER,INLINE SNAP-IN #254-066	SHURFLO LLC	1	EA
6	3432301	PUMP,WATER PRD BLASTER II DELUXE 4.0	SHURFLO LLC	1	EA
7	3331140	ELBOW,SWVEL FEM, 1/2"CTSXNPS #3586-1008	SEA TECH, INC.	4	EA

5-C PLAN VIEW - RAW WATER SCHEMATIC

SCALE: 3/4"=1'-0"

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
8	3332010	TEE,STACKABLE 1/2"DTS #3533-10	SEA TECH, INC.	1	EA
9	3331170	ELBOW,STACKABLE 1/2"CTSXSTEM #3518-10	SEA TECH, INC.	1	EA
10	3332515	HOSE,1/2" WHITE, STEMXSTEM 28' #UB1596168	SEA TECH, INC.	2	EA
11	3331110	1/2"CONNECTOR,FEM-1008	SEA TECH, INC.	2	EA
12	3596590	SPEED TAP WHITE W/ WHITE LID #ST300	SEA TECH, INC.	2	EA
-	3280050	HOSE,WATER HARDWALL 3/4"ID 50FT/RL	MPI PRODUCTS INC.	4	LFT

ISSUED FOR PRODUCTION

REV	ZONE	DESCRIPTION	DATE	APPRV'D
REVISIONS				

#	ZONE	DESCRIPTION	DATE
REFERENCES			

#	ZONE	DESCRIPTION	DATE	APPRV'D
RESERVATIONS				

PURSUIT BOATS ©2018

CONFIDENTIAL PRODUCT DEVELOPMENT DATA

C:\Users\Product Development\Desktop\DC 365\D5-523-001 Raw Water Washdown Schematic_170717.dwg

PURSUIT BOATS

MODEL D5 — DC 355 DUAL CONSOLE

DESCRIPTION

RAW WATER WASHDOWN SCHEMATIC


SCALE: 3/4" = 1'0"

DWG NO. D5-523-001

REV

DATE: 3/13/18


SHEET 1 OF 1



#	PART #	COMPONENT	MANUFACTURER	QTY	UNIT
1	5364750	HEAD,VACU-FLUSH MODEL 506, WHITE	SEALAND TECHNOLOGY INC	1	EA
2	3307681	PANEL,HEAD MACERATOR - REV A	PACER MARINE	1	EA
3	5364760	KIT,VACUUM GENERATOR #VG4-12VS	SEALAND TECHNOLOGY, INC.	1	EA
4	5369875	TANK, HOLDING 24 GAL. W/ REMOTE VENT 15	SEALAND TECHNOLOGY, INC	1	EA
5	3451840	PUMP, MACERATOR 12V MODEL 3200-003	PENTAIR FLOW TECHNOLOGIES, LLC	1	EA
6	3200840	THRUHULL,3/4" BRASS W/NUT #THMK-750-B	MARINE HARDWARE INC.	1	EA
7	3226780	VALVE,BALL,BRASS 3/4" BALVLV-750-FPBL	MARINE HARDWARE INC.	1	EA
8	3331740	ADAPTER,ELBOW BRZ FULL-FLOW 3/4"	GROSS MECHANICAL LABORATORIES	1	EA
9	3344771	FILL,DECK 1-1/2" WASTE CONNECTION	WHITECAP INDUSTRIES	1	EA
10	3344211	VENT,FLUSH TANK 90 DEG. 5/8"+B BOTH CUPS	MARINE HARDWARE INC.	1	EA
11	3285640	HOSE,SANITATION 1-1/2" HVY DTY SOFT/RL	MPI PRODUCTS INC.	9	LFT
12	3285630	HOSE,SANITATION 1" HEAVY DUTY SOFT/RL	MPI PRODUCTS INC.	9	LFT
13	3285500	HOSE,VENT 5/8" NMMA/CE TYPE A1 250FT/RL	TRIDENT RUBBER INC.	20	LFT

REV	ZONE	DESCRIPTION	DATE	APPRV'D
		REVISIONS		

#	ZONE	DESCRIPTION	DATE	APPRV'D
		RESERVATIONS		



GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE COMPLETED GRAY WATER SYSTEM. FULLY REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURES OF COMPONENTS.

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	3344130	DRAIN, 1.5" NPT LOW PROFILE W/ S/S COVER	GEM PRODUCTS INC	4	EA
2	3344131	ADAPTER, 1.5" NPT TO 2" HOSE BARB	GEM PRODUCTS INC	4	EA
3	3346980	THRUHULL,BRZ 2" #3773PLUS05CHR	PERKO INC	5	EA
4	3229290	VALVE,BALL BRONZE 2"NPT #BVLV-2.000-FPHL	MARINE HARDWARE INC	5	EA
5	3331970	ADAPTER,2"FPT X 2"HB #PTHAS-2.00X2.00	HARDWARE INC	5	EA
6	3342510	DRAIN,SINK W/BASKET 1"ELBOV SW-4 #907017	FORESPAR PRODUCTS CORP	1	EA
7	3346220	SCUPPER,THRUHULL ADJUSTABLE #FTG343	PERKO INC	2	EA
8	3344180	THRUHULL,BRZ 1-1/8" X 3/4"HB FLT HD #THB892	T-H MARINE SUPPLIES INC	3	EA
9	3343540	THRUHULL,PLASTIC 1-1/8" ELBOV #THB892	T-H MARINE SUPPLIES INC	2	EA
10	3220011	DRAIN, FLUSH COCKPIT BARB #10307 HOSE	SCANDVIK INC	1	EA
11	3344160	DRAIN, FLUSH COCKPIT ELBOV 2" X 100 DEG.	MARINE EAST INC	2	EA

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
12	3226015	TEE, 2" HB X HB X HB-PVC	ACR INDUSTRIES	1	EA
13	3220005	ADAPTER,CDUPLING 3/4" HOSE BARB X 3/4"HB	ACR INDUSTRIES	1	EA
14	3225740	TEE, 3/4"HB X 3/4"HB X 3/4"HB PVC #1401-010	ACR INDUSTRIES	3	EA
15	3346230	THRUHULL,BRZ 3/4"CHR #THB750-C	MARINE HARDWARE INC	1	EA
16	3226780	VALVE,BALL BRONZE 3/4" BVLVD,750-FPHL	HARDWARE INC	1	EA
17	3229000	ADAPTER,STRT BRZ FULL-FLOV 3/4" #FF-750	MECHANICAL GRATS LABORATORIES	1	EA
18	3345370	SCOOP,PICKUP LOV PROF	MARINE HARDWARE INC	1	EA
19	3345461	THRUHULL,RESIN W/SS CAP 1-1/8" 90DEG	PREMIER PRODUCTS LTD	1	EA
20	3220004	3/4"HB#1401-002	ACR INDUSTRIES	1	EA

7-A TABLE - GRAY WATER SYSTEM COMPONENTS

SCALE: NA

5C PLAN VIEW - GRAY WATER SYSTEM SCHEMATIC

SCALE: 1"= 1'-0"

ISSUED FOR PRODUCTION

REV	ZONE	DESCRIPTION	DATE	APPRV'D
		REVISIONS		


#	ZONE	DESCRIPTION	DATE	APPRV'D
		REFERENCES		


#	ZONE	DESCRIPTION	DATE	APPRV'D
		RESERVATIONS		

PURSUIT BOATS

MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION GRAY WATER SYSTEM SCHEMATIC
DRAWN BY: D. DEPENDER
CHECKED BY:
SCALE: 1" = 1'-0"
DWG NO. D5-529-001
DATE: 3/15/18
SHEET 1 OF 3
REV –

PURSUIT BOATS ©2018
OWNER PRODUCT DEVELOPMENT\05 DOT\16-F Prototype Design\A-1 Master Drawing Package - AUXILIARY SYSTEMS\05-529-001.dwg | Layout: Gray Water & Graywater Schematic | 7/10/17 | Jerry


ISSUED FOR PRODUCTION
13-C PLAN VIEW - GRAY WATER SYSTEM SCHEMATIC
SCALE: 1"=1'0"
15-C TABLE - GRAY WATER SYSTEM COMPONENTS
SCALE: N/A
PART # COMPONENT MANUFACTURER QTY UNIT
1 3283555 HOSE, 2" ID CORR BILGE SERIES #141 MPT PRODUCTS INC. 27 LFT
2 3283580 HOSE-1"ID 1/4" PVC LIVEWELL 100FT/RL MPT PRODUCTS INC. 8 LFT
3 3283560 HOSE-3/4"ID HD PVC LIVEWELL 100FT/RL MPT PRODUCTS INC. 8 LFT
MODEL D5 - 365 DUAL CONSOLE
DESCRIPTION
GRAY WATER SYSTEM SCHEMATIC
DWG NO. D5-529-001
REV -
SIZE D
SCALE 1" = 1'0"
DATE 3/15/18
SHEET 2 OF 3
PURSUIT BOATS ©2016



21-C PLAN VIEW - GRAY WATER SYSTEM SCHEMATIC

SCALE 3/4" = 1'-0"

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	3345711	THRUHULL,RESIN W/SS CAP 1-1/2"	PREMIER PRODUCTS, LTD.	2	EA
2	3345270	SUMP,SHOWER SYSTEM W/LID #998A-M	ITT JABSCO	1	EA
3	3345450	THRUHULL,RESIN W/SS CAP 1-1/2" 90DEG	PREMIER PRODUCTS, LTD	1	EA
4	3345567	DRAIN,SINK,FLIP-TOP 1-1/2" w/MOUNT RING ADAPTER,STR #103385	THE PRODUCT'S SUPPLY	1	EA
5	3332610	1-1/4"FPT,BRASS (2PCS)	SCANDVIK INC	1	EA
6	3452220	PUMP,DISCHARGE SERIES 1,#3600/3200	SEALAND TECHNOLOGY, INC.	1	EA
7	3332600	HOSE,ADAPTER,FLEX THRE,AD #3856-401270	SEALAND TECHNOLOGY, INC.	2	EA
8	3223080	ELL,90,1-1/2FP X 1-1/2HB,PLSTC	MARINE EAST INC.	2	EA
9	3344430	THRUHULL,FLEX FLANGE 1-1/2" STRAIGHT	T-H MARINE SUPPLIES INC.	2	EA

#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
21	3283590	HOSE,1-1/2" ID HD PVC LIVEWELL 100FT/RL #1	MPT PRODUCTS INC	19	LFT
22	3283560	HOSE,1-1/2" ID HD PVC LIVEWELL 100FT/RL #2	MPT PRODUCTS INC	13	LFT
23	3283580	HOSE,1ID HD PVC LIVEWELL 100FT/RL BALLAST W/BARB 5/8" #6216V	MPT PRODUCTS INC	3	LFT
24	3227620		MARINE EAST INC	3	EA


#	PART #	COMPONENT	MANUFACTUER	QTY	UNIT
1	3345440	THRUHULL,PLSTC,1-1/2" ELBOW 4"H1592	SUPPLIES INC.	1	EA
2	3229820	ADAPTER,PLAS 1-1/2"MPT X 1-1/2"HB #A112	ACR INDUSTRIES	1	EA
3	3223370	ELBOW,90°,PVC,1-1/2FS X TEE,1-1/2FS X FP X FS,PVC	ACR INDUSTRIES	1	EA
4	3223390	ADAPTER,PVC,STR 1.5HB,2.5"OD,#3018	ACR INDUSTRIES	2	EA
5	3223730	TEE,PVC 1-1/2FPT MP 3 SIDES #405-015	ACR INDUSTRIES	1	EA
6	3225030	ADAPTER,BUSHING 1-1/2MP X 1-1/4FP,PVC	ACR INDUSTRIES	1	EA
7	3225090	ADAPTER,STRAIGHT 1-1/4MPT X 1-1/4HB #8941	MARINE EAST INC.	1	EA
8	3227960	1-1/2"MPTX3/4"HB #8941	MARINE EAST INC.	1	EA
9	3227980	ADAPTER,STRAIGHT 1-1/2"MPTX1-1/4"HB #8943	MARINE EAST INC.	1	EA
10	3229590	PLUG,PVC,1-1/2"MPT #450-015	ACR INDUSTRIES	1	EA
11	3332100	VAL,VE,CHECK DUCKBILL 1"MPT #74-1M-DB	THE BOSWORTH CO.	1	EA


22-A TABLE - GRAY WATER SYSTEM COMPONENTS


SCALE:NA


ISSUED FOR PRODUCTION

MODEL: D5 - 365 DUAL CONSOLE					
DESCRIPTION: GRAY WATER SYSTEM SCHEMATIC					
SIZE: D	DRAWN BY:	DWG NO: D5-529-001		REV: -	
SCALE: 3/4" = 1'0"	APPROVED BY:	DATE: 3/15/18	SHEET: 3 OF 3		


ISSUED FOR PRODUCTION
PLAN VIEW - BILGE SYSTEM
SCALE: 3/4"= 1'-0"
5-C
TABLE - BILGE SYSTEM
SCALE: N/A
7-A
AUTO FLOAT SWITCH
HIGH WATER ALARM
12'
13.5'
14'
PART # COMPONENT MANUFACTURE QTY UNIT
1 3450710 PUMP,BILGE 1500 GPH 12V #62EM ITT JABSCO 2 EA
2 3450715 PUMP,BILGE 900 GPH 12V W/2" SWITCH ITT JABSCO 2 EA
3 3452130 SWITCH,FLOAT WATER WITCH #101-1 WATER WITCH, INC. 2 EA
4 3345461 THRUHULL,RESIN W/SS CAP PREMIER PRODUCTS LTD. 3 EA
5 3283610 HOSE,1-1/8" ID RED PVC LIVEWELL 100/RL MPI PRODUCTS INC. 52 LFT
REFERENCES
RESERVATIONS
REV ZONE DESCRIPTION DATE APPRV'D
REVISIONS
MODEL D5 - DC 365 DUAL CONSOLE
DESCRIPTION
HULL LIMBERING & BILGE SYSTEM SCHEMATIC
DRAWN BY:
APPROVED BY:
SIZE D
DWG NO. D5-529-002
REV 1
SCALE: 3/4" = 1'0"
DATE: 3/13/18
SHEET: 1 OF 2
PURSUIT BOATS ©2018
C:\NEW PRODUCT DEVELOPMENT\D5 (2017)\4.0 Prototype Design\4.1 Master Drawing Files\500 - AUXILIARY SYSTEMS\500-529-002_Rev1\[Hull Limbering & Bilge System Schematic_170711.dwg


1" PVC LIMBER
DRAINS
2 PER BOAT
1-3/8" WEEP HOLES
TYP. 7 LOCATIONS
ISSUED FOR PRODUCTION
13-C
PLAN VIEW - HULL LIMBERING
SCALE: 3/4" = 1'-0"
15-A
LEGEND - HULL LIMBERING
SCALE: N/A
FIBERGLASS HAT SECTIONS
6 PER BOAT
MODEL: D5 - DC-365 DUAL CONSOLE
DESCRIPTION
HULL LIMBERING &
BILGE SYSTEM SCHEMATIC
DWG NO. D5-529-002
REV
SIZE D
SCALE: 3/4" = 1'-0"
DATE: 3/13/18
SHEET: 2 OF 2


GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE FRESH WATER SYSTEM ONLY. REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURE OF COMPONENTS.
VESSEL ℄
ISSUED FOR PRODUCTION
5-C PLAN VIEW - FILL SCHEMATIC
SCALE: 3/4" = 1'-0"
7-A TABLE - FILL SCHEMATIC
SCALE: N/A
PART # COMPONENT MANUFACTURE QTY UNIT
1 3344761 FILL,DECK 1-1/2" WATER COUPLED WHITECAP INDUSTRIES 1 EA
2 3220930 ELBOW,90 DEG,1/2"MP X 1-1/2"HB,PLSTC ACR INDUSTRIES 1 EA
3 3195055 TANK, FRESH WATER 45 GAL D5 MOELLER MARINE PRODUCTS 1 EA
4 3223450 ELBOW,100 DEGREE 5/8" HOSE,PLASTIC MARINE EAST INC. 1 EA
5 3344211 VENT,FLUSH TANK,90 DEG. 5/8"HB BOTH CUPS MARINE HARDWARE INC. 1 EA
6 3346835 STRAP, HOLD DOWN WATER TANK D5 BAUSCH ENTERPRISES 2 EA
7 3283590 HOSE,1-1/2" ID HD PVC LIVEWELL WHT/RED MPT PRODUCTS INC. 12 LFT
8 3283570 HOSE,5/8"ID HD PVC LIVEWELL 100FT/RL MPT PRODUCTS INC. 9 LFT
- 5291590 GASKET, NEOPRENE 1/4"X2"X60' PAK-LITE INC. 10 LFT
REFERENCES
ZONE DESCRIPTION DATE
RESERVATIONS
ZONE DESCRIPTION DATE APPRV'D
REVISIONS
REV ZONE DESCRIPTION DATE APPRV'D
MODEL D5 - 365 Dual Console
DESCRIPTION FRESH WATER SYSTEM HULL SCHEMATIC
SIZE D
DRAWN BY:
APPROVED BY:
SCALE: 3/4" = 1'0"
DWG NO. D5-530-002
REV -
DATE: 2/27/18
SHEET 1 OF 3
PURSUIT BOATS ©2018



#	PART #	COMPONENT	MANUFACTURE	QTY	UNIT
1	3331150	ELBOW MALE 1/2"CTSXNPT #3519-1008	SEA TECH, INC.	1	EA
2	3332390	HOSE,PEX 1/2"CTS WHITE 250'/RL	SEA TECH, INC.	3	LFT
3	3331140	ELBOW,SWIVEL FEM. 1/2"CTSXNPS #3520-1008	SEA TECH, INC.	2	EA
4	3451862	PUMP, FRESHWATER PRESSURE,12VDC	ITT JABSCO	1	EA
5	3331110	CONNECTOR,FEMALE 1/2"CTSXNPS #3510-1008	SEA TECH, INC.	1	EA
6	3331390	HOSE,1/2" BLUE STEMXSTEM #3522-5-BLU	SEA TECH, INC.	1	EA
7	3332460	MANIFOLD,5 SECTION #3508-1610-1046 YG	SEA TECH, INC.	1	EA
8	5366240	HEATER,HOT WATER 6GAL,220V, #57585S3S-240	WHALE WATER SYSTEMS, LLC	1	EA
9	3827710	ADAPTER,STEM 1/2"BSP BRASS WHALE,WX1513B	WHALE WATER SYSTEMS, LLC	1	EA
10	3827520	ADAPTER,STEM 1/2"BSP BRASS WHALE,WX1534B	WHALE WATER SYSTEMS, LLC	1	EA
11	3332090	NIPPLE,BARB 1/2"NPT #38-2145	ACR INDUSTRIES	1	EA
12	3381290	HOSE,WAT CLRFORTBL 1/2" 250FT/RL	MFI PRODUCTS INC.	10	LFT
13	3345650	THRU-HULL,SS,PASS CAM 5/8" STRAIGHT	PERKO, LTD. PRODUCTS	1	EA
14	3331420	HOSE,1/2" RED STEMXSTEM 4' #UB0329S5-48	SEA TECH, INC.	1	EA
15	3331230	HOSE,1/2" BLUE STEMXSTEM 4' #UB0329S2-48	SEA TECH, INC.	1	EA

15-A TABLE - HOT WATER SCHEMATIC


SCALE: NA

12-C PLAN VIEW - HOT WATER SCHEMATIC

SCALE: 3/4" = 1'0"


ISSUED FOR PRODUCTION

MODEL	D5 – 365 DUAL CONSOLE
DESCRIPTION	FRESH WATER SYSTEM SCHEMATIC
SIZE	D
DRAWN BY	
APPROVED BY	
DWG. NO.	D5-530-001
REV	–
SCALE	3/4" = 1'0"
DATE	2/27/18
SHEET	12 OF 3



#	PART #	COMPONENT	MANUFACTURE	QTY	UNIT
1	3332680	HOSE,1/2" BLUE STEMSYSTEM 20'#U822525-240	SEA TECH INC	1	EA
2	3331460	HOSE,1/2" RED STEMSYSTEM 20'#U822525-240	SEA TECH INC	1	EA
3	3331120	CONNECTOR,MALE 1/2"CTSXNPT #3501-1008	SEA TECH INC	4	EA
4	5551620	FAUCET,FOLDING W/MIXING VALVE #10811	SCANDVIK INC	1	EA
5	3331380	HOSE,1/2" BLUE STEMSYSTEM 12'#U822525-168	SEA TECH INC	1	EA
6	3331140	ELBOW,SWIVEL FEM. 1/2"CTSXNPS #3520-1008	SEA TECH INC	1	EA
7	5338680	INLET,DOCKSIDE WATER CHROME #183-020-14	PENTAIR FLOW TECHNOLOGIES LLC	1	EA
8	5562711	MIXER,SHOWER CHROME #183-010-14	ITC INCORPORATED	1	EA
9	5562912	HOSE,SPRAYER NYLON WHITE #97014NH-B	ITC INCORPORATED	1	EA
10	5561041	SPRAYER,PUSH BUTTON ITC #97029-B	ITC INCORPORATED	1	EA
11	5561042	THRUHULL,SPRAYER PUSH BUTTON ITC #97029-T	ITC INCORPORATED	1	EA
12	3331110	CONNECTOR,FEMALE 1/2"CTSXNPT #3501-1008	SEA TECH INC	1	EA
13	3332500	HOSE,1/2" RED STEMSYSTEM 33'#U832525-396	SEA TECH INC	1	EA
14	3332520	HOSE,1/2" BLUE STEMSYSTEM 33'#U832525-396	SEA TECH INC	1	EA
15	3331150	ELBOW,MALE 1/2"CTSXNPT #3519-1008	SEA TECH INC	3	EA
16	5558620	MIXER,SHOWER FOR WAND SPRAYER #70105	SCANDVIK INC	1	
17	3331210	HOSE,1/2" BLUE STEMSYSTEM 1'#U822525-12	SEA TECH INC	1	
18	5558630	CONNECTOR,BULKHEAD ELBOW #10007	SCANDVIK INC	1	
19	5562060	SPRAYER,SHOWER W/SS HOSE YS/ DS #70112	SCANDVIK INC	1	EA
20	3332710	HOSE,1/2" RED STEMSYSTEM 12'#U832525-144	SEA TECH INC	1	EA
21	3331280	HOSE,1/2" BLUE STEMSYSTEM 14'#U822525-168	SEA TECH INC	1	EA
22	5369690	SPEED TAP,WHITE W/ WHITE LID #ST300	SEA TECH INC	1	EA
23	3332690	HOSE,1/2" BLUE STEMSYSTEM 29'#U822525-348	SEA TECH INC	1	EA
24	3331270	HOSE,1/2" BLUE STEMSYSTEM 10'#U822525-120	SEA TECH INC	1	EA
25	5559130	FAUCET,HEAD VANITY H&C #70108	SCANDVIK INC	1	EA
26	3331230	HOSE,1/2" BLUE STEMSYSTEM 4'#U822525-48	SEA TECH INC	1	EA
27	3331420	HOSE,1/2" RED STEMSYSTEM 4'#U832525-48	SEA TECH INC	1	EA
28	3331190	HOSE,1/2" BLUE STEMSYSTEM 1'#U822525-12	SEA TECH INC	1	EA
29	3299950	SOLENOID,WINDSHIELD WASHER	SEA TECH INC	1	EA

GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE FIRE FIGHTING SYSTEM ONLY. REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURES OF COMPONENTS.



5-C PLAN VIEW - DECK & HULL FIRE FIGHTING EQUIPMENT
SCALE: 3/4" = 1'0"

#	PART #	COMPONENT	MANUFACTURE	QTY	UNIT
1	3358700	EXTINGUISHER,FIRE 175CF #CG2-175-227	FIREBOY/XINTEX SAFETY SYSTEMS	1	EA
2	3358302	EXTINGUISHER,FIRE 3.9LB 110 W/METAL NZL	LOGISTICS SUPPLY	3	EA
3	3451620	BLOWER,BILGE IN-LINE 12V 4" #7019	ITT JABSCO	1	LFT
4	5562880	VENT,LOUVERED SQUARE 5" 304SS #793	GEM PRODUCTS INC.	1	EA
5	3282100	HOSE,VENT PVC 4"BLK 4"#420-4000 (200FT)	MPI PRODUCTS INC.	4	LFT
-	3355160	SHUTDOWN,3 CIRCUIT 12V.#ES-3000-01-12VDC	FIREBOY/XINTEX SAFETY SYSTEMS	1	EA

7-A TABLE - DECK & HULL FIRE FIGHTING EQUIPMENT
SCALE: N/A

ISSUED FOR PRODUCTION

REV	ZONE	DESCRIPTION	DATE	APPRV'D
REVISIONS				

PURSUIT BOATS
PO BOX 1370, LUCIE BLVD.
FT. PIERCE, FLORIDA 34954
PH (772) 465-4000
FAX (772) 465-4277

MISC. THIS COPY AND ANY COPY THEREOF ARE PROPRIETARY AND CONFIDENTIAL AND THE PROPERTY OF PURSUIT BOATS. NO PART OF THIS PUBLICATION, IN WHOLE OR IN PART, MAY BE PHOTOCOPIED UNLESS APPROVED IN WRITING BY PB YACHTS, INC.

MODEL D5 – 365 DUAL CONSOLE
DESCRIPTION
FIRE FIGHTING SYSTEM
DECK&HULL FIRE FIGHTING EQUIPMENT


#	ZONE	DESCRIPTION	DATE
REFERENCES			


#	ZONE	DESCRIPTION	DATE	APPRV'D
RESERVATIONS				

SIZE: D | DRAWN BY: CF | APPROVED BY: CF | DWG NO. D5-555-001 | REV -
SCALE: 3/4" = 1'0" | DATE: 3/5/18 | SHEET: 1 OF 1

PURSUIT BOATS ©2018

O:\NEW PRODUCT DEVELOPMENT\D5 (2017)\4.0 Prototype Design\4.1 Master Drawing Files\500 - AUXILIARY SYSTEMS\D5-555-001_Rev(1)_Fire Fighting Schematic_170711.dwg


GENERAL NOTES:
1. DRAWING IS A REPRESENTATION OF THE SCHEMATIC OF THE STEERING SYSTEM ONLY. REFER TO APPLICABLE DOCUMENTATION (HARDWARE DRAWING, WORK INSTRUCTION, ETC.) FOR LOCATION AND INSTALLATION PROCEDURES OF COMPONENTS.
ISSUED FOR PRODUCTION
5-C PLAN VIEW - HELM MASTER SCHEMATIC
SCALE: 3/4" = 1'0"
7-A TABLE - HELM MASTER COMPONENTS
SCALE: N/A
PART # COMPONENT MANUFACTURER QTY UNIT
1 3215731 KIT,HELM MASTER, SET PNT - HM-H3MB YAMAHA MOTOR CORPORATION (ENGINE) 1 KIT
2 3215735 KIT,HELM MASTER - STEERING TRIPLE HM-S3A YAMAHA MOTOR CORPORATION (ENGINE) 1 KIT
3 3282931 HOSE,HYD SEASTAR PRO 5/16 ID 1000"/ROLL SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX 74 LFT
- 3282920 FITTING, SWAG #HP6010 SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX 16 EA
- 3282910 FITTING,BEND-RESTRICTERS #HP6012 SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX 12 EA
- 3173370 BEND RESTRICTOR,BULKHEAD #HP5016 SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX 4 EA
13'x2
12'x2
12'x2
ZONE DESCRIPTION DATE
REFERENCES
ZONE DESCRIPTION DATE APPRV'D
RESERVATIONS
REV ZONE DESCRIPTION DATE APPRV'D
REVISIONS
PURSUIT BOATS
MODEL D5 - 365 DUAL CONSOLE
DESCRIPTION
HYDRAULIC STEERING SYSTEM
SCHEMATIC - HELM MASTER
SIZE D
DRAWN BY
APPROVED BY
DWG NO D5-561-001 REV -
SCALE 3/4" = 1'0" DATE 3/13/18 SHEET 1 OF 2
PURSUIT BOATS ©2018
CMEN PRODUCT DEVELOPMENT\D5 (2017)\A-0 Prototype Designs\1 Master Drawings\Rev000 - AUXILIARY SYSTEMS\D5-561-A01_Rev-1_Steering System Schematic_180306.dwg



13-C PLAN VIEW - STEERING SYSTEM SCHEMATIC

SCALE: 3/4" = 1'-0"

#	PART #	COMPONENT	MANUFACTURER	QTY	UNIT
-	3173840	FITTING,TEE,STEERING BLK/YD W/#5330 (QPK)	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	2	EA
-	3288920	FITTING, SWAG W/#F6010	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	12	EA
-	3288910	FITTING,BEND-RESTRICTERS W/#F6012	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	14	EA
-	3173370	BEND RESTRICTOR,BULKHEAD W/#F5516	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	2	EA


14-A TABLE - STEERING SYSTEM COMPONENTS


SCALE: N/A


#	PART #	COMPONENT	MANUFACTURER	QTY	UNIT
1	3173781	HELM, SPPRT, TILT PLUS HYDRAULIC 2.4	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	1	EA
2	3173660	UNIT,POWER ASSIST #PA1200-2	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	1	EA
3	3173500	CYLINDER,STEERING TOURNAMENT II #HC6845	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	2	EA
4	3173510	KIT,TIEBAR TOURNAMENT II #HC6823	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	2	EA
5	3173520	KIT,HARDWARE TOURNAMENT II TRIPS #HC6806	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	1	EA
6	3282930	HOSE,HYD SEASTAR 1.11 5/16 ID 1000"/ROL	SEASTAR SOLUTIONS FORMERLY KNOWN AS TELEFLEX	53	LFT


ISSUED FOR PRODUCTION


MODEL	DS – 365 DUAL CONSOLE
DESCRIPTION	HYDRAULIC STEERING SYSTEM SCHEMATIC
SIZE	D
DRAWN BY	DWG. NO. D5-561-001 REV. -
APPROVED BY	
SCALE: 3/4" 1'0"	DATE: 3/13/18 SHEET: 2 OF 2



GENERAL NOTES:
1. ALL THRU HULL DIMENSIONS IN THE HORIZONTAL DIRECTION ARE MEASURED LONGITUDINALLY FROM THE KEEL PERPENDICULAR INTERSECTION. ALL THRU HULL DIMENSIONS IN THE VERTICAL DIRECTION ARE MEASURED PERPENDICULAR TO THE CHINE.
VESSEL ℄
ISSUED FOR PRODUCTION
REV | ZONE | DESCRIPTION | DATE | APPRV'D
REVISIONS
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION D5 - DC 355 HULL HARDWARE STATION MARKS
SIZE D
DWG NO D5-611-001
REV
SCALE 3/4" = 1'0"
DATE 3/19/18
SHEET 1 OF 6
| ZONE | DESCRIPTION | DATE
REFERENCES
| ZONE | DESCRIPTION | DATE | APPRV'D
RESERVATIONS
PURSUIT BOATS ©2018
CONFI PRODUCT DEVELOPMENT\D5 (2017)\4.0 Prototype Deck\pro.1 Master Drawing Files\600 - RIGGING & OUTFITTING\D5-611-001 Rev1_Hull Hardware_170711.dwg



1-3/8" ENTERTAINMENT CENTER SINK DRAIN
1-3/8" FRESH WATER VENT
7/8" WATER HEATER PRESSURE RELIEF
1-3/8" HEAD SINK DRAIN
2-3/8" DECK DRAIN
1-1/16" FWD STORAGE DRAIN
2-1/4" DRAIN MANIFOLD
1-3/8" BILGE PUMP OUTLET
1-3/8" BLACK WATER VENT
1-7/8" LIVEWELL DRAIN
2-3/8" DECK DRAIN
7/8" COCKPIT AC DISCHARGE (OPTION)
1-3/8" COCKPIT AC DRAIN PAN (OPTION)
13-C
PROFILE VIEW - STBD THRU HULLS
SCALE: 3/4" = 1'-0"
ISSUED FOR PRODUCTION
PURSUIT BOATS GROUP
MODEL D5 - DC 365 DUAL CONSOLE
DESCRIPTION
D5 HULL HARDWARE
STBD THRU HULL PENETRATIONS
SIZE D
DRAWN BY:
APPROVED BY:
DWG. NO. D5-611-001
REV -
SCALE 3/4" = 1'0"
DATE 3/19/18
SHEET 2 OF 6



2-1/4" FISHBOX DRAIN OUTLET
2" GENERATOR EXHAUST
1-3/8" DIESEL TANK VENT
2-3/8" DECK DRAIN
1-5/8" FUEL TANK VENT
1-3/8" BILGE PUMP OUTLET
20-C
PROFILE VIEW - PORT THRU HULLS
SCALE: 3/4" = 1'0"
ISSUED FOR PRODUCTION
MODEL D5 - DC 365 DUAL CONSOLE
DESCRIPTION
D5 HULL HARDWARE
PORT THRU HULL PENETRATIONS
D5-611-001
SCALE 3/4" = 1'0"
DATE 3/19/18
SHEET 3 OF 6



29-C
PLAN VIEW - BOTTOM THRU HULLS
SCALE: 1" = 1'0"
ISSUED FOR PRODUCTION
10-1/2"
13-3/4"
4"
35"
39"
46"
54-1/2"
38"
9"
6"
3"
5"
PURSUIT BOATS
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION
HULL HARDWARE
BOTTOM THRU HULLS
PAGE NO. D5-611-001
REV -
SIZE D
SCALE 1" = 1'0"
DATE 3/27/18
SHEET 4 OF 6



ISSUED FOR PRODUCTION
1-3/8" AC PICKUP
1-3/8" GENERATOR PICKUP
1-1/16" RAW WATER WASHDOWN
1-1/16" COOLER & GUTTER DRAIN
1-1/16" MACERATOR PUMP
1-3/8" GARBOARD DRAIN
1-1/16" LIVEWELL PICKUP
37-C
PLAN VIEW - BOTTOM THRU HULLS
SCALE: 1"= 1'-0"
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION
HULL HARDWARE
BOTTOM THRU HULLS
DWG NO. D-611-001
REV -
SIZE D
SCALE 1" = 1'-0"
DATE 3/27/18
SHEET 5 OF 6


PORT
STBD
66-1/2"
52"
59"
66"
2-1/2"
12"
12"
4-1/2"
124"
5-1/2"
10"
198"
4-1/2"
37-C
PLAN VIEW - BOTTOM THRU HULLS
SCALE: 1"=1'0"
ISSUED FOR PRODUCTION
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION HULL HARDWARE BOTTOM THRU HULLS
SIZE D
DRAWN BY:
APPROVED BY:
DWG NO. D5-611-001
REV –
DATE 3/26/18
SHEET 6 OF 6
SCALE 1" = 1'0"


ISSUED FOR PRODUCTION
COOLER DRAIN 1-3/8" HOLE
DECK DRAIN 2-3/8" HOLE
STORAGE DRAIN 2-3/8" HOLE
COOLER DRAIN 1-3/8" HOLE
GUTTER DRAIN 1-3/8" HOLE
DECK DRAIN 2-3/8" HOLE
DECK DRAIN 2-3/8" HOLE
5-C
PLAN VIEW - DECK HARDWARE
SCALE: 3/4" = 1'0"
REV ZONE DESCRIPTION DATE APPRV'D
REVISIONS
MODEL D5 - 365 DUAL CONSOLE
DESCRIPTION
DECK HARDWARE PENETRATIONS
DWG NO. D5-611-002
REV -
SIZE D
SCALE 3/4" = 1'0"
DATE 3/19/18
SHEET 1 OF 1
ZONE DESCRIPTION DATE APPRV'D
REFERENCES
ZONE DESCRIPTION DATE APPRV'D
RESERVATIONS
PURSUIT BOATS ©2018


GENERAL NOTES:
1. WHEN USING STRAPS, ENSURE VESSEL IS LIFTED WITH THE KEEL LEVEL.
2. STRAPS ARE RATED FOR LOAD PRIOR TO USE.
3. STRAPS SHOULD BE INSPECTED FOR WEAR AND/OR DAMAGE PRIOR TO USE.
4. VESSEL WEIGHT WILL VARY. EXACT LCG DEPENDS ON VESSEL LOADING CONDITION.
5. INCREASE OVERALL HEIGHT BY 5" FOR OUTRIGGERS AND 12" FOR RADAR.
FORWARD SLING LABEL LOCATION
AFT SLING LABEL LOCATION
APPROX. LCG LOCATION
Aft Sling
Fwd Sling
132 1/4"
56 9/16"
22 13/16"
315 5/16"
281 1/2"
ISSUED FOR PRODUCTION
5-C PROFILE VIEW - SLING LOCATIONS
SCALE: 3/4" = 1'-0"
REVISIONS
REV | ZONE | DESCRIPTION | DATE | APPRV'D
– | ALL | INITIAL ISSUE | 01/16/18 | CTR
REFERENCES
| ZONE | DESCRIPTION | DATE
RESERVATIONS
| ZONE | DESCRIPTION | DATE | APPRV'D
MODEL D5 – DC 365 DUAL CONSOLE
D5 TRANSPORTATION SLING LOCATIONS
DWG NO D5-854-001
REV –
SCALE: 3/4" = 1'-0"
DATE: 01/16/2018
SHEET 1 OF 3


ISSUED FOR PRODUCTION
PURSUIT BOATS
MODEL D5 – DC 365 DUAL CONSOLE
DESCRIPTION
D5 TRANSPORTATION TRAILER DRAWING
SIZE D
DWG NO. D5-854-001
REV -
SCALE 1/2" = 1' 0"
DATE 01/16/2018
SHEET 2 OF 3
VESSEL ℄
PLAN VIEW - D5 HULL
SCALE 1/2" = 1'-0"
13-D
PROFILE VIEW - D5 HULL
SCALE 1/2" = 1'-0"
13-B
35 15/16"
17 11/16"
11 3/16"
52 7/16"
57 5/8"
46 7/8"
387 3/8"
420 5/8"
454 15/16"
25 1/16"
5 1/8"
4 1/16"
33 1/4"


21-C
ELEVATION - D5 HULL
SCALE: 2" = 1'0"
60"
52 8/16"
24 1/4"
36"
21 1/16"
17 13/16"
11 3/16"
119 15/16"
11 7/8"
18 15/16"
15 1/16"
13 3/16"
ISSUED FOR PRODUCTION
PURSUIT
MODEL D5 - DC 365 DUAL CONSOLE
DESCRIPTION
D5 TRANSPORTATION TRAILER DRAWING
DWG NO D5-854-001
REV -
DATE 01/16/2018
SHEET 3 OF 3
SCALE 2" = 1' 0"

Operator Notes

Fresh Water System

The fresh water system must be disinfected before first use and yearly at the beginning of each season. A clean sanitized fresh water system will greatly reduce the risk of developing coliform bacteria or other disease-causing organisms (pathogens) and will help protect the health of everyone onboard.

⚠ WARNING

DISINFECT THE ENTIRE FRESH (POTABLE) WATER SYSTEM PRIOR TO USE AND YEARLY AT THE BEGINNING OF EACH SEASON. FAILURE TO DO SO CAN RESULT IN DEVELOPING COLIFORM BACTERIA OR OTHER DISEASE-CAUSING ORGANISMS (PATHOGENS) IN THE WATER SYSTEM. CONSUMPTION OF CONTAMINATED WATER COULD RESULT IN SEVERE PERSONAL INJURY OR DEATH.

Follow this procedure to disinfect the fresh water system, kill bacteria that may be present, and prepare the system for operation:

Note: The fresh water system may be filled with nontoxic potable water antifreeze. If antifreeze was not used, skip to step 7.

1. Turn both water heater valves to the normal operation position.

2. Open all faucets (hot & cold), setting single faucets to the warm position.

3. Switch ON the FRESH WATER PUMP breaker(s), located on the DC Distribution Panel. The pumps are self-priming.

4. When anti-freeze stops flowing out of the faucets, switch the pump breaker(s) OFF. Do not close faucets.

5. Fill the fresh water tank with clean, fresh water. The fill fitting for the water tank is on the deck amidships, labeled WATER. The tank should be filled until water runs out of the vent located on the hull side just below the fill.

6. Keeping all faucets open, switch the FRESH WATER PUMP breaker(s) ON and empty the water tank. When the water tank is empty turn the pump breaker(s) OFF.

7. Repeat steps 5 and 6 until all nontoxic potable water antifreeze is removed from the system.

8. Ensure the water system, including the water heater and pump(s), is drained completely.

9. Close all faucets.

⚠ CAUTION

Notify all persons aboard that the fresh water system is being sanitized. Do not allow anyone to drink from the fresh water system during the sanitizing process.

10. Prepare a chlorine sanitizing solution: in a container with 1 gallon of fresh water, mix 1/4 cup of Clorox® or Purex® regular unscented household bleach (5% sodium hypochlorite solution) for each 15 gallons of water tank capacity (**Table A-1**).

Table A-1: Tank capacity vs. cups of bleach

Water Tank Capacity	Cups of Bleach
15 Gal.	1/4 Cup
30 Gal.	1/2 Cup
45 Gal.	3/4 Cup
60 Gal.	1 Cup
75 Gal.	1-1/4 Cups
90 Gal.	1-1/2 Cups
105 Gal.	1-3/4 Cups
120 Gal.	2 Cups
135 Gal.	2-1/4 Cups
150 Gal.	2-1/2 Cups

11. Fill the fresh water tank halfway with clean, fresh water.

12. Pour the sanitizing solution into the water tank through the deck WATER fill fitting.

13. Fill the remainder of the tank with clean, fresh water. The tank should be filled until water runs out of the vent. (See step 5.)

14. Switch ON the FRESH WATER PUMP breaker(s).

15. At each faucet, run about 1/2 gallon of water out of each tap (hot and cold), then close the tap. You should be able to smell chlorine out of each tap.

16. Switch OFF the FRESH WATER PUMP breaker(s).

17. **Allow the chlorine sanitizing solution to sit in the system for three (3) hours.** A shorter time period will require a greater concentration of chlorine sanitizing solution to disinfect the water system.

18. Switch ON the FRESH WATER PUMP breaker(s).

19. Drain the chlorine sanitizing solution by opening all faucets (hot & cold), setting single faucets to the warm position, and empty the water tank. When the water tank is empty turn the pump breaker(s) OFF.

20. Ensure the water system, including the water heater and pump(s), is drained completely.

21. Fill the fresh water tank with clean, fresh water. The tank should be filled until water runs out of the vent. (See step 5.)

22. Keeping all faucets open, switch the FRESH WATER PUMP breaker(s) ON and empty the water tank. When the water tank is empty turn the pump breaker(s) OFF.

23. Repeat steps 21 and 22.

24. Final fill: Fill the fresh water tank with clean, fresh water. The tank should be filled until water runs out of the vent. (See step 5.)

25. Turn the FRESH WATER PUMP breaker(s) ON.

26. Open each faucet. When a smooth flow of water is observed from each hot and cold tap, close the faucet. When all faucets are closed, the pumps will shut off as the system pressure increases. Any air should now be purged from the system. Leave the FRESH WATER PUMP breaker(s) ON.

The fresh water system is now commissioned and ready for use.

To remove excessive chlorine taste or odor that might remain in the system, do the following:

1. Ensure the water tank has enough available capacity to accept 10 additional gallons. If there is ample room in the tank, proceed to step 3, below.

2. Drain at least 10 gallons of water out of the system so the following vinegar solution will have room to be added. To do this switch ON the FRESH WATER PUMP breaker(s) and open a faucet. When at least 10 gallons has been drained, close the faucet and turn the pump breaker(s) OFF.

3. Prepare a solution of one (1) quart vinegar to five (5) gallons fresh water.

4. Pour the vinegar solution into the water tank through the deck WATER fill fitting.

5. Repeat steps 3 and 4.

6. Allow the vinegar solution to agitate in the tank for 24 hours.

7. Switch ON the FRESH WATER PUMP breaker(s).

8. Drain the vinegar solution by opening all faucets (hot & cold), setting single faucets to the warm position, and empty the water tank. When the water tank is empty turn the pump breaker(s) OFF.

9. Close all faucets.

10. Fill the fresh water tank with clean, fresh water. The fill fitting for the water tank is on the deck amidships, labeled WATER. The tank should be filled until water runs out of the vent located on the hull side just below the fill.

11. Turn the FRESH WATER PUMP breaker(s) ON.

12. Open each faucet. When a smooth flow of water is observed from the hot and cold tap, close the faucet. When all faucets are closed, the pumps will shut off as the system pressure increases. Any air should now be purged from the system. Leave the FRESH WATER PUMP breaker(s) ON.

13. Repeat if necessary.

Acuatic Invasive Species

Aquatic invasive species (AIS) are plants and animals that occur in waters in which they are not native and whose introduction causes or is likely to cause economic or environmental damage or harm to human health. AIS have a negative impact on the waterway, its native species, and recreational and commercial uses of the waterway. As responsible boaters and citizens, each boat owner should do their part to prevent the spread of these aquatic hitchhikers. In many cases, it is also required by law. Check local regulations for any waterway where you will boat. After each boating trip, follow these three simple steps before you leave the water access to stop the spread of AIS: Clean, Drain, and Dry. This is the boater's way to help protect the environment from the damage that AIS can cause.



PATHWAYS OF AQUATIC INVASIVE SPECIES

We are living in a very different era where goods, people and services are being shipped around the world. Because of this globalized economy, different species are hitchhiking through many different pathways. Species can be moved to new locations in many ways, and most are a result of human activity, including recreational activities. Some common ways that species may be moved during recreational boating and other activities include:


- Attaching to watercraft, trailers, motor and fishing gear.
- Transport by water ballast water, bilge, and other water containing devices.
- Dumping of unwanted live bait.
- Tangled in fishing lines and downrigger cables
- Sticking to the soles of waders
- Trapped in mud on a dog's paws

Just one organism, or in some case a piece of a plant, is enough to start a new invasion.

GENERAL CLEAN DRAIN DRY PROCEDURE

Clean, Drain, Dry… In every waterbody, every time.

Preventing the spread of aquatic invasive species starts with you. A cooperative effort is necessary by all persons and agencies involved with recreational activities to achieve the best results and protect our aquatic resources and recreational opportunities. The general Clean Drain Dry procedure is described below:



CLEAN

Clean off visible aquatic plants, animals, and mud from all equipment before leaving water access. Inspect and clean motor or engine, including the lower unit and motor mounts; trailer, including axles, bunks, and rollers; anchors; dock lines; and equipment before leaving the water body.

- Rinse equipment and boat hulls (with high pressure, hot water when possible)
- Rinse interior compartments of boats with low pressure, hot water (120°F) for a minimum of 130 seconds contact time.
- Flush motor with hot water (120°F) for 2 minutes (or according to owner's manual)

DRAIN

Drain the motor, motor cooling system, bilge, live well, fish box, and other water containing devices before leaving water access.

DRY

Allow the boat to completely dry OR wipe with a towel before reuse, before visiting any other bodies of water. For ANGLERS, the additional step of DISPOSE is recommended.

DISPOSE

Dispose of unwanted bait, worms, and fish parts in the trash. When keeping live bait, drain bait container and replace with spring or dechlorinated tap water. Never dump live fish or other organisms from one water body into another. Together the three steps of Clean Drain Dry greatly minimizes the risk of spreading Aquatic Hitchhikers into new locations.

- Cleaning will remove visible large-bodied organisms attached to or in watercraft or recreational equipment. Rinsing with water removes organisms, while hot water often kills them. Water at least 120°F is recommended; be sure to avoid contact with skin and check manufacturers' recommendations to ensure equipment can withstand high temperatures. If hot water is not available or may cause damage, rinsing with tap water and completely drying will help prevent spread of aquatic invasive species.
- Draining removes small and nearly invisible organisms such as zebra mussel larvae (veligers) potentially entrained in water containing devices.
- Drying is necessary as many organisms can survive in standing water.

A note about chemicals. The use of chemical prophylactics or disinfectants (e.g., bleach) are not recommended for treating watercraft and recreational equipment. Chemicals may:

- Damage equipment or components
- Cause environmental damage
- Harm human health
- May not be effective against many aquatic invasive species

Report new sightings. If you think you have found an invasive species, note its exact location and, if possible, take a photo. Report new sightings to the appropriate authorities or use the USGS Sighting Report Form.

Know the rules! Specimens are needed to confirm sightings, but some jurisdictions prohibit possession and transport of invasive aquatic plants and animals. Before collecting specimens, contact your local natural resource management agency for instructions. Unauthorized introduction of plants, fish, or invertebrates into the wild is illegal in most states. Protect your property and our waters.

Remember that AIS Threaten the Environment, Recreation, Economy, and Human Health. Refer to the Stop Aquatic Hitchhikers! Website for more details (www.StopAquaticHitchhikers.org).

Operator Notes

